



FW: Winnebago GMZ App

Brad Hunsberger to: Bernard Schorle
Cc: Tom Hilbert

05/08/2012 02:23 PM

From: Brad Hunsberger <bhunsberger@andrews-eng.com>
To: Bernard Schorle/R5/USEPA/US@EPA
Cc: Tom Hilbert <thilbert@rresvcs.com>

1 attachment



GMZ Eval-2 (5-1-2012).pdf

Bernie,

Pursuant to my conversation with Tom Hilbert, the Five-Year Status Report and Evaluation of Groundwater Corrective Actions and Groundwater Management Zone for the Winnebago Landfill is attached in PDF. The subject report was submitted to the Illinois EPA on May 1. If you have any questions or comments, please contact Tom.

Thank you.

Brad J. Hunsberger, LPG
Director of Hydrogeological Services
Andrews Engineering, Inc.
3300 Ginger Creek Drive
Springfield, Illinois 62711

(217) 787-2334



ANDREWS
ENGINEERING, INC.

90-1142010/20

May 1, 2012

Stephen F. Nightingale
Manager, Permit Section
Bureau of Land
Illinois Environmental Protection Agency
1021 North Grand Ave. East
P.O. Box 19276
Springfield, IL 62794-9276

RECEIVED
MAY 01 2012
SECURITY DESK
4:30pm

Re: 2018080001 – Winnebago County
Winnebago Landfill – Northern Unit
Status Report and Evaluation of Groundwater Corrective
Actions and Groundwater Management Zone

Dear Mr. Nightingale:

On behalf of Winnebago Landfill, submitted herein are an original and three copies of a Status Report for the Groundwater Corrective Actions in accordance with Condition VIII.23 of Permit No. 1991-138-LF, Modification 53. Application forms (Certification of Authenticity and LPC-PA1) are provided in Appendix A of the application.

Please contact Tom Hilbert at (815) 963-7516 if you have any questions or require additional information.

Sincerely,

Joshua L. Rhoades, LPG
Hydrogeologist

JLR:jlr:sjb

Enclosure

cc: Tom Hilbert – Rock River Environmental Services
Evan Buskohl – Rock River Environmental Services
Bernie Shorle – US EPA Region 5

**Winnebago Landfill
Northern Unit
Winnebago County, Illinois**

**Permit Number: 1991-138-LF
Site Number: 2018080001**

Status Report and Evaluation of Groundwater Corrective Actions and Groundwater Management Zone

May 2012



Submitted to:
Illinois Environmental Protection Agency
Bureau of Land
Springfield, Illinois

Prepared for:
Winnebago Landfill
8403 Lindenwood Road
Rockford, Illinois



Prepared by:

**ANDREWS
ENGINEERING, INC.**

3300 Ginger Creek Drive
Springfield, Illinois 62711
Tel: (217) 787-2334; Fax: (217) 787-9495

TABLE OF CONTENTS

| | | |
|-----------|---|----|
| 1. | INTRODUCTION..... | 1 |
| 1.1 | Background Information and Previous Submittals..... | 1 |
| 2. | SITE HYDROGEOLOGICAL SUMMARY | 3 |
| 2.1 | Unconsolidated Deposits | 3 |
| 2.2 | Bedrock | 4 |
| 2.3 | Uppermost Aquifer..... | 4 |
| 2.4 | Groundwater Flow Conditions..... | 4 |
| 3. | GROUNDWATER MONITORING WELL NETWORK..... | 6 |
| 4. | GROUNDWATER CORRECTIVE ACTION..... | 6 |
| 4.1 | Groundwater Management Zone (GMZ) | 6 |
| 4.2 | Remedial Performance Monitoring..... | 9 |
| 5. | GROUNDWATER QUALITY | 9 |
| 5.1 | Background Groundwater Quality | 9 |
| 5.2 | Trend Analyses..... | 9 |
| 5.2.1 | Upper Zone..... | 10 |
| 5.2.1.1 | Parameter Specific Trends | 10 |
| 5.2.1.1.1 | GMZ Parameters..... | 10 |
| 5.2.1.1.2 | Non-GMZ Parameters | 20 |
| 5.2.2 | Lower Zone | 22 |
| 5.2.2.1 | Parameter Specific Trends | 23 |
| 5.2.2.1.1 | GMZ Parameters..... | 23 |
| 5.2.2.1.2 | Non-GMZ Parameters | 30 |
| 5.2.3 | Bedrock Zone..... | 31 |
| 5.2.3.1 | Parameter Specific Trends | 32 |
| 5.2.3.1.1 | GMZ Parameters..... | 32 |
| 5.2.3.1.2 | Non-GMZ Parameters | 35 |
| 6. | GMZ EVALUATION..... | 39 |
| 6.1 | Upper Zone..... | 39 |
| 6.2 | Lower Zone..... | 40 |
| 6.3 | Bedrock Zone | 41 |
| 7. | CONCLUSIONS AND RECOMMENDATIONS..... | 42 |

TABLES

Table 1 – Surface Water Exceedences
Table 2 – GMZ Wells and Parameters
Table 3 – Exceedence Summary Table
Table 4 – Analytical Results for GMZ Parameters (1997-2012)

FIGURES

Figure 1 – Site Map
Figure 2 – Geologic Cross Section
Figure 3 – 1995 Upper Zone GMZ Extent
Figure 4 – 1995 Lower Zone GMZ Extent
Figure 5 – 2004 Upper Zone GMZ Extent
Figure 6 – 2004 Lower Zone GMZ Extent
Figure 7 – 2004 GMZ Vertical Boundary Map
Figure 8 – 2007 GMZ Extent Map-Revised
Figure 9 – 2007 GMZ Vertical Boundary Map
Figure 10 – 2012 Upper Zone GMZ Extent
Figure 11 – 2012 Lower Zone GMZ Extent
Figure 12 – 2012 Vertical GMZ Boundary Map

APPENDICES

Appendix A – Application Forms
Appendix B – Quarterly Potentiometric Surface Maps
Appendix C – Acme Solvent Site Potentiometric Surface Maps
Appendix D – Upper Zone Trend Graphs
Appendix E – Lower Zone Trend Graphs
Appendix F – Bedrock Zone Trend Graphs
Appendix G – Upper Zone Concentration Exceedence Maps
Appendix H – Lower Zone Concentration Exceedence Maps

1. INTRODUCTION

Condition No. VIII.23 of Permit No. 1991-138-LF, Modification No. 53 requires an evaluation and report of the current status of the groundwater management zone (GMZ) based on existing corrective actions for the Northern Unit. The application forms (Certification of Authenticity and LPC-PA1) are contained in Appendix A. The subject condition, a result of approval of the permit renewal application dated December 2002 and identified as Illinois Environmental Protection Agency (Illinois EPA) Application Log No. 2002-373, states:

The operator shall provide status reports on the groundwater corrective actions, which shall identify the current state of the groundwater management zone (GMZ) via the remedial performance-monitoring program and evaluation of groundwater quality. The report shall include, at minimum, the current groundwater remediation activities, groundwater quality of all wells contained within the GMZ, trend analysis data in graphical and tabular formats for all GMZ parameters and wells, vertical and horizontal GMZ extent maps and cross sections, potentiometric maps, conclusions and recommendations of the GMZ. The report shall be submitted as a Significant Modification Application to the Permit no later than May 1, 2012, in accordance with the 1995 Record of Decision. Future evaluations of the groundwater corrective action will be submitted to the Illinois EPA as an Application for Significant Modification to the Permit on the same schedule as the submittal date for the "Five Year Review Report for Pagel's Pit Superfund Site", which is required by the USEPA.

As required by Condition No. VIII.23, this report includes a review of current groundwater remediation activities, groundwater quality of all groundwater monitoring wells contained within the GMZ, trend analysis data in graphical and tabular formats for all GMZ parameters and wells, vertical and horizontal GMZ extent maps, cross-sections, potentiometric surface maps, and recommendations for the GMZ if necessary.

The Northern Unit has a history of groundwater quality investigations due to the conditions of the Acme Solvent Superfund Site (Acme Solvent site) and elevated concentrations related to the waste unit. Results of previous groundwater quality investigations in addition to the remedial performance monitoring program were utilized to determine the current status of the corrective actions and GMZ (i.e., effectiveness of the remedial measures and extent of groundwater impacts adjacent to the Northern Unit). Although some data (i.e., groundwater elevations and analytical results) from the North Expansion Unit (NEU) and Southern Unit have been used to characterize the hydrogeology for the Northern Unit, the NEU and Southern Unit are not specifically discussed as part of this application as the GMZ and remedial activities are not applicable to these disposal areas.

1.1 Background Information and Previous Submittals

Winnebago Landfill, located approximately five miles south of Rockford, Illinois, consists of three separate disposal areas (NEU, Northern Unit, and Southern Unit) authorized under two different operating permits (Illinois EPA Permit No. 2006-221-LF for the NEU and 1991-138-LF for the Northern and Southern Units). The Northern Unit, previously known as Pagel's Pit and the subject of this application, is located between the existing Southern Unit and NEU. A site map delineating the disposal areas has been provided as Figure 1.

The Northern Unit was added to the National Priorities List in June 1986 due to upgradient groundwater contamination resulting from the Acme Solvent site. Based on perceived groundwater contamination adjacent to the Northern Unit (at the Acme Solvent site), the United States Environmental Protection Agency (U.S. EPA) issued a Record of Decision (ROD) in June 1991 requiring Remedial Design and Remedial Action plans. The ROD was incorporated in a Consent Decree entered in the United States District Court for the Northern District of Illinois, Western Division, Case No. 92-C-20346 on February 11, 1993. A ROD amendment was submitted to the U.S. EPA in 1997 for a new or revised Consent Decree to reflect a new Statement of Work (SOW) due to a change in the remedy. The subject ROD was issued in 1999 (signed on September 30, 1999) and acknowledged that the U.S. EPA's response at the site was complete thereby achieving construction completion. The Northern Unit currently exists with a GMZ and approved remediation program. The remediation program was submitted July 10, 1995 (Illinois EPA Application Log No. 1995-250) to facilitate compliance of the Northern Unit with the applicable requirements of 35 Illinois Administrative Code (Ill. Adm. Code) Part 811 and 812, pursuant to Sections 814.104, 814.301 and 814.302.

Previous groundwater quality evaluations to determine the effectiveness of the remedial measures were submitted by HSI GeoTrans in 1998 and 1999 in accordance with the schedule provided in Illinois EPA Application Log No. 1996-403. The annual progress reports, which included an assessment of groundwater quality, were based on the remedial performance groundwater monitoring plan (HSI GeoTrans, 1997) and conducted in accordance with the Performance Assessment Criteria (PAC) provided in the May 8, 1997 addendum to the Illinois EPA application dated January 14, 1997. The PAC includes evaluation of concentration trends at wells near the landfill and at the boundary of the dissolved plumes. This entails a statistical trend analysis for each subject parameter to determine movement of the plumes. The August 1999 report (HSI GeoTrans) concluded that a small number of inorganic parameters were still present beneath and downgradient to the Northern Unit. Organic concentrations were very low, near, or below the applicable groundwater quality standards (AGQSS) throughout the GMZ. At the time of the 1999 report, remediation measures were still being implemented. Therefore, it was recommended that quarterly sampling and analysis continue for the 33 wells and 3 stream monitoring points in the remedial performance groundwater monitoring plan.

The Pagel's Pit Superfund Site First Five-Year Review Report, prepared by U.S. EPA pursuant to the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) §121 and the National Contingency Plan (NCP) (40 Code of Federal Regulations (CFR) Part 300), was completed in September 2002. The impetus for the statutory review was the reported initiation of the remedial action on August 8, 1997; the date for the formal acceptance of the design for the closure of part of the landfill. The assessment determined that the remedy was constructed in accordance with the two RODs and functioning as anticipated. However, the conclusion of the first five-year report was that the remedy at the site was not protective in the long-term because the additional institutional controls specified by the second ROD had not yet been implemented at the time of review.

The initial Status Report for the groundwater corrective action and evaluation of the GMZ was submitted July 2004 by Andrews Engineering as Illinois EPA Application Log No. 2004-257. The subject application, submitted pursuant to Condition No. VIII.22 of Permit No. 1991-138-LF Modification No. 24, was the result of approval of the permit renewal application dated December 2002 and identified as Illinois EPA Application Log No. 2002-373. The GMZ evaluation was approved September 28, 2005 with the issuance of Permit Modification No. 28. The application concluded that although a few parameters were still showing increasing trends,

improvements to the groundwater quality were evident as demonstrated by a decrease in the overall GMZ extents. Furthermore, the organic constituents that prompted the remedial actions were typically not detected in downgradient groundwater monitoring wells.

The Pagel's Pit Superfund Site Second Five-Year Review Report, prepared by U.S. EPA, was completed in August 2007 in accordance with the signing of the first five-year review on September 27, 2002. The assessment determined that the remedy was constructed in accordance with the two RODs and the ROD amendment that was part of the second ROD.

A Status Report for the groundwater corrective action and evaluation of the GMZ was submitted May 1, 2007 by Andrews Engineering as Illinois EPA Application Log No. 2007-181. The subject application, submitted pursuant to Condition No. VIII.22 of Permit No. 1991-138-LF Modification No. 33, was approved October 31, 2008 with the issuance of Permit Modification No. 37. The application concluded that significant improvements to the groundwater quality were evidenced by decreases in individual parameter concentrations and corrective measures had been successful in source reduction as evidenced by the decreased GMZ extents (compared to the 2004 GMZ evaluation). In accordance with the September 29, 2008 addendum of Illinois EPA Application Log No. 2007-181 (2007 Status Report), a GMZ Investigation Report addressing Condition VIII.23 of Modification No. 37 was submitted May 1, 2009. The GMZ investigation identified as Illinois EPA Application Log No. 2009-221 and approved July 29, 2009 with the issuance of Permit Modification No. 40, included advancement of borings in four locations along the western edge of the GMZ within the floodplain of Kilbuck Creek. Although the results of the GMZ investigation were that groundwater quality to the west of the GMZ did not appear to be affected by the Northern Unit, issues with the turbidity of the groundwater and sampling methodology warranted additional investigation. The additional GMZ investigation, identified as Illinois EPA Application Log No. 2010-038, was submitted January 29, 2010 addressing Condition VIII.23 of Modification No. 40. The additional GMZ investigation was approved September 22, 2011 with the issuance of Permit Modification No. 50. Based on the results of both GMZ investigations, groundwater quality to the west of the GMZ did not appear affected by the Northern Unit. Concentrations of all organic and inorganic GMZ parameters were non-detect or below the AGQS with the exception of dissolved ammonia at T2U-A, T2L-A, and T3U-A. The dissolved ammonia concentrations were determined to be affected by background conditions and spatial variability associated with the agricultural land use of the area.

2. SITE HYDROGEOLOGICAL SUMMARY

2.1 Unconsolidated Deposits

The composition of the unconsolidated deposits, which appear to be glacial outwash, varies with location throughout the boundaries of Winnebago Landfill. Coarse-grained sand and gravel with occasional silt and/or clay seams typically underlie the site. The thickness of the sand and gravel varies from just a few feet along the eastern side of the facility to approximately 70 feet beneath the western edge. The sand and gravel, which thickens to the west corresponding with the erosion of the dolomite bedrock, directly underlies the western portion of the Northern Unit while fractured dolomite underlies the eastern portion. A geologic cross-section illustrating the subsurface geology is provided as Figure 2.

2.2 Bedrock

The bedrock consists of dolomite, fractured and weathered, to varying extents. Chert layers, chert nodules, and small vugs were commonly noted on facility boring logs. However, larger voids or karst characteristics were not indicated on the boring logs. The bedrock surface is highly variable throughout the facility. East of Winnebago Landfill a dolomite bedrock upland is present and outcrops in the vicinity of the Acme Solvent site and two quarries. This bedrock upland represents the eastern bedrock escarpment of the Upper Rock buried valley; Winnebago Landfill is situated on the eastern edge of the Upper Rock buried bedrock valley. The overburden thickens as the elevation of the bedrock surface decreases to the west. As determined by previous boring investigations, the bedrock continues to decrease in elevation west of Winnebago Landfill to approximately 645 feet above mean sea level (MSL) directly west of Kilbuck Creek (HSI GeoTrans, May 1997). A geologic cross-section illustrating the subsurface geology is provided as Figure 2.

2.3 Uppermost Aquifer

The uppermost aquifer for Winnebago Landfill is located within the glaciofluvial sand and gravel deposits and the upper portion of the fractured dolomite bedrock. The saturated sands and gravels, which directly overlie the bedrock, occur over the western two-thirds of the Northern Unit. In locations where there are no saturated glaciofluvial deposits, the uppermost aquifer is located within the dolomite bedrock; this occurs in the eastern one-third of the Northern Unit.

2.4 Groundwater Flow Conditions

The general flow direction within the uppermost aquifer is to the west-northwest and downward in the bedrock upland located to the east as shown by quarterly potentiometric surface maps provided in Appendix B. The vertical gradient for flow, although typically slight at any individual location, is generally upward from the bedrock to the unconsolidated sediments in areas where sediments are saturated (HSI GeoTrans, 1995 report for the Northern Unit at Winnebago Landfill). Therefore, groundwater elevations from the bedrock wells and wells screened in the unconsolidated materials (sand and gravel) were used to create one potentiometric surface for each quarterly sampling period. The existence of a slight vertical gradient within the uppermost aquifer is due to the higher elevations of the recharge areas to the east and greater permeability of the sand and gravel deposits overlying the bedrock.

The Northern Unit GMZ is located in the vicinity of Kilbuck Creek; typically a gaining stream that receives recharge from shallow groundwater but may be a losing stream during drier periods where the water table drops below the creek. This seasonal fluctuation allows mixing of surface water with shallow groundwater, often on a seasonal and precipitation event-specific basis. A geologic cross-section is provided as Figure 2 illustrating the direct hydraulic connection between the surface water (Kilbuck Creek and the wetland mitigation area) and the underlying sand and gravel deposits. Surface water samples from Kilbuck Creek are collected from three locations on a quarterly basis and analyzed for all the GMZ list parameters. However, during first quarter 2012, water samples were unable to be obtained from locations SG1 and SG4 due to frozen conditions. Table 1 lists the creek sample results for the review period.

Construction dewatering operations at the NEU, initiated in order to construct the invert of the NEU and negate any hydraulic uplift forces during construction and initial filling of the unit, commenced fourth quarter 2007. In areas where the landfill liner was and is being constructed, the potentiometric surface elevation has been lowered using vertical extraction wells and below-

grade dewatering sumps around the perimeter of the construction area. The dewatering wells are decommissioned after sufficient waste has been placed to balance the buoyant force of the water, and additional wells are added as landfill development progresses. Construction dewatering operations at the NEU prompted the submittal of a Groundwater Investigation of Construction Dewatering (Illinois EPA Application Log No. 2011-197) approved November 2, 2011 by Modification No. 15 to Permit No. 2006-221-LF. The Groundwater Investigation of Construction Dewatering was prepared to address Condition No. VIII.24 of Permit No. 2006-221-LF in order to determine what effects the construction dewatering activities may have had on the groundwater flow direction with respect to groundwater in the vicinity of the NEU, specifically at the location of Northern Unit Compliance Boundary Wells G52M, G52S, and Temporary GMZ Assessment Wells T1U-A, T2U-A, T3U-A, T1L-A, T2L-A, and T3L-A. It should be noted that Temporary GMZ Assessment Wells T1U-A and T1L-A, installed to investigate the area west of the permitted Northern Unit GMZ pursuant to Condition No. VIII.23 of Permit No. 1991-138-LF Modification No. 41, were renamed G54S and G54M, respectively, in accordance with Modification No. 50 to Permit No. 1991-138-LF. It should be further noted that Condition VIII.9.A of Modification No. 50 to Permit No. 1991-138-LF removed the Temporary GMZ Assessment Well listing.

The Groundwater Investigation of Construction Dewatering included data from a comprehensive hydrogeologic investigation that was conducted west and northwest of the Southern and Northern Units as part of the facility expansion (Illinois EPA Application Log Nos. 2006-221 and 2010-221). A series of piezometers were installed in the area identified as the Western Expansion Unit. This area is located south of Northern Unit Compliance Boundary wells G52S, G52M, G54S, G54M and Temporary GMZ Assessment Wells T2U-A, T2L-A, T3U-A, and T3L-A. Additionally, groundwater elevation data from wells in the vicinity of the Acme Solvent site were used in the compilation of potentiometric contours. The potentiometric surface information from the Western Expansion Unit piezometers and wells in the vicinity of the Acme Solvent site included data from April 2004, March 2005, and April 2006.

The potentiometric surface maps from third quarter 2007 to first quarter 2011 were provided in Illinois EPA Application Log No. 2011-197 and have been included in Appendix B of this report. Potentiometric surface maps for first and second quarter 2007 as well as second quarter 2011 to fourth quarter 2011 have also been provided. The potentiometric surface maps illustrate a temporary cone of depression (inward radial flow) created by construction dewatering. Although the potentiometric surface maps indicate dewatering activities have changed the groundwater flow characteristics for downgradient NEU monitoring wells, causing monitoring wells along the north and northwest sides of the NEU to receive water from the north and west of the NEU in addition to the south and east (upgradient), comparison of potentiometric surface maps prior to and subsequent to initiation of construction dewatering activities indicate groundwater movement in the vicinity of the subject wells has not been significantly affected. A consistent gradient and flow direction (northward) have been maintained in the area of the Northern Unit GMZ prior to and subsequent to construction dewatering activities as illustrated by the equipotential lines (contours) on the potentiometric surface maps near the subject wells. Furthermore, groundwater elevations in Northern Unit GMZ wells G37S and G37D only vary minimally, and are consistent prior to and subsequent to initiation of dewatering activities. Kilbuck Creek and the wetland mitigation area may buffer the potential drawdown in the vicinity of the creek due to construction dewatering activities in the NEU.

The Groundwater Investigation of Construction Dewatering also utilized groundwater elevation data obtained from both Winnebago Landfill and the Acme Solvent site to determine dewatering effects east and southeast of the NEU. A series of wells and piezometers east of Lindenwood

Road are monitored for quarterly groundwater elevations as part of the remediation system monitoring. The most recent set of data was presented in the LTRA Performance Evaluation Report (July 1 to December 31, 2010). Potentiometric surface maps were presented in Figure 1 of the LTRA report, dating from the third quarter 2007 to the third quarter 2010. The subject data transcend activation of the dewatering wells at the NEU (fourth quarter 2007). As shown, the contours contained in Figure 1 of the LTRA report (provided herein as Appendix C) are consistent prior to and subsequent to initiation of dewatering activities. This indicates the extent of influence did not encroach on the Acme Solvent site to the southeast of the NEU and east of the Northern Unit.

3. GROUNDWATER MONITORING WELL NETWORK

The facility has an extensive system of groundwater monitoring wells from which groundwater data are obtained. Pursuant to Permit No. 1991-138, the groundwater monitoring wells are divided into two differentiable networks: one for the Northern Unit and one for the Southern Unit. The Northern Unit network currently contains 33 groundwater monitoring wells. Of those, five are designated as upgradient wells, 14 monitor the zone of attenuation (ZOA), and one is a compliance boundary well at the edge of the ZOA. Winnebago Landfill samples 13 additional wells on a quarterly basis as part of the GMZ monitoring network. The Northern Unit GMZ wells are listed in Table 2 and shown in Figure 1.

The Southern Unit currently contains 17 groundwater monitoring wells. Of the 17 groundwater wells, six are designated as upgradient wells (two of which are Northern Unit upgradient wells) and 11 monitor the ZOA. Although some data (i.e., groundwater elevations and analytical results) from the NEU and Southern Unit have been used to characterize the hydrogeology for the Northern Unit, the NEU and Southern Unit are not specifically discussed as part of this application as the GMZ and remedial activities are not applicable to these disposal areas.

4. GROUNDWATER CORRECTIVE ACTION

4.1 Groundwater Management Zone (GMZ)

The results of historical groundwater sampling at Winnebago Landfill indicated that impacted groundwater was present beneath and downgradient to the Northern Unit. Elevated levels of inorganic compounds and organic solvents were detected, which prompted the 1995 applications for a GMZ. Although organic compounds were previously detected within the GMZ, the actual boundaries were determined by inorganic concentrations. The GMZ delineated the three-dimensional extent of groundwater that exhibits concentrations in excess of the AGQSS and was defined by the furthest extent of constituents above those standards.

In the 1995 applications, chloride and ammonia were chosen to demarcate the GMZ boundary because the extent of the elevated concentrations of these compounds incorporated the largest area. Two zones (Upper and Lower Zones) were developed in order to address differences in groundwater quality exhibited between the upper and lower parts of the sand and gravel aquifer. The limit of the GMZ was determined not to extend to the dolomite bedrock since no contaminants were detected in bedrock wells downgradient of the waste unit. Although only slight differences in hydraulic head existed between the bedrock and the Upper Zone, groundwater quality indicated appreciable differences in concentrations. These variations were likely due to the slight upward flow from the bedrock to the lower sand and gravel in addition to the different

flow regimes between the Upper and Lower Zones. As noted in Section 2, shallow groundwater normally discharges to Kilbuck Creek while deeper groundwater flows beneath the creek. The limits identified in 1995 for the upper and lower zones are shown in Figures 3 and 4, respectively.

The remedial measures and remedial performance monitoring program implemented pursuant to U.S. EPA guidelines were also the chosen remedial actions for the GMZ and were incorporated into the 1995 Permit Renewal and GMZ applications (Illinois EPA Application Log Nos. 1995-250 and 1996-058, respectively). The remedial measures, consisting of source reduction and natural attenuation, were implemented pursuant to a 1997 ROD Amendment for a new or revised Consent Decree, which reflected a new SOW due to a change in the remedy (issued in 1999). Source reduction was accomplished via three corrective measures: construction of a final cover; installation of additional leachate extraction wells; and installation of a gas extraction system. The concentrations of chlorinated compounds attributable to the Acme Solvent site decreased significantly during the 1990s due to the installation and operation of various remedial systems upgradient of the landfill at the Acme Solvent site. As such, the remedies designated for these compounds for the Northern Unit were deemed unnecessary.

The final cover for the Northern Unit was constructed in two phases. The western portion was completed in 1998 and the eastern portion in July 2001. The final cover inhibits infiltration of precipitation, thereby significantly reducing leachate production. A collection system, which includes 35 vertical dual gas/leachate extraction wells, was also installed with the recovered gas being directed to a flare system and leachate to storage tanks. Subsequent to completion of the final cover placement, the gas extraction system was modified in late 2002 to include a larger capacity system (2,500 cfm system vs. the initial 1,000 cfm system). This system enhancement considerably increased the efficiency of the gas extraction system.

The GMZ boundaries, as depicted in 1995, were based on one set of data (March 1995) obtained while the Northern Unit was active (four years prior to initial closure activities). A re-evaluation of the GMZ was conducted in 2004 pursuant to Condition VIII.22 of Permit No. 1991-138-LF, Modification No. 24. The evaluation was submitted July 15, 2004 as Illinois EPA Application Log No. 2004-257 (approved by Permit Modification No. 28). The results of the evaluation indicated that the large majority of GMZ parameter concentrations substantially decreased, many to levels below the permitted AGQSSs. Revised GMZ boundaries were similar to those depicted in 1995, although the 2004 perimeter was extended to encapsulate a small number of wells that were not included within the initial GMZ. The revision included extending the lower boundary of the GMZ in the vicinity of upgradient well G09D (and former well G14D) to include the upper portion of the dolomite bedrock. Dissolved ammonia and dissolved boron were chosen to demarcate the GMZ boundary because the extent of the elevated concentrations of these compounds incorporated the largest area. The use of dissolved ammonia and dissolved boron superseded the use of dissolved chloride as an indicator of leachate-derived compounds due to the other potential chloride sources (road salt, water softeners, etc.) within the vicinity of the facility. The horizontal extents of the GMZ (2004) for the upper and lower zones are provided in Figures 5 and 6, respectively.

The changes in the boundaries/extent from 1995 to 2004 were not an indication of the effectiveness of the remediation program. When comparing the differences between the 1995 and 2004 GMZ boundaries, the operational status of the Northern Unit and the amount of available data were considered. In 1995, the Northern Unit was fully operational with no closed areas and the GMZ boundaries were determined from one sampling event. Six additional years of waste disposal occurred prior to the completion of the closure activities. Final cover placement began in 1999 and was completed in July 2001. Additional closure activities were

completed in 2002 with the revision of the leachate/gas extraction system. The Groundwater Impact Assessment (GIA [1995]), which evaluated the natural attenuation/degradation remediation method, assumed steady-state conditions after completion of the closure activities and estimated five to ten years for cleanup to achieve background conditions.

As stated previously in Section 1, a re-evaluation of the GMZ was conducted in 2007 pursuant to Condition VIII.22. The re-evaluation was submitted May 1, 2007 as Illinois EPA Application Log No. 2007-181 (approved by Permit Modification No. 37). The results of the re-evaluation indicated that although a few inorganic parameters were still detected at concentrations above backgrounds, significant improvements to groundwater quality were evident as demonstrated by the decreases in individual parameter concentrations and GMZ extents. In addition, the organic constituents, which prompted the remedial actions, were typically not detected in groundwater downgradient of the facility during the review period. Revised GMZ boundaries were similar to those depicted in the 2004 evaluation. Although decreases in the GMZ extent and parameter concentrations were demonstrated in Illinois EPA Application Log No. 2007-181, the Illinois EPA requested further characterization of the western boundary of the GMZ.

In accordance with the September 29, 2008 addendum to Illinois EPA Application Log No. 2007-181, further characterization of the western boundary of the GMZ was submitted May 1, 2009 as Illinois EPA Application No. 2009-221 (approved by Modification No. 40). Based on the results of the GMZ investigation, groundwater quality to the west of the GMZ appeared unaffected by the Northern Unit. However, due to issues with the turbidity of the groundwater and sampling methodology, additional investigation was proposed. As a result of the issuance of Modification No. 40, Condition VIII.23 was revised requiring the installation of temporary investigation wells T1U-A, T1L-A, T2U-A, T2L-A, T3U-A, and T3L-A. In accordance with Condition VIII.23 of Modification No. 40, the results of the GMZ investigation report, submitted January 29, 2010 as Illinois EPA Application Log No. 2010-038 (approved by Permit Modification No. 50), indicated that concentrations of all organic and inorganic GMZ parameters, with the exception of dissolved ammonia, were non-detect or below the AGQS at T2U-A, T2L-A, and T3U-A. However, the investigation results indicated that dissolved ammonia concentrations west of Kilbuck Creek may be affected by background conditions and spatial variability, possibly associated with the agricultural land use of the area, and not fully represented by the Northern Unit AGQS.

Addendums 1 and 2 to Illinois EPA Application Log No. 2010-038, submitted September 16, 2010 and June 14, 2011, respectively, provided a comprehensive evaluation regarding the direction of groundwater movement in the vicinity of Northern Unit Compliance Boundary wells G52S and G52M, including the Northern Unit GMZ temporary investigation wells. An additional evaluation was performed in response to Condition VIII.24 of Permit No. 2006-221-LF, identifying the extent of influence of construction dewatering activities in the NEU, specifically in the vicinity of Northern unit Compliance Boundary wells G52S and G52M and temporary investigation wells T1U-A, T1L-A, T2U-A, T2L-A, T3U-A, and T3L-A (see discussion Section 2.4). Based on the evaluation, a northerly groundwater movement was maintained in the subject area prior to and subsequent to initiation of construction dewatering activities in the NEU due to Kilbuck Creek and the wetland mitigation area acting as a buffer against potential drawdown. As a result of consistent northerly groundwater movement, the dissolved ammonia concentrations in the groundwater west of Kilbuck Creek were determined to be affected by conditions present to the south and southeast and not the result of the Northern Unit. Further investigation for the dissolved ammonia exceedences at temporary investigation wells T2U-A, T2L-A, and T3U-A was refuted citing that dissolved ammonia sources other than the landfill are evidenced by: concentrations of dissolved ammonia upgradient to the facility waste units exceeding concentrations downgradient to the waste units during the December 2009 GMZ investigation; lack of additional indicator parameter

exceedences during the GMZ investigation; and a demonstration that the Temporary GMZ Assessment Wells located west of Kilbuck Creek receive water from the south and southeast and are influenced by mixing of surface water and groundwater.

4.2 Remedial Performance Monitoring

The remedial performance monitoring program is the nomenclature used to describe the additional efforts implemented to further define the status of the groundwater quality adjacent to the Northern Unit. As stated above in Section 3, the program consists of 33 groundwater monitoring wells and 3 stream gauge locations located on Kilbuck Creek. More than one well designation exists for many of the wells; however, this evaluation will utilize the Illinois EPA designations for all references and drawings, where appropriate.

The subject wells were installed to access groundwater at three general intervals of the saturated deposits or dolomite bedrock. In areas where the saturated sand and gravel deposits are thick, multiple screen intervals (nested wells) exist, providing access to shallow and deep intervals within the deposit as well as the bedrock. This was necessary to monitor potential movement of contaminants at multiple vertical intervals within the saturated medium. The wells have been sampled quarterly and analyzed for List G1 parameters. Annually, the wells have been sampled and tested for an expanded list (List G2). Results of the analyses are discussed in Section 5 below.

5. GROUNDWATER QUALITY

5.1 Background Groundwater Quality

Quarterly and annual groundwater quality results are evaluated based on the statistical interwell background concentrations, or AGQSs, in accordance with Illinois EPA Permit No. 1991-138-LF. The AGQSs for the facility were derived from upgradient wells G09M, G09D, G13S, G13D and G20D. Impacts on background groundwater quality by releases from the Acme Solvent site have been well established in previous investigations and residual effects are occasionally observed. Table 3 lists the wells and parameters in which concentrations have exhibited exceedences above the AGQS since the previous GMZ evaluation for the Northern Unit.

5.2 Trend Analyses

Historical trend analyses were conducted for the GMZ parameters in the GMZ wells. Parameters not currently exceeding the AGQS and displaying no significant trends since the 2007 GMZ evaluation are not discussed below. As previously discussed, three zones have been delineated, an Upper Zone, a Lower Zone, and the Bedrock Zone. Trend graphs for parameter concentrations from groundwater monitoring wells in each zone, compiled from data obtained from the initial sampling event for each well through first quarter 2012, are presented in Appendix D, Appendix E, and Appendix F, respectively. Data utilized to construct the graphs is provided in tabular format in Table 4. Since routine monitoring of the GMZ began with the issuance of the 1995 permit renewal application and GMZ application (approved in August 1996) the data prior to issuance of the subject applications are not included due to their sporadic collection. Data prior to 1997 were presented in Table 4 of the 2004 GMZ Evaluation (Illinois EPA Application Log No. 2004-257).

5.2.1 Upper Zone

The Upper Zone of the GMZ generally ranges from an elevation of 690 feet above MSL to the surface of the water table and is currently monitored by wells G130, G17S, G33S, G34S, G35S, G37S, G40S, G41S, G50S, G51S, G52S, G54S, R03S, and R42S. As shown in Table 2, wells G119 and G15S were replaced in December 2008 by wells G50S and G51S, respectively. The dataset analyzed ranges from first or second quarter 1997 (depending on the parameter) through first quarter 2012 with the exception of G15S, G119, and G18S, which were abandoned due to development activities of the North Expansion Unit in July 2011.

The trend analyses as described below are based on evaluation of individual parameters. Graphs depicting parameter specific concentrations are contained in Appendix D.

5.2.1.1 Parameter Specific Trends

5.2.1.1.1 GMZ Parameters

Inorganic Parameters (Upper Zone)

Ammonia as N, dissolved

Ammonia can be difficult to evaluate given that the facility is located in a rural area, susceptible to agricultural runoff containing fertilizers. Not only can fertilizer components be transported through the fractured bedrock, but they can also be transported via surface drainage into Kilbuck Creek. Given the facility hydrogeologic characteristics, constituents contained in the surface water can easily influence groundwater quality. As mentioned previously in Section 4.1, dissolved ammonia concentrations in the groundwater west of Kilbuck Creek were determined to be affected by conditions present to the south and southeast and not the result of the Northern Unit. Further investigation for the dissolved ammonia exceedences at Temporary GMZ Assessment Wells T2U-A, T2L-A, and T3U-A was refuted citing that dissolved ammonia sources other than the landfill are evidenced by: concentrations of dissolved ammonia upgradient to the facility waste units exceeding concentrations downgradient to the waste units during the December 2009 GMZ investigation; lack of additional indicator parameter exceedences during the GMZ investigation; and a demonstration that the Temporary GMZ Assessment Wells located west of Kilbuck Creek receive water from the south and southeast and are influenced by mixing of surface water and groundwater.

As shown in the exceedence summary table for the current review period (Table 3), historic analytical data (Table 4), and trend graph (Appendix D), concentrations in several Upper Zone wells exceeded the AGQS (0.9 mg/L) before and during the current review period. Wells exhibiting stable concentrations below the AGQS are not discussed in this section.

G15S—Concentrations in well G15S have consistently exceeded the AGQS since sampling commenced first quarter 1997. The concentrations in the replacement for well G15S (G51S installed in December 2008) have also consistently exceeded the AGQS, although concentrations have been much lower. In general, concentrations in well G15S and its replacement well G51S are sporadic with no apparent increasing or decreasing trends and appear to have a component of seasonal influence, with concentrations greater during first and third quarters.

G34S—Dissolved ammonia concentrations in well G34S exhibit an overall decreasing trend from 26 mg/L during first quarter 2008 to non-detect since first quarter 2011. Concentrations have been below the AGQS since first quarter 2010.

G35S—Dissolved ammonia concentrations in well G35S exhibit an overall decreasing trend throughout the current review period from 16 mg/L during second quarter 2007 to non-detect during first quarter 2012. Concentrations in well G35S have been below the AGQS since fourth quarter 2010. As shown in Table 4, the dissolved ammonia concentrations recorded in well G35S during the current review period are lower than any concentrations recorded during previous review periods.

G37S—Concentrations in well G37S exhibit an overall stable to decreasing trend throughout the previous and current review periods. Concentrations above the AGQS were recorded at well G37S during second and third quarters 2007. However, concentrations during these two sampling events were within historic limits and lower than concentrations recorded from fourth quarter 2004 through fourth quarter 2006 (see Table 4).

G40S—Dissolved ammonia concentrations in well G40S have consistently exceeded the AGQS during the current, as well as previous, review periods. Following a slight increasing trend, which reached a maximum concentration during second quarter 2006, dissolved ammonia concentrations have been decreasing to stable.

G41S—Concentrations at well G41S have been lower than previous review periods and continue to display a significant decreasing trend. Within the current review period, the concentration of dissolved ammonia at well G41S has decreased from 35 mg/L (second quarter 2007) to 0.37 mg/L (first quarter 2012).

R03S—The concentrations of dissolved ammonia at well R03S have consistently exceeded the AGQS during previous review periods, but have been below the AGQS since fourth quarter 2010 and are currently non-detect. The decreasing trend for dissolved ammonia concentrations at well R03S has continued since third quarter 2002.

R42S—Concentrations of dissolved ammonia at R42S have historically remained stable slightly above the AGQS, a trend that continues through the current review period. Concentrations are stable and within historic limits for this parameter.

Prior to and during the current review period, concentrations of dissolved ammonia in several Upper Zone wells exceeded the AGQS. However, during the current review period, no increasing trends are displayed for any wells that have been reported exceeding the AGQS. Instead, decreasing trends are apparent for wells G34S, G35S, G37S, G40S, G41S, and R03S while a stable trend is apparent for G15S/G51S and R42S. Wells not discussed are those with dissolved ammonia concentrations stable or decreasing below the AGQS.

Arsenic, dissolved

Concentrations of dissolved arsenic from several Upper Zone wells (G15S/G51S, G18S, G40S, G41S, G52S, R03S, and R42S) have exceeded the AGQS (2 ug/L) during the current review period. The remaining wells screened in the Upper Zone exhibit stable concentrations below the AGQS.

G15S—Concentrations in well G15S have historically exceeded the AGQS until sampling ceased third quarter 2008. Sampling resumed first quarter 2009. An increasing trend is apparent at G51S with the highest concentration (12 ug/L) recorded during second and third quarters 2011.

G18S—Dissolved arsenic concentrations in well G18S exceeded the AGQS sporadically since sampling commenced first quarter 1997. The only detection of dissolved arsenic in G18S during the current review period was during second quarter 2007. As previously mentioned, well G18S was abandoned July 2011.

G40S—Concentrations of dissolved arsenic in well G40S have been non-detect or stable below the AGQS during previous review periods. During the current review period, concentrations above the AGQS were recorded during second and third quarters 2009; subsequently the concentrations decreased until the well became dry for the third quarter 2010 sampling event. Well G40S has been dry since.

G41S—Dissolved arsenic concentrations in well G41S have been above the AGQS and have increased during previous review periods. However, dissolved arsenic concentrations in well G41S have decreased significantly throughout the current review period from 38 ug/L (third quarter 2007) to non-detect since fourth quarter 2011.

G52S—Concentrations in well G52S, sampled since fourth quarter 2009, have been relatively stable below the AGQS or non-detect with the exception of sporadic detections above the AGQS during second quarter 2010 and fourth quarter 2011.

R03S—Dissolved arsenic concentrations in well R03S have historically fluctuated above the AGQS, but as shown by the trend graph (Appendix D) have decreased significantly throughout the current review period from 10 ug/L (first quarter 2007) to non-detect since first quarter 2008.

R42S—Concentrations in well R42S have consistently exceeded the AGQS during previous as well as the current review period. Although fluctuation of dissolved arsenic concentrations is prominent in well R42S, no increasing trend is apparent.

Prior to and during the current review period, concentrations of dissolved arsenic in several Upper Zone wells exceeded the AGQS. However, during the current review period, all wells with dissolved arsenic concentrations above the AGQS, with the exception of G51S, display decreasing or stable trends. Concentrations in wells G41S and R03S, which have historically exceeded the AGQS, have decreased below the detection limit during the current review period. Wells not discussed are those with dissolved arsenic concentrations stable or decreasing below the AGQS.

Arsenic is naturally occurring in groundwater and is highly sensitive to oxygen reducing conditions. The groundwater at the facility is unconfined and shallow. Movement beneath a structure (i.e., waste unit) is sufficient to cause anaerobic conditions, which can cause the arsenic concentrations to increase without any direct influence from the waste unit. Arsenic concentrations detected in downgradient wells do not necessarily indicate an impact from the waste unit.

Arsenic, total

Concentrations of total arsenic from several Upper Zone wells (G15S/G51S, G18S, G41S, G50S, G52S, G54S, R03S, and R42S) have exceeded the AGQS (10 ug/L) during the current review period. Total arsenic was sampled on an annual basis until the issuance of Permit Modification Number 28, at which time quarterly sampling commenced.

G15S—Total arsenic concentrations in well G15S increased above the AGQS during the third quarter 2007 sampling event and remained above the AGQS until replaced by well G51S. Total arsenic concentrations in well G51S have remained above the AGQS throughout the current review period with highest concentrations generally recorded during first and third quarter sampling events. As shown by the trend graph provided in Appendix D, no increasing trend is apparent indicating the concentrations are the result of temporal variability.

G18S—Total arsenic concentrations in well G18S consistently exceeded the AGQS throughout the current as well as previous review periods and displayed an increasing trend from 1997 to 2005, reaching a maximum concentration of 150 ug/L (second quarter 2005). Since second quarter 2005 the concentrations have decreased and have been within historic limits for this parameter. No increasing trend is apparent for total arsenic in well G18S (abandoned July 2011).

G41S—Concentrations in well G41S have been above the AGQS throughout its sampling history and only most recently (second quarter through fourth quarter 2011) decreased below the AGQS. As shown by the trend graph, no increasing or decreasing trend is apparent for the current or previous review periods.

G50S—Well G50S has been dry since second quarter 2010. Prior to going dry, concentrations did exceed the standard. Since well G50S has only contained sufficient water to sample during five sampling events, a determination of trend cannot be concluded.

G52S—Total arsenic concentrations in well G52S have been above the AGQS throughout its sampling history (fourth quarter 2009 through first quarter 2012) with the exception of fourth quarter 2009 and fourth quarter 2011. The concentration reached a maximum (74 ug/L) during second quarter 2010 and has been decreasing since that time.

G54S—The first sampling for well G54S was conducted first quarter 2012 with a recorded concentration of 18 ug/L. No additional information exists currently for this well.

R03S—Total arsenic concentrations in well R03S have historically been above the AGQS during previous review periods. However, during the current review period concentrations have decreased and been non-detect or stable below the AGQS with sporadic detections above the AGQS.

R42S—Concentrations in well R42S have been above the AGQS since sampling commenced second quarter 1997. During the current review period the concentration increased to 70 ug/L during first quarter 2007, the highest concentration since second

quarter 1999. However, since first quarter 2007 the concentration of total arsenic in well R42S has been decreasing.

Prior to and during the current review period, concentrations of total arsenic in several Upper Zone wells exceeded the AGQS. However, during the current review period, all wells with total arsenic concentrations above the AGQS display decreasing or stable trends. Concentrations in wells G41S and R03S, which have historically exceeded the AGQS, have decreased below the AGQS during the current review period. Wells not discussed are those with total arsenic concentrations stable or decreasing below the AGQS.

Boron, dissolved

As discussed previously, dissolved boron was one of the parameters used to delineate the GMZ extent as part of the 2004 application (Illinois EPA Application Log No. 2004-257). Concentrations of dissolved boron from several Upper Zone wells (G15S/G51S, G18S, G34S, G37S, G40S, G41S, G50S, and R42S) have exceeded the AGQS (98 ug/L) during the current review period. The remaining wells screened in the Upper Zone exhibit stable concentrations below the AGQS; boron concentrations in these wells are not discussed below.

G15S—Dissolved boron concentrations in well G15S have consistently exceeded the AGQS throughout its sampling history. Although variability increased during the previous review period no significant increasing or decreasing trend was apparent. Upon completion of sampling at G15S (second quarter 2008) the concentration of dissolved boron was 1,300 ug/L. Well G51S replaced G15S and was initially sampled the second quarter 2009. Concentrations were detected below the AGQS until second quarter 2010. Since second quarter 2010 dissolved boron concentrations in well G51S have been increasing to the current concentration of 520 ug/L (third quarter 2011).

G18S—Concentrations in well G18S have been slightly below the AGQS except during fourth quarter sampling events when concentrations increased. The temporary increases above the AGQS during fourth quarter sampling events appear to be the result of seasonal fluctuation and temporal variability. No increasing trends are apparent for dissolved boron in well G18S (abandoned July 2011).

G34S—Dissolved boron concentrations in well G34S have fluctuated slightly above and below the AGQS since inclusion of the well into the monitoring program during the second quarter 1999. During the current review period, dissolved boron concentrations have decreased below the AGQS and have remained since second quarter 2008.

G37S—Dissolved boron concentrations in well G37S have been similar to concentrations in well G34S, fluctuating slightly above and below the AGQS with no apparent increasing trend. Dissolved boron concentrations in well G37S have been below the AGQS since second quarter 2007.

G40S—Concentrations in well G40S have historically remained stable above the AGQS but decreased below the AGQS during the current review period from second to fourth quarter 2007. After reaching a minimum concentration (80 ug/L) during fourth quarter 2007, concentrations increased, reaching a maximum (340 ug/L) during third

quarter 2009. Although sufficient volume of groundwater has not been available for sampling purposes since second quarter 2010, there were no significant increasing trends apparent for dissolved boron in well G40S.

G41S—Dissolved boron concentrations in well G41S have consistently remained above the AGQS during previous review periods. However, since first quarter 2003, concentrations have been decreasing significantly and were no longer exceeding the AGQS beginning first quarter 2008. The concentrations have continued to decrease below the AGQS with the exception of fourth quarter 2008 and third quarter 2009.

G50S—Dissolved boron concentrations in well G50S, which has been dry since second quarter 2010, were below the AGQS from second quarter 2009 to first quarter 2010. The only concentration to exceed the AGQS was recorded during first quarter 2009. Since well G50S has only had sufficient water to sample during five sampling events, a determination of trend cannot be concluded.

R42S—Dissolved boron concentrations in well R42S have fluctuated below the AGQS since second quarter 2002 with the exception of fourth quarter 2011 (99 ug/L). Dissolved boron concentrations appear stable near the AGQS.

Prior to and during the current review period, concentrations of dissolved boron in several Upper Zone wells exceeded the AGQS. However, with the exception of G51S, all wells with dissolved boron concentrations above the AGQS display decreasing or stable trends throughout the current review period. Dissolved boron concentrations in well G41S, which have historically exceeded the AGQS, have decreased below the AGQS during the current review period.

Boron, total

Concentrations and trends for total boron are similar to those recorded for dissolved boron.

G15S—Total boron concentrations in well G15S have consistently exceeded the AGQS (200 ug/L) throughout its sampling history. Although variability increased during the previous review period, no significant increasing or decreasing trend was apparent. The last sampling event for G15S occurred the second quarter 2008, resulting in a concentration of 1,400 ug/L. The well was abandoned and replaced by G51S. Initial total boron concentrations obtained from G51S were below the AGQS until third quarter 2010. Since third quarter 2010 total boron concentrations in well G51S have been increasing to the current concentration of 500 ug/L (third quarter 2011).

G18S—Concentrations in well G18S have fluctuated above and below the AGQS with maximum concentrations generally recorded during fourth quarter sampling events. Similar to the trend for dissolved boron, the increases above the background and maximum concentrations recorded during fourth quarter sampling events appear to be the result of seasonal fluctuation and temporal variability. No increasing trends are apparent for total boron in well G18S (abandoned July 2011).

G34S—Total boron concentrations in well G34S, with the exception of first quarter 2008, have remained stable and below the AGQS throughout previous review periods as well as the current review period.

G40S—Concentrations in well G40S have fluctuated above and below the AGQS during previous review periods as well as the current review period. During the current review period, concentrations have been recorded above the AGQS during first quarter 2007, third quarter 2009, and second quarter 2010. Although the well has been dry since second quarter 2010, there were no increasing trends apparent for total boron in well G40S.

G41S—Total boron concentrations in well G41S, similar to dissolved boron concentrations, have consistently remained above the AGQS during previous review periods. However, since first quarter 2003 concentrations have been decreasing significantly, dropping below the AGQS during first quarter 2008. The concentrations have continued to decrease below the AGQS throughout the current review period.

G50S—Total boron concentrations in well G50S, which has been dry since second quarter 2010, were below the AGQS from second quarter 2009 to fourth quarter 2009. The only concentrations to exceed the AGQS were recorded during first quarter 2009 and first quarter 2010.

G52S—Total boron concentrations in well G52S, sampled since fourth quarter 2009, were initially below the AGQS and increased above the AGQS to a maximum concentration (290 ug/L) during first quarter 2011. Since first quarter 2011 concentrations have decreased below the AGQS.

Prior to and during the current review period, concentrations of total boron in several Upper Zone wells exceeded the AGQS. However, with the exception of G51S, all wells with total boron concentrations above the AGQS display decreasing or stable trends throughout the current review period. Similar to dissolved boron concentrations, total boron concentrations in well G41S, which have historically exceeded the AGQS, have decreased below the AGQS during the current review period. Concentrations and trends for total boron are similar to those recorded for dissolved boron. Wells not discussed are those with total boron concentrations stable or decreasing below the AGQS.

Chloride, dissolved

As discussed previously, dissolved chloride was the original indicator parameter used by Geotrans for delineating the GMZ in 1995. In later applications (1998 and 1999) Geotrans indicated that dissolved chloride may not be an effective indicator of leachate-derived compounds due to the possibility of other potential sources within the vicinity of the facility. The use of dissolved chloride as an indicator parameter to demarcate the GMZ was superseded by dissolved ammonia and dissolved boron. Concentrations of dissolved chloride from several Upper Zone wells (G15S/G51S, G18S, G34S, G37S, G40S, G41S, G50S, R03S, and R42S) have exceeded the AGQS (87.5 mg/L) during the current review period. Wells exhibiting exceedences during the review period are discussed below.

G15S—Dissolved chloride concentrations in well G15S have consistently exceeded the AGQS during previous review periods as well as the current review period (until sampling ceased after second quarter 2008). Well G15S was abandoned and replaced with G51S, which initiated sampling the first quarter 2009. Chloride concentrations in the replacement well have been similar to those recorded for G15S. Most recently (third quarter 2011), the concentration of dissolved chloride decreased to 4.4 mg/L.

Due to construction activities in the NEU, G51S was been dry the fourth quarter 2011 and the first quarter 2012. Although dissolved chloride concentrations in well G51S have fluctuated significantly since approximately 2003, no significant increasing trends are noted for this parameter.

G18S—Concentrations in well G18S have been below the AGQS since first quarter 2002. During the final sampling event for well G18S (abandoned in July 2011), the concentration had increased to 110 mg/L, significantly lower than concentrations recorded prior to 2002.

G34S—Dissolved chloride concentrations in well G34S have historically fluctuated above and below the AGQS. However, during the current review period concentrations have decreased and remained stable below the AGQS since second quarter 2008.

G37S—Similar to well G34S, dissolved chloride concentrations in well G37S have fluctuated above and below the AGQS throughout its sampling history. However, since first quarter 2007, concentrations have continued to decrease below the AGQS.

G40S—Dissolved chloride concentrations in well G40S increased gradually during the previous review period before decreasing below the AGQS during the second quarter 2007 sampling event. Concentrations remained below the AGQS until first quarter 2008 at which time concentrations began to fluctuate above the AGQS, increasing to a high of 290 mg/L (first quarter 2009). Concentrations consistently decreased to 190 mg/L from the first quarter 2009 to through second quarter 2010. Due to construction activities in the NEU, G40S has been dry since third quarter 2010.

G41S—Dissolved chloride concentrations in well G41S have been gradually decreasing since 1999. During the current review period, the concentrations have continued to decrease below the AGQS.

G50S—Concentrations in well G50S, sampled from first quarter 2009 to first quarter 2010, after which time the well went dry, were below the AGQS with the exception of the initial sampling event (first quarter 2009). The available data suggests the concentrations are stable well below the AGQS.

R03S—Dissolved chloride concentrations in well R03S have remained below the AGQS during the current review period with the exception of second quarter 2007 (90 mg/L). Concentrations continue to decrease since 2002.

R42S—Dissolved chloride concentrations in well R42S have historically fluctuated above and below the AGQS, and are currently below the AGQS with a concentration of 67 mg/L. The trend has continued through the current review period with no apparent increasing or decreasing characteristics.

Prior to and during the current review period, concentrations of dissolved chloride in several Upper Zone wells exceeded the AGQS. However, with the exception of G40S which has been dry since the third quarter 2010, dissolved chloride concentrations above the AGQS display decreasing trends (i.e., G34S, G37S, G41S, and R03S) or stable trends (i.e., G15S/G51S, G18S, and R42S) throughout the current review period.

Chloride, total

Concentrations and trends for total chloride are consistent with those exhibited for the dissolved component. Ten wells (G15S/G51S, G18S, G34S, G37S, G40S, G41S, G50S, R03S, and R42S) have had total chloride concentrations above the AGQS (87.5 mg/L) during the current review period. A detailed discussion of the trends can be found in the dissolved chloride section above along with the trend graph contained in Appendix D. Overall, most concentrations have decreased since completion of the final cover in 2001 and with the exception of increasing trends observed for G40S and G15S/G51S, the wells currently exceeding the AGQS exhibit stable to decreasing trends.

Nitrate as N, dissolved

Concentrations in wells screened in the Upper Zone are generally stable and below the AGQS of 11.74 mg/L. Only wells exhibiting concentrations above the AGQS are discussed below.

G119/G50S—Well G119, replaced by G50S in December 2008, was last sampled the first quarter 2007, resulting in a concentration of 13 mg/L, which exceeded the AGQS. However, results from the replacement well (G50S) have been below the AGQS during each subsequent sampling event.

G130—Concentrations in well G130 have been stable and slightly above the AGQS value at approximately 12 mg/L during the previous and current review periods.

G40S—Dissolved nitrate concentrations in well G40S have been below the AGQS except for sporadic increases above the AGQS during second quarter 2007 and second quarter 2008.

Nitrate as N, total

Concentrations and trends for total nitrate are consistent with those exhibited for the dissolved component of nitrate. Four wells (G119, G130, G33S, and G40S) have exhibited total nitrate concentrations above the AGQS (11.74 mg/L) during the current review period. A discussion of the trends can be found in the dissolved nitrate section above along with the trend graph contained in Appendix D. Overall, most concentrations have stabilized since completion of the final cover in 2001 and the variability that is observed appear to be the result of seasonal fluctuations due to the implementation of the quarterly sampling scheduling which began in 2005.

Potassium, total

Total potassium was sampled annually until the issuance of Permit Modification No. 28 (approval of the 2004 GMZ evaluation) during fourth quarter 2005, at which point a quarterly sampling schedule was implemented. Only wells exhibiting exceedences of the AGQS are discussed below. Wells reporting concentrations consistently below the AGQSs are not discussed.

G15S—Concentrations in well G15S have consistently exceeded the AGQS (29.01 mg/L) during previous review periods as well as the current review period. Significant fluctuations in concentration began in 2003 and continued until sampling was discontinued after the second quarter 2008 sampling event due to well abandonment. Well G51S, which replaced G15S, has been sampled since first quarter 2009.

Concentrations have been steadily increasing above the AGQS to a concentration of 46 mg/L (third quarter 2011 – G51S was dry the four quarter 2011 and first quarter 2012).

G18S—Concentrations in well G18S have been decreasing since second quarter 2005 and have sporadically increased above the AGQS during first and fourth quarters 2008 and first and fourth quarters 2009. However, the temporary concentration increases were within historic limits for the parameter.

G40S—Concentrations above the AGQS were recorded in well G40S during first quarter 2007 and second quarter 2008 (30 and 38 mg/L, respectively). After reaching a maximum concentration during second quarter 2008, the concentration has been steadily decreasing. Well G40S has been dry since the third quarter 2010, but total potassium concentrations have been stable during previous review periods as well as the current review period, and typically below the AGQS.

G41S—Total potassium concentrations in well G41S were recorded above the AGQS during first and second quarters 2007. However, concentrations have been decreasing steadily since fourth quarter 2005 and have been below the AGQS since third quarter 2007.

G50S—Concentrations in well G50S have fluctuated significantly above and below the AGQS from first quarter 2009 to first quarter 2010, after which time the well has been dry. Based on the limited data available for well G50S, no significant increasing or decreasing trends are apparent.

G52S—Concentrations in well G52S, initially sampled first quarter 2009, increased above the AGQS to 55 mg/L (first quarter 2011) but has since decreased to 24 mg/L (first quarter 2012). The limited dataset for G52S cannot be used to conclude any long-term trends.

Prior to and during the current review period, concentrations of total potassium in a few of the Upper Zone wells exceeded the AGQS. However, with the exception of G51S, concentrations have been decreasing or stable throughout the current review period.

Sodium, total

Concentrations of total sodium above the AGQS (164.79 mg/L) were recorded in two wells (G15S and G51S) during the current review period. Concentrations in well G51S, which replaced well G15S, have been steadily increasing since it was initially sampled first quarter 2009. Well G15S and its replacement G51S are the only wells with total sodium concentrations exceeding the AGQS during the current review period.

Organic Parameters (Upper Zone)

1,4-Dichlorobenzene

Historically, concentrations in well G15S have exceeded the AGQS (5 ug/L) but have shown a steady decrease from 13 ug/L in 1997 to 9 ug/L in 2008. Although concentrations in well G51S, which replaced well G15S, have increased above the AGQS during fourth quarter 2010 and second quarter 2011, the concentrations are

lower than recorded in well G15S. G15S/G51S are the only wells that exhibited 1,4-dichlorobenzene exceedences of the AGQS during the current review period.

Tetrahydrofuran

Concentrations of tetrahydrofuran have exceeded the AGQS (42 ug/L) in well G51S during the current review period. As shown by the trend graph provided in Appendix D, concentrations have increased steadily since the initial sampling event (second quarter 2009). Well G51S has been dry since the fourth quarter 2011; no additional data are available from well G51S.

5.2.1.1.2 Non-GMZ Parameters

During the current review period, some parameters not currently included in the GMZ list of parameters have exhibited concentrations exceeding the respective AGQS (Table 3). Trend graphs detailing the concentrations of the subject parameters in all Upper Zone wells are contained in Appendix D.

Inorganic Parameters (Upper Zone)

Chemical Oxygen Demand (COD)

Chemical oxygen demand (COD) is a measure of the amount of oxygen needed to fully oxidize an organic compound by the addition of a strong oxidizing agent under acidic conditions. The COD analysis is commonly used as an indirect measurement of the amount of organic compounds in water; it is not a specific chemical constituent and cannot differentiate between the type of organic present in a sample.

COD measurements exceeded the AGQS (50.04 mg/L) in well G15S during second quarter 2008. Although COD measurements have historically exceeded the AGQS in well G15S, measurements were below the AGQS during second quarter 2007, the only other measurement obtained during the current review period. Furthermore, concentrations appear stable and the replacement well for G15S (G51S) has not exceeded the AGQS.

Cobalt, total

Concentrations of total cobalt in well G18S exceeded the AGQS (50 ug/L) during second quarter 2008. No increasing trend is noted for this parameter.

Iron, dissolved

Dissolved iron was removed from the routine monitoring list (List G1) as part of the regulatory amendments imposed by Illinois Pollution Control Board Rulemaking Docket No. R2007-008. Concentrations of dissolved iron in well R42S have historically been above the AGQS (12,189.61 ug/L), although no increasing trends are present. Dissolved iron exceedences or significant increasing trends have not been recorded at other Upper Zone monitoring points. The elevated concentrations at R42S may be the result of natural spatial variability between the screen interval for well R42S and the other Upper Zone wells. Well R42S is substantially shallower than the other Upper Zone wells and encounters a black organic silty clay lens, as opposed to the sand and gravel screened by the other shallow Northern Unit monitoring wells.

Lead, dissolved

Concentrations of dissolved lead have exceeded the AGQS (4 ug/L) in two Upper Zone wells (G51S and G52S) during the current review period. Concentrations in well G51S have been non-detect except during third quarter 2010 with a recorded concentration of 27 ug/L. Concentrations in well G52S exceeded the AGQS during second quarter 2010, and third and fourth quarters 2011. Dissolved lead was not detected during first quarter 2012.

Magnesium, dissolved

Concentrations of dissolved magnesium have exceeded the AGQS (170.41 mg/L) in Upper Zone wells G51S and G52S during the current review period. Dissolved magnesium exceeded the AGQS in G51S during third quarter 2010 but returned to representative concentrations the following quarter. Concentrations in well G52S exceeded the AGQS during second quarter 2010 and again during fourth quarter 2011. Concentrations decreased the following quarters and no increasing trends are apparent for either well.

Magnesium, total

Concentrations of total magnesium exceeded the AGQS (109.5 mg/L) in Upper Zone wells G18S and G40S during second quarter 2008. No other exceedences during the current review period have been noted and no increasing trends are apparent.

Manganese, dissolved

Dissolved manganese was removed from the routine monitoring list (List G1) as part of the regulatory amendments imposed by Illinois Pollution Control Board Rulemaking Docket No. R2007-008. Concentrations in well R42S exceeded the AGQS (1,479.53 ug/L) during third quarter 2007. However, upon sampling the following quarter the concentration had decreased below the AGQS.

pH (field)

Field measurements of pH have increased above the AGQS range (5.4 – 8.1) in several Upper Zone wells (G130, G18S, G33S, G34S, G35S, G37S, G40S, and G52S) during the current review period. The vast majority of exceedences occurred during the fourth quarter 2011 sampling event and were not confirmed during follow up sampling. No increasing or decreasing trends are apparent.

Selenium, total

Concentrations of total selenium exceeded the AGQS (4 ug/L) in three Upper Zone wells (G15S, G18S, and G40S) during the current review period. Concentrations have frequently exceeded the AGQS in well G15S during previous review periods as well as the current review period. However, concentrations are stable and within historic limits for this parameter. Total selenium concentrations exceeded the AGQS in wells G18S and G40S during second quarter 2008. However, no other exceedences were recorded for this parameter in the subject wells and concentrations were stable with no increasing trends noted.

Specific Conductance

Field measurements of specific conductance exceeded the AGQS (3,820 umhos/cm) in well G15S during fourth quarter 2007 and first quarter 2008 (confirmed by

resample). However, upon sampling the following quarter measurements had decreased below the AGQS and no increasing trends are noted. Furthermore, concentrations in the replacement for G15S (G51S) have not exceeded the AGQS.

Sulfate, dissolved

Concentrations of dissolved sulfate exceeded the AGQS (360 mg/L) in well R42S during second quarter 2007. Upon sampling the following quarter the concentration decreased below the AGQS and has been stable to decreasing since that time.

Sulfate, total

The total sulfate concentrations in well R42S have exceeded the AGQS (179.37 mg/L) during each sampling event (three total) in which total sulfate was analyzed during the review period. However, the concentration above the AGQS was stable with no increasing trend noted.

Organic Parameters (Upper Zone)

Acetone

Concentrations of acetone, a common laboratory artifact, have exceeded the AGQS (10 ug/L) in wells G15S and G51S during the current review period. However, concentrations decreased to non-detect upon sampling the following quarter and have remained stable.

Acrylonitrile

The concentration of acrylonitrile exceeded the AGQS (10 ug/L) in well R03S during second quarter 2007. However, the concentration decreased to non-detect upon sampling the following quarter and has remained non-detect since second quarter 2007.

Carbon Disulfide

The concentration of carbon disulfide exceeded the AGQS (5 ug/L) in well G17S during fourth quarter 2008. Upon sampling the following quarter the concentration decreased to non-detect.

5.2.2 Lower Zone

The Lower Zone of the GMZ generally ranges from 681 feet above MSL to the bedrock surface and is currently monitored by wells G03M, G16M, G33D, G34D, G35D, G36S, G37D, G38S, G41M, G52M, and G54M. The dataset analyzed ranges from first or second quarter 1997 (depending on the parameter) through first quarter 2012 with the exception of G18D (abandoned July 2009) and G39S (replaced by R39S in January 2009). The wells are typically screened in saturated sand and gravel deposits.

The trend analyses as described below are based on evaluation of individual parameters. Graphs depicting parameter specific concentrations are contained in Appendix E.

5.2.2.1 Parameter Specific Trends

5.2.2.1.1 GMZ Parameters

Inorganic Parameters (Lower Zone)

Ammonia as N, dissolved

The presence of dissolved ammonia in the groundwater has been associated with activities from the Northern Unit and was designated an indicator parameter in previous investigations (HSI Geotrans 1998 and 1999). As shown in the exceedence summary table for the current review period (Table 3), historic analytical data (Table 4), and trend graph (Appendix E), concentrations in several Lower Zone wells exceeded the AGQS (0.9 mg/L) before and during the review period. Wells discussed below include only those that exhibited exceedences of AGQSs during the current review period.

G16M—Dissolved ammonia concentrations in well G16M have consistently exceeded the AGQS during previous review periods and have continued to exceed the AGQS in the current review period until second quarter 2008. However, since second quarter 2008, concentrations have decreased below the AGQS and have been non-detect since third quarter 2008.

G18D—Concentrations in well G18D have historically been non-detect, a trend which continued into the current review period until second quarter 2008 at which time concentrations increased above the AGQS. Dissolved ammonia concentrations in well G18D increased to a maximum of 14 mg/L (third quarter 2009) before steadily decreasing to 1 mg/L (first and second quarters 2011). Well G18D was abandoned in July 2011 due to development of the NEU.

G34D—Concentrations in well G34D have sporadically exceeded the AGQS during previous review periods but have remained above the AGQS since first quarter 2009. Concentrations have steadily decreased since the fourth quarter of 2009 to a current value of 1.5 mg/L (first quarter 2012).

G35D—Dissolved ammonia concentrations in well G35D have frequently increased above the AGQS throughout its sampling history. During the current review period concentrations have fluctuated above and below the AGQS but have been below the AGQS consistently since third quarter 2010 and have been non-detect since first quarter 2011.

G37D—Concentrations in well G37D were above the AGQS from first quarter 1999 through first quarter 2002 at which time concentrations decreased below the AGQS. Concentrations remained below the AGQS until first quarter 2008 when they increased to a maximum concentration of 2.1 mg/L. Concentrations have since decreased to the most recent concentration of 0.49 mg/L (second quarter 2011).

G38S—Dissolved ammonia concentrations in well G38S have historically and consistently exceeded the AGQS. However, concentrations have been steadily decreasing since fourth quarter 2007 and except for second quarter 2011 (0.93 mg/L) have been below the AGQS since fourth quarter 2010.

G39S—Concentrations in well G39S consistently exceeded the AGQS from third quarter 1999 to second quarter 2007. However, since 2001 concentrations have been

decreasing and have been below the AGQS since the third quarter 2007. Well G39S was replaced by well R39S in January 2009 and the initial sampling was conducted second quarter 2009. Initially non-detect, concentrations increased to 42 mg/L (second quarter 2010) before decreasing to the current concentration of 12 mg/L (third quarter 2011).

G41M—Concentrations in well G41M have historically exceeded the AGQS, but during the current review period concentrations decreased below the AGQS (second quarter 2008 to second quarter 2010). Upon sampling third quarter 2010, concentrations increased to 2.3 mg/L and again during fourth quarter 2010 to 3.6 mg/L before decreasing below the AGQS during fourth quarter 2011. The decreasing trend has continued with the most recent concentration recorded at 0.18 mg/L (first quarter 2012).

G52M—With the exception of third and fourth quarters 2011 sampling events, dissolved ammonia concentrations in well G52M have been below the AGQS since inclusion into the monitoring program the fourth quarter 2009. Although a slight increasing trend is noted for this parameter, the dataset is of limited temporal extent and a definitive conclusion regarding trend cannot be made at this time. Additionally, the most recent (first quarter 2012) concentration is below the AGQS.

Prior to and during the current review period, concentrations of dissolved ammonia in several Lower Zone wells exceeded the AGQS. However, as shown by the trend graph provided in Appendix E, concentrations have decreased significantly during previous review periods and continued to decrease or have been stable throughout the current review period. No increasing trends are noted for any wells which have been reported exceeding the AGQS.

Arsenic, dissolved

Concentrations in all Lower Zone wells typically exceeded the AGQS (2 ug/L) prior to 2001, at which time concentrations in all but three wells decreased below the AGQS. During the current review period, dissolved arsenic concentrations have exceeded the AGQS (2 ug/L) in four Lower Zone wells (G38S, G39S/R39S, and G41M). Only these wells are discussed below.

G38S—Concentrations in well G38S were above the AGQS for the majority of sampling events until decreasing below the AGQS during first quarter 2010. Since first quarter 2010 the concentration of dissolved arsenic in well G38S has remained below the AGQS and has been consistently non-detect since first quarter 2011.

G39S/R39S—Dissolved arsenic concentrations in well G39S have historically and consistently been below the AGQS until third quarter 2008 (3.6 ug/L). Concentrations remained above the AGQS until sampling at well G39S ceased first quarter 2009. Concentrations in the replacement for well G39S (R39S) remained relatively stable above the AGQS until second quarter 2010 at which time concentrations decreased and have remained below the AGQS. Dissolved arsenic was not detected in well R39S during the most recent sampling event (third quarter 2011). Well R39S was dry the fourth quarter 2011 and first quarter 2012.

G41M—With the exception of second quarter 2007, concentrations in well G41M have been below the AGQS throughout the current review period. Dissolved arsenic has not been detected in well G41M since fourth quarter 2010.

Prior to the current review period, dissolved arsenic concentrations in several Lower Zone wells exceeded the AGQS. During the current review period concentrations of dissolved arsenic have exceeded the AGQS in only four of the Lower Zone wells. As shown by the trend graph provided in Appendix E, concentrations have decreased significantly during previous review periods and continued to decrease or have been stable throughout the current review period. No increasing trends are noted for any wells which have been reported exceeding the AGQS. As discussed in Section 5.2.1.1.1, arsenic is naturally occurring in groundwater and is highly sensitive to oxygen reducing conditions. The groundwater at the facility is unconfined and shallow. Movement beneath a structure (i.e., waste unit) is sufficient to cause anaerobic conditions, which can cause the arsenic concentrations to increase without any direct influence from the waste unit. Arsenic concentrations detected in downgradient wells do not necessarily indicate an impact from the waste unit.

Arsenic, total

Concentrations of total arsenic in several Lower Zone wells have exceeded the AGQS (10 ug/L) during the current review period. As illustrated in the trend graph contained in Appendix E, concentrations in several wells fluctuated significantly beginning the first quarter 2006. However, the increases above the AGQS have been short-term increases that subsequently decreased below the AGQS within one or two sampling events. Only wells that exhibited exceedences during the current review period (2007 to 2012) are discussed below.

G03M—Concentrations in well G03M have exceeded the AGQS only once since second quarter 1997. The exceedence of the AGQS was recorded during the first quarter 2012 sampling event (14 ug/L). No increasing trend is noted for this parameter in well G03M.

G18D—Total arsenic concentrations in well G18D have historically been below the AGQS but have increased above the AGQS (third quarter 2007 and first quarter 2011) as a result of the increased fluctuation beginning in 2006. For each of the two exceedences, concentrations have decreased below the AGQS the following quarter and there are no increasing trends noted for this parameter. Well G18D was abandoned due to development of the NEU.

G33D—Concentrations in well G33D have increased above the AGQS during previous review periods but have subsequently decreased the following quarter. Similar to previous review periods, the concentrations of total arsenic in well G33D have increased above the AGQS during first and second quarters 2011 (19 and 11 ug/L, respectively), decreased below the AGQS the third and fourth quarters of 2011, and increased again during the first quarter 2012 (21 ug/L). The concentrations significantly fluctuated in 2011, but no specific trend is apparent.

G34D—Concentrations in well G34D have historically and consistently been below the AGQS. However, during first quarter 2009 the concentration increased to 15 ug/L, exceeding the AGQS. The concentration decreased below the AGQS the following quarter where it has remained since.

G35D—Total arsenic concentrations in well G35D have significantly fluctuated above and below the AGQS during the current review period. Due to the range of fluctuation, no trend is apparent.

G38S—Concentrations in well G38S have fluctuated similar to other Lower Zone wells, which have exceeded the AGQS. The range of fluctuation became more pronounced later in the review period. Total arsenic concentrations exceeded the AGQS during first and fourth quarter 2011 sampling events (12 ug/L and 16 ug/L, respectively). However, as with several other Lower Zone wells, concentrations following a sharp increase subsequently decreased below the AGQS.

G39S - Total arsenic concentrations in well G39S exceeded the AGQS from third quarter 2008 to first quarter 2009, at which time well G39S was replaced by well R39S. The increasing trend continued in well R39S until second quarter 2010 (130 ug/L) at which time concentrations decreased. Total arsenic concentrations in well R39S have been below the AGQS since fourth quarter 2010 and no increasing trend is noted for this parameter.

G41M—Concentrations in well G41M have historically been recorded above the AGQS. An increasing trend noted during the previous review period ended with a maximum concentration of 170 ug/L during fourth quarter 2006 before decreasing and becoming stable, fluctuating above and below the AGQS. During the current review period total arsenic concentrations in well G41M have fluctuated but generally remained below the AGQS. Similar to other Lower Zone wells, no increasing trend is apparent for this parameter and the short-term exceedences of the AGQS are the result of fluctuation beginning in 2006.

As indicated by the trend graph contained in Appendix E, only concentrations from well G41M have consistently exceeded the subject AGQS during previous review periods. An increase in fluctuation beginning in 2006 in all Lower Zone wells has caused concentrations to periodically exceed the AGQS but exceedences have been short-lived, decreasing below the AGQS after one or two quarters with no increasing trends noted.

Boron, dissolved

As discussed previously, dissolved boron was designated as an indicator parameter in previous investigations (HSI Geotrans, 1999 & 1998) and one of the parameters used to delineate the GMZ extent as part of the 2004 application (Illinois EPA Application Log No. 2004-257). Dissolved boron concentrations in seven Lower Zone wells (G18D, G34D, G35D, G38S, G39S/R39S, and G41M) have exceeded the AGQS (98 ug/L) during the current review period. However, as indicated by the trend graph provided in Appendix E, decreasing or stable trends can be observed in nearly all GMZ wells.

G18D—Concentrations in well G18D have historically been below the AGQS but increased from 75 ug/L during first quarter 2008 to 160 ug/L second quarter 2008. Concentrations decreased steadily since second quarter 2008 and were below the AGQS by second quarter 2009. The decreasing trend continued until well G18D was abandoned July 2011 due to development of the NEU.

G34D—Dissolved boron concentrations in well G34D have been similar to concentrations in well G18D, increasing from 79 ug/L during fourth quarter 2007 to 140 ug/L during first quarter 2008. Concentrations decreased steadily since third quarter 2008 and were below the AGQS by second quarter 2009. Concentrations have continued to decrease below the AGQS in well G34D.

G35D—Concentrations in well G35D have exceeded the AGQS during previous review periods but have been decreasing steadily throughout the current review period. During fourth quarter 2007 the concentration was recorded as 410 ug/L, but was below the AGQS the following quarter.

G38S—Dissolved boron concentrations in well G38S have been stable to decreasing since 2000. Although concentrations have generally remained above the AGQS during previous review periods, concentrations decreased below the AGQS from fourth quarter 2010 to second quarter 2011. Upon sampling third quarter 2011 the concentration of dissolved boron had increased above the AGQS to 110 ug/L and increased again during fourth quarter 2011. The elevated concentration of dissolved boron in well G38S is within historic limits for the parameter and a concentration increase during one sampling event is insufficient to conclude a trend.

G39S—Dissolved boron concentrations in well G39S have been stable above the AGQS since 1998 but began increasing through third and fourth quarters of 2008 before decreasing. Well G39S was replaced by well R39S in January 2009 and concentrations were similar to those recorded in well G39S. Dissolved boron concentrations have steadily decreased in well R39S since third quarter 2009 and decreased below the AGQS upon sampling first quarter 2011. Concentrations have remained below the AGQS since.

G41M—Dissolved boron concentrations in well G41M have shown a steadily decreasing but fluctuating trend from 1,100 ug/L in 1998 to current concentrations below the AGQS. Concentrations have remained below the AGQS since first quarter 2008.

Prior to the current review period dissolved boron concentrations in several Lower Zone wells exceeded the AGQS. However, steadily decreasing trends can be observed in nearly all GMZ wells as indicated by the trend graph provided in Appendix E. With the exception of G38S, which has increased above the AGQS during the third and fourth quarter 2011 sampling events, no increasing trends are noted for any wells which have been reported exceeding the AGQS during the current review period.

Boron, total

Concentrations in six Lower Zone wells (G18D, G35D, G38S, G39S/R39S, and G41M) have exceeded the AGQS for total boron (200 ug/L) during the current review period.

G18D—Concentrations in well G18D have historically been below the AGQS, a trend that has continued throughout the current review period with the exception of an exceedence noted during third quarter 2007 (230 ug/L). Upon sampling the following quarter the concentration decreased below the AGQS to 37 ug/L. Since the concentration spike during third quarter 2007, concentrations of total boron in well G18D have remained stable below the AGQS until abandonment in July 2011.

G35D—Similar to well G18D, total boron concentrations in well G35D have historically been below the AGQS, a trend that has continued throughout the current review period with the exception of an exceedence noted during second quarter 2007 (430 ug/L). Upon sampling the following quarter the concentration decreased to 34 ug/L and has remained stable.

G38S—Total boron concentrations in well G38S have commonly exceeded the AGQS during previous review periods, remaining stable until second quarter 2004 at which time concentrations began increasing. Concentrations began decreasing second quarter 2005 with some fluctuation above and below the AGQS. However, since first quarter 2008, concentrations have significantly decreased and have consistently been below the AGQS since second quarter 2008.

G39S—Total boron concentrations in well G39S have historically been below the AGQS. However, concentrations increased above the AGQS during third quarter 2008 and increased until sampling was discontinued (first quarter 2009). Well G39S was replaced by well R39S in January 2009 and concentrations were similar to those recorded in well G39S. Although concentrations continued to increase until second quarter 2010, total boron concentrations (similar to dissolved boron concentrations) subsequently decreased and have been below the AGQS since fourth quarter 2010.

G41M—Total boron concentrations in well G41M, similar to dissolved boron concentrations, have shown a steadily decreasing but fluctuating trend since 1998. Although total boron concentrations have periodically exceeded the AGQS during the current review period, concentrations have remained stable below the AGQS since first quarter 2008.

Prior to the current review period total boron concentrations in several Lower Zone wells exceeded the AGQS. However, steadily decreasing trends can be observed in nearly all GMZ wells as indicated by the trend graph provided in Appendix E. With the exception of G39S/R39S, which has recently increased above the AGQS but subsequently displayed a decreasing trend, no increasing trends are noted for any wells which have been reported exceeding the AGQS during the current review period. Wells not discussed are those with total boron concentrations stable or decreasing below the AGQS.

Chloride, dissolved

Dissolved chloride was the original indicator parameter presented by Geotrans for delineating the GMZ in 1995. In later applications (Geotrans 1998 and 1999), it was concluded that chloride may not be as effective an indicator of leachate-derived compounds due to the possibility of other potential sources within the vicinity of the facility and was superseded with dissolved ammonia and dissolved boron. Concentrations in seven Lower Zone wells (G18D, G34D, G35D, G38S, G39S/R39S, and G41M) have exceeded the AGQS for dissolved chloride (87.51 mg/L) during the current review period.

G18D—Concentrations in well G18D have periodically fluctuated above the AGQS during previous review periods as well as the current review period. However, since the first quarter 2008, concentrations have been decreasing and have been below the AGQS since third quarter 2008.

G34D—Dissolved chloride concentrations in well G34D were stable below the AGQS until the first quarter 2004 sampling event. Concentrations increased through the fourth quarter 2007 (170 mg/L) at which time a significant and steady decreasing trend began. Concentrations have continued to decrease and have been below the AGQS since third quarter 2008.

G35D—Dissolved chloride concentrations in well G35D have historically been stable with periodic fluctuations (single event exceedences) above the AGQS. With the exception of a sporadic spike, concentrations have been below the AGQS since 2004. During the current review period concentrations have remained stable below the AGQS.

G38S—Concentrations in well G38S have historically fluctuated above the AGQS but have decreased since third quarter 2004. With the exception of first and second quarter 2010 and second quarter 2011, dissolved chloride concentrations have been below the AGQS in well G38S since first quarter 2009.

G39S—Concentrations in well G39S have historically remained above the AGQS with periodic decreases below the AGQS. As shown by the trend graph provided in Appendix E, fluctuation of the dissolved chloride concentrations increased after fourth quarter 2007 and continued until the final sampling event first quarter 2009. Concentrations in well R39S were similar to well G39S but fluctuated less and began decreasing after third quarter 2009. With the exception of second quarter 2011, concentrations have continued to decrease. Furthermore, during the current review period concentrations in well R39S have remained below the AGQS for three consecutive quarters.

G41M—Dissolved chloride concentrations in well G41M significantly decreased beginning fourth quarter 2002, and subsequently fluctuated above and below the AGQS. During the current review period concentrations have remained stable below the AGQS since first quarter 2008.

Prior to and during the current review period, concentrations of dissolved chloride in several Lower Zone wells exceeded the AGQS. However, the majority of exceedences above the AGQS are due to fluctuating concentrations, which do not obscure the decreasing trends that can be observed in all GMZ wells. No increasing trends are noted for any wells that have been reported exceeding the AGQS during the current review period.

Chloride, total

Trends and concentrations for total chloride are comparable to those seen for dissolved chloride; concentrations from the same wells were identified as exceeding the AGQS for total chloride (87.51 mg/L) during the current review period. With the exception of a sporadic one-quarter exceedence (second quarter 2011) in well G38S, concentrations of total chloride have been stable below the AGQS in all GMZ wells since third quarter 2010.

Nitrate as N, dissolved

Concentrations above the AGQS (11.74 mg/L) were recorded in five Lower Zone wells (G03M, G16M, G33D, G35D, and G36S) during the current review period. All five wells are located along Kilbuck Creek which flows through several agricultural areas upgradient to the facility. The creek not only receives direct runoff from agricultural fields during precipitation events, but also is a gaining creek during periods of low flow; allowing mixing of groundwater and surface water thereby receiving groundwater potentially impacted by nitrogen based fertilizers applied to the agricultural fields. Concentrations in several wells fluctuate considerably, many below the AGQS. The

exceedences referenced above and fluctuating concentrations are generally no greater than 12 mg/L and likely influenced by the creek.

Nitrate as N, total

Trends and concentrations for total nitrate are comparable to those seen for dissolved nitrate; concentrations from the same wells were identified as exceeding the AGQS for total nitrate (11.74 mg/L) during the current review period. As shown by the trend graph provided in Appendix E, the concentrations do fluctuate; however, almost all are below the AGQS. Both total and dissolved nitrate do not appear to have been impacted by the closure activities at the facility. Therefore, nitrate concentrations in the groundwater were not influenced by facility operations.

Potassium, total

Concentrations have exceeded the AGQS for total potassium (29.01 mg/L) in four Lower Zone wells (G35D, G38S, G41M, and R39S) during the current review period. However, with the exception of concentrations in well R39S during second and third quarter 2010, concentrations in all GMZ wells have been stable or decreasing below the AGQS since first quarter 2008. The significant decrease in concentrations in nearly all GMZ wells is readily apparent by visual inspection of the trend graph provided in Appendix E.

Organic Parameters (Lower Zone)

With the exception of a single exceedence of acetone in well G16M (fourth quarter 2009) and carbon disulfide in well G36S (fourth quarter 2010) organic parameter concentrations in all Lower Zone GMZ wells have been non-detect during the current review period. Each of the exceedences was recorded as non-detect the following quarter and concentrations are stable with no significant increasing or decreasing trends noted. Table 3 provides a summary of the exceedences during the current review period and Table 4 provides a table of the historical GMZ parameter analytical results.

5.2.2.1.2 Non-GMZ Parameters

During the current review period, some parameters not currently included in the GMZ list of parameters have exhibited concentrations exceeding the respective AGQS (Table 3). Trend graphs detailing the concentrations of the subject parameters in all Lower Zone wells are contained in Appendix E.

Inorganic Parameters (Lower Zone)

Chemical Oxygen Demand (COD)

Chemical oxygen demand (COD) is a measure of the amount of oxygen needed to fully oxidize an organic compound by the addition of a strong oxidizing agent under acidic conditions. The COD analysis is commonly used as an indirect measurement of the amount of organic compounds in water; it is not a specific chemical constituent and cannot differentiate between the type of organic present in a sample. The COD measurement exceeded the AGQS (50.04 mg/L) in well G41M during second quarter 2007 (confirmed by resample). However, the measurement was within the historic range of measurements of COD at well G41M and upon sampling second quarter 2008 had decreased to 6.9 mg/L.

Chromium, dissolved

The concentration of dissolved chromium in well G35D exceeded the AGQS (72 ug/L) during first quarter 2011. However, upon sampling the following quarter the parameter was not detected; the exceedence was not confirmed.

Lead, dissolved

The concentration of dissolved lead in well R39S exceeded the AGQS (4 ug/L) during third quarter 2010. However, upon sampling the following quarter the parameter was not detected; the exceedence was not confirmed.

Magnesium, dissolved

The concentration of dissolved magnesium exceeded the AGQS (170.41 mg/L) in Lower Zone well R39S during third quarter 2010. However, upon sampling the following quarter the concentration decreased below the AGQS and has since remained; the exceedence was not confirmed.

pH (field)

Field measurements of pH have increased above the AGQS range (5.4 to 8.1) in eight Lower Zone wells (G03M, G16M, G18D, G33D, G35D, G36S, G37D, and G41M) during the current review period. However, with the exception of fourth quarter 2011 and first quarter 2012 measurements in well G33D, all measurements were recorded within the permitted range during the following quarter. Furthermore, there are no increasing or decreasing trends apparent throughout the current review period.

Selenium, total

Concentrations of total selenium exceeded the AGQS (4 ug/L) in three Lower Zone wells (G35D, G38S, and G41M) during the current review period. The exceeding concentration recorded in G35D (second quarter 2007) was not confirmed by resample. Concentrations in wells G38S and G41M have periodically fluctuated above the AGQS during previous review periods. However, the exceedences of the AGQS during second quarter 2007 (confirmed by resample) decreased to non-detect during the second quarter 2008 sampling event. No other exceedences were recorded for this parameter in the subject wells and concentrations were stable throughout the current review period with no significant increasing trends noted.

5.2.3 Bedrock Zone

Previous investigations (Geotrans 1995, 1998, 1999) have shown that a slight upward gradient exists between the bedrock and the lower sand and gravel zone, making it unlikely that influences from landfill activities will affect groundwater quality within the bedrock. Wells G09M, G09D, G13D, G13S, G16D, G20D, and G41D are all screened within the dolomite underlying the facility. Wells G09M, G09D, G13S, G13D, and G20D are all upgradient to the Northern Unit and listed as background wells in the current operating permit. Several organic compounds (generally organic solvents) have historically been detected in bedrock wells G13S, G13D, G09M, and G09D. The subject detections have been largely attributed to conditions at the Acme Solvent site. As part of the 2004 GMZ evaluation, the Illinois EPA requested the area proximal to upgradient wells G09M and G09D be included in the GMZ due to elevated concentrations of 1,4-dichlorobenzene and total and dissolved iron. The modified vertical extent of the 2004 GMZ evaluation is presented in Figure 7. The vertical extent of the GMZ from the 2007 evaluation and

the current 2012 evaluation are presented in Figures 9 and 12, respectively. Trend graphs illustrating parameter concentrations are provided in Appendix F.

The following sections discuss parameters that have exceeded the AGQSs during the current review period only. Parameters and related wells in which concentrations do not exceed the AGQS are not discussed.

5.2.3.1 Parameter Specific Trends

5.2.3.1.1 GMZ Parameters

Inorganic Parameters (Bedrock Zone)

Ammonia as N, dissolved

Only concentrations of dissolved ammonia in Bedrock Zone wells G13D and G13S exceeded the AGQS (0.9 mg/L) during the current review period. Concentrations in both wells are currently stable above the AGQS. As previously discussed, wells G13D and G13S are upgradient to the Northern Unit and monitor groundwater representative of conditions to the east of the facility. The subject wells are nested; the “D” and “S” designations refer to the screen interval as being deep and shallow, respectively. Both wells are screened in the dolomite bedrock. As shown in the trend graph, the concentrations in the deep well exceed those of the shallow wells. The shallow well would expect to reflect higher concentrations than the deep well if the landfill unit were influencing the groundwater quality at that location. Given the upgradient location of the wells and the fact that the deep well contains higher concentrations than the shallow well, the ammonia concentrations appear due to an offsite source.

Arsenic, dissolved

Concentrations in Bedrock Zone wells G09D, G13D, and G13S exceeded the AGQS for dissolved arsenic (2 ug/L) during the current review period. Concentrations in all three wells are currently stable above the AGQS with some fluctuation. As previously discussed, wells G09D, G13D, and G13S are upgradient to the Northern Unit and therefore monitor groundwater representative of conditions to the east of the facility.

Arsenic, total

Concentrations of total arsenic exceeded the AGQS (10 ug/L) during the current review period in Bedrock Zone wells G13D, G13S, and G20D. As shown by the trend graph provided in Appendix F, concentrations in well G13D have fluctuated significantly above the AGQS throughout the current review period. Although concentrations in wells G13D and G13S have increased over the last few quarters, concentrations remain within historic limits for the parameter. Wells G13D, G13S, and G20D are upgradient to the Northern Unit and therefore monitor groundwater representative of conditions to the east of the facility. Well G20D is located approximately 700 feet west of the landfill facility closer to the Acme Solvent site.

Boron, dissolved

Concentrations of dissolved boron have been recorded exceeding the AGQS (98 ug/L) during the current review period in Bedrock Zone wells G09D, G13D, and G13S. Concentrations have consistently and historically been below the AGQS in well G09D with the exception of first quarter 2007 (110 ug/L). However, upon sampling the

following and subsequent quarters, concentrations decreased and have remained stable below the AGQS. Dissolved boron concentrations in well G13D have historically been stable below the AGQS until third quarter 2007 at which time concentrations began significant fluctuation above the AGQS. After peaking the third quarter 2010, concentrations have decreased significantly to the current concentration of 480 ug/L (first quarter 2012). Concentrations in well G13S, similar to well G13D, have historically been below the AGQS with periodic fluctuations above the AGQS until fourth quarter 2008 at which time concentrations increased. After reaching a maximum concentration of 470 ug/L during the second and third quarter 2011 sampling events, concentrations have decreased to the current concentration of 250 ug/L (first quarter 2012). As previously discussed, wells G09D, G13D, and G13S are upgradient to the Northern Unit and therefore monitor groundwater representative of conditions to the east of the facility. The increasing concentrations of dissolved boron during the current review period may be indicative of changing background groundwater quality. As discussed above, G13S and G13D are nested wells. Similar to dissolved ammonia concentrations, the highest dissolved boron concentrations occurs in the deep well (G13D). The screen interval for G13D is a greater distance from the waste unit. Additionally, nested wells G09M and G09D are located closer to the Northern Unit than G13S and G13D (See Figure 1). If the Northern Unit were affecting the groundwater quality at G13S and G13D, impacts would be detected at higher concentrations in G09M and G09D. However, this is not occurring.

Boron, total

Trends and concentrations for total boron are comparable to those seen for dissolved boron; concentrations from the same wells (except for G09D) were identified as exceeding the AGQS for total boron (200 ug/L) during approximately the same time period within the current review period. Similar to dissolved concentrations, total boron concentrations have most recently been decreasing.

Chloride, dissolved

Concentrations of dissolved chloride have exceeded the AGQS (87.51 mg/L) in Bedrock Zone wells G09D, G09M, G13D, and G13S during the current review period.

G09D—Concentrations in well G09D have occasionally exceeded the AGQS until first quarter 2009 at which time concentrations remained above the AGQS. Since second quarter 2011 concentrations have decreased below the AGQS and continue to decrease to the current concentration of 65 mg/L (first quarter 2012).

G09M—As shown by the trend graph provided in Appendix F, dissolved chloride concentrations in upgradient Bedrock Zone well G09M have been steadily increasing since commencement of sampling first quarter 1997. Currently (first quarter 2012) the concentration was recorded as 600 mg/L.

G13D—Dissolved chloride concentrations in well G13D were stable slightly above the AGQS during the previous review period and then decreased below the AGQS from second quarter 2007 to fourth quarter 2008 (with the exception of fourth quarter 2007). Concentrations have fluctuated above the AGQS since first quarter 2009. An uncharacteristic spike occurred during second quarter 2010 (830 mg/L), followed by a significant decrease in concentrations over the next four quarters. Dissolved chloride

concentrations in well G13D have continued to decrease to the current concentration of 160 mg/L (first quarter 2012).

G13S—Dissolved chloride concentrations in well G13S have increased with respect to previous review periods but remained relatively stable during the current review period. As shown by the trend graph provided in Appendix F, concentrations in well G13S increased above the AGQS during third quarter 2007 and reached a maximum concentration during second quarter 2008 (220 mg/L). Concentrations then decreased until second quarter 2010 at which time concentrations began increasing again. Currently, the concentration of dissolved chloride in well G13S is decreasing but remains above the AGQS. It is anticipated the dissolved chloride concentration will decrease below the AGQS within the next two quarters.

The exceedences of dissolved chloride concentrations above the AGQS have primarily occurred during the current review period in Bedrock Zone wells G09D, G09M, G13D, and G13S. However, all Bedrock Zone wells with exceedences above the AGQS are upgradient wells for the Northern Unit which monitor groundwater conditions to the east of the facility. The increasing concentrations of dissolved chloride during the current review period, similar to boron concentrations, are indicative of background groundwater quality.

Chloride, total

Trends and concentrations for total chloride are comparable to those seen for dissolved chloride; concentrations from the same wells were identified as exceeding the AGQS for total chloride (87.51 mg/L) during approximately the same time period within the current review period.

Nitrate as N, total

Concentrations of total nitrate in all Bedrock Zone GMZ wells have historically remained below the AGQS (11.74 mg/L). During the current review period the concentration of total nitrate increased above the AGQS in well G41D (second quarter 2009). However, upon sampling the following quarter the concentration decreased below the AGQS where it has remained since; the exceedence was not confirmed. No other exceedences were recorded for this parameter in the subject wells and concentrations have been stable throughout the current review period with no significant increasing trends noted.

Potassium, total

Concentrations of total potassium have periodically exceeded the AGQS (29.01 mg/L) during the current review period in Bedrock Zone wells G13D and G13S. Concentrations in the subject wells have historically remained stable below the AGQS until the current review period at which time concentrations began fluctuating significantly above and below the AGQS. Wells G13D and G13S are both upgradient to the Northern Unit and monitor groundwater representative of conditions to the east of the facility. The fluctuating concentrations above the AGQS are indicative of background groundwater quality. As discussed above, G13S and G13D are nested wells. Similar to dissolved ammonia and boron concentrations, the highest dissolved boron concentrations occurs in the deep well (G13D). The screen interval for G13D is a greater distance from the waste unit.

Sodium, total

Concentrations of total sodium have exceeded the AGQS (164.79 mg/L) during the current review period in wells G09D, G09M, and G13D. Concentrations in well G09D have historically remained stable below the AGQS until increasing fourth quarter 2008. A steady concentration increase is noted for total sodium with the exception of a concentration spike above the AGQS during first quarter 2010. Upon sampling the following quarter, concentrations decreased and continued to follow the previously established increasing trend. Concentrations have been decreasing since second quarter 2011 to the current concentration of 50 mg/L (first quarter 2012). Total sodium concentrations in well G09M have been steadily increasing (below the AGQS) since commencement of sampling during second quarter 1997. Concentrations have continued to increase during the current review period and have been above the AGQS since second quarter 2008. The current concentration recorded first quarter 2012 (270 mg/L) is the maximum concentration of total sodium in well G09M. Concentrations in well G13D have historically remained stable below the AGQS until the current review period at which time significant fluctuation is noted. Concentrations increased since second quarter 2008 until reaching a maximum concentration of 730 mg/L during second quarter 2010. Since second quarter 2010 concentrations have continued to decrease and have been below the AGQS since second quarter 2011.

Total sodium concentrations have generally been increasing during the previous review periods as well as current review period in Bedrock Zone GMZ wells G09D, G09M, and G13D. Since the only wells with concentrations exceeding the AGQS are upgradient to the Northern Unit, the concentrations are indicative of background groundwater quality.

Organic Parameters (Bedrock Zone)

1,4-Dichlorobenzene

Concentrations of 1,4-Dichlorobenzene have exceeded the AGQS (5 ug/L) in Bedrock Zone well G09D, G09M, and G13S during the current review period. Concentrations in well G09D have consistently exceeded the AGQS until most recently (fourth quarter 2011) at which time concentrations decreased to 1.1 ug/L. Concentrations in well G09M have been detected but have remained stable throughout the current review period until fourth quarter 2010. The concentration decreased below the AGQS during second quarter 2011, but again exceeded the AGQS during fourth quarter 2011. A similar trend in 1,4-dichlorobenzene concentrations is noted for G13S which have been detected since fourth quarter 2010 and have exceeded the AGQS since second quarter 2011. As previously discussed, wells G09D, G09M, and G13S are upgradient to the Northern Unit and therefore monitor groundwater conditions to the east.

Tetrahydrofuran

Concentrations of tetrahydrofuran have exceeded the AGQS (42 ug/L) in well G13D during the second quarter 2009 and second quarter 2010 sampling events. However, upon sampling the following quarter, concentrations have decreased below the AGQS and have remained since. Well G13D is upgradient to the Northern Unit.

5.2.3.1.2 Non-GMZ Parameters

During the current review period, some parameters not currently included in the GMZ list of parameters have exhibited concentrations exceeding the respective AGQS (Table 3). Trend

graphs detailing the concentrations of the subject parameters in all Bedrock Zone wells are contained in Appendix F.

Inorganic Parameters (Bedrock Zone)

Lead, dissolved

Concentrations of dissolved lead have exceeded the AGQS (4 ug/L) during the current review period in wells G09D and G13D. Concentrations in wells G09D and G13D have consistently been non-detect until second quarter 2011 and third quarter 2010, respectively. However, upon sampling the following quarter the concentration of dissolved lead was either non-detect (G09D) or below the AGQS (G13D). Dissolved lead concentrations in wells G09D and G13D, which are both upgradient to the Northern Unit and monitor groundwater conditions to the east, are currently non-detect.

Magnesium, dissolved

Concentrations of dissolved magnesium have been below the AGQS (170.41 mg/L) throughout the current review period in all Bedrock Zone wells with the exception of an exceedence recorded during second quarter 2010 in well G13D. Since second quarter 2010 concentrations have stabilized at 110 mg/L.

Magnesium, total

Concentrations of total magnesium exceeded the AGQS (109.5 mg/L) in upgradient well G13D during second quarter 2007 (confirmed by resample). However, the concentration decreased below the AGQS during the following sampling event (second quarter 2008).

Manganese, dissolved

Concentrations of dissolved manganese exceeded the AGQS (1,479.53 ug/L) in upgradient wells G13D and G13S during the current review period. Concentrations in wells G13D and G13S have historically been below the AGQS until third quarter 2007 and fourth quarter 2007, respectively. However, upon sampling the following quarter the concentration of dissolved manganese decreased below the AGQS.

Mercury, dissolved

Concentrations of dissolved mercury in upgradient well G13S exceeded the AGQS (0.2 ug/L) during second quarter 2011 (0.24 ug/L). However, upon sampling the following quarter, concentrations returned to non-detect; the detection was not confirmed.

pH (field)

Measurements of pH in Bedrock Zone wells have generally fallen within the permitted range (5.4-8.1 units) during the current review period. Measurements in upgradient well G20D were above the range during third quarter 2007 (8.28 units), second quarter 2008 (8.62 units), and fourth quarter 2008 (8.11 units). Measurements of pH have decreased and stabilized within the permitted range since fourth quarter 2008. Measurements of pH in well G41D have been within the permitted range throughout the current review period with the exception of third quarter 2007 (8.22 units). Measurements of pH have been within the permitted range since the single exceedence.

Selenium, total

Concentrations of total selenium exceeded the AGQS (4 ug/L) in upgradient wells G09M and G13D during the current review period. However, the only sampling events during which total selenium was analyzed for were during second quarter 2007 and second quarter 2008. Concentrations from well G09M exceeded the AGQS during both sampling events and well G13D exceeded the AGQS during only the second quarter 2007 sampling event.

Sulfate, dissolved

Concentrations of dissolved sulfate in upgradient well G13D fluctuated above and below the AGQS (360 mg/L) until third quarter 2009. Concentrations have not exceeded the AGQS since third quarter 2009.

Sulfate, total

Concentrations of total sulfate exceeded the AGQS (179.37 mg/L) in upgradient wells G13D and G13S during the current review period. However, the only sampling events during which total sulfate were analyzed for were during second quarter 2007 and second quarter 2008. Concentrations from well G13D exceeded the AGQS during second quarter 2007 (unconfirmed by resample) and again during second quarter 2008. Concentrations in well G13S also exceeded the AGQS during second quarter 2007 (confirmed by resample) but were recorded below the AGQS during second quarter 2009.

Vanadium, total

Concentrations of total vanadium exceeded the AGQS (100 ug/L) in well G13D during the second quarter 2007 sampling event (confirmed by resample). Concentrations decreased below the AGQS during subsequent sampling events.

Organic Parameters (Bedrock Zone)

Acetone

Concentrations of acetone have exceeded the AGQS (10 ug/L) in Bedrock Zone wells G09D and G13D during the current review period. However, upon sampling the following quarter concentrations decreased below the AGQS. Concentrations in both upgradient wells are stable with no significant increasing or decreasing trends noted.

Benzene

Concentrations of benzene have exceeded the AGQS (2.8 ug/L) in Bedrock Zone wells G13D and G13S during the current review period. Concentrations in G13D have historically been non-detect until second quarter 2011 (1.7 ug/L). Upon sampling during fourth quarter 2011 the concentration increased above the AGQS to 3.7 ug/L. However, upon sampling the following quarter (first quarter 2012) the concentration decreased to 2.7 ug/L. Similar to well G13D, benzene concentrations in well G13S have historically been non-detect until the current review period. Concentrations have increased above the AGQS since fourth quarter 2010. Both wells are upgradient and monitor groundwater representative of conditions to the east of the Northern Unit.

Carbon Disulfide

Concentrations of carbon disulfide have exceeded the AGQS (5 ug/L) in wells G09D, G13S, and G20D during the current review period. However, the exceeding concentrations were all recorded during fourth quarter 2010 after which time concentrations decreased to non-detect the following quarter and therefore were not confirmed. Concentrations in each well have been non-detect since fourth quarter 2010.

Chlorobenzene

Concentrations of chlorobenzene have exceeded the AGQS (5 ug/L) in Bedrock Zone wells G09D, G09M, G13D, and G13S during the current review period.

G09D—Concentrations in well G09D have been detected throughout the current review period and increased above the AGQS during second quarter 2009. However, the exceedence was not confirmed. Concentrations increased above the AGQS again during second quarter 2010 and after reaching a maximum concentration of 11 ug/L during fourth quarter 2010, decreased but remained above the AGQS.

G09M—Concentrations in well G09M have also been detected throughout the current review period, increasing above the AGQS since fourth quarter 2010. A maximum concentration of 6.6 ug/L was recorded most recently during fourth quarter 2011.

G13D—Chlorobenzene concentrations in well G13D have been detected since second quarter 2010 and have been above the AGQS since second quarter 2011. A maximum concentration of 14 ug/L was recorded most recently during fourth quarter 2011.

G13S—Chlorobenzene concentrations in well G13S have been detected since fourth quarter 2009 and have exceeded the AGQS consistently since second quarter 2010. A maximum concentration of 29 ug/L was recorded most recently during fourth quarter 2011. As previously discussed, wells G09D, G09M, G13D, and G13S are upgradient to the Northern Unit and monitor groundwater conditions to the east. The increasing trends noted for chlorobenzene in the subject wells are likely indicative of background groundwater quality.

cis-1,2-Dichloroethene

Concentrations in well G20D have consistently been above the AGQS (5 ug/L) during previous review periods as well as the current review period. However, no increasing trends are present and the current concentrations are within historic limits for this parameter. Well G20D is located east of Lindenwood road (approximately 700 feet east of the Northern Unit), upgradient to the Northern Unit, and monitors groundwater representative of conditions to the east of the facility. This compound is also an organic solvent likely attributable to the Acme Solvent site.

Methylene Chloride

Concentrations of methylene chloride have exceeded the AGQS (8 ug/L) in well G09M during the current review period. However, concentrations have consistently been non-detect with the exception of second quarter 2007. The exceedence recorded during second quarter 2007 was not confirmed by resample and concentrations have not been detected since that time. Methylene chloride is used in

the laboratory during the analyses process. Given the one-time detection, it is likely the second quarter 2007 result was a laboratory artifact.

6. GMZ EVALUATION

An evaluation of the GMZ extent has been completed. Consistent with the 1995, 2004, and 2007 applications, the horizontal and vertical extent of the GMZ varies by constituent. Thus, the GMZ was defined by the constituents that encompass the largest area and include all detectable leachate components above their respective AGQs. Each GMZ parameter that was detected above the applicable AGQS was identified on a concentration exceedence map such that the extent of the groundwater concentrations present could be determined. The referenced maps are contained in Appendix G (Upper Zone) and Appendix H (Lower Zone). All downgradient bedrock wells exhibited groundwater concentrations for the GMZ parameters below their respective AGQs with the exception of total nitrate in well G41D. As noted in the discussion regarding GMZ parameters in the Bedrock Zone (Section 5.2.3.1.1), the exceedence of the AGQS for total nitrate in well G41D was not confirmed by resample and the concentration subsequently decreased below the AGQS upon sampling the following quarter (third quarter 2009). Therefore, no concentration exceedence maps have been generated for the Bedrock Zone.

6.1 Upper Zone

The parameters used to establish the extent of the GMZ were evaluated in prior sections of this report to verify the concentrations were associated with the facility and not attributable to temporal variability or offsite sources. All individual GMZ parameters have been compared with the 2004 and 2007 GMZ boundaries to determine whether the affected area has increased or decreased in size. The 2007 Upper Zone GMZ extent map, provided originally as Figure 9 of Application Log No. 2007-181, was revised June 2008 in an addendum and provided as Figure 2. The revised GMZ extent map from June 2008 (for both the Upper and Lower Zones) is provided herein as Figure 8. The approximated extents of parameter specific concentrations exceeding the AGQs in the Upper Zone are contained in Appendix G.

The 2004 GMZ boundary in the Upper Zone was largely controlled by four parameters (arsenic, ammonia, boron, and chloride) with generally the same limits of occurrence. The 2007 GMZ boundary was largely controlled by three primary parameters (arsenic, ammonia, and boron). As shown by the composite concentration exceedence map provided as Figure G-8 in Appendix G, the 2012 GMZ boundary appears to be controlled by arsenic. The occurrence of total arsenic generally dictates the shape of the horizontal extent of the Upper Zone GMZ (Figure G-2 in Appendix G), encompassing well G41S. The 2012 extent of arsenic is nearly the same as illustrated in the 2004 GMZ evaluation with the exception of the area near R03S, in which concentrations of arsenic were below the AGQS during first quarter 2012. Although well G40S was dry at the time of sampling, concentrations had decreased below the AGQS prior to the well becoming dry. Therefore, the extent as shown does not include well G40S. Furthermore, due to the direction of groundwater movement in the areas west and north of Kilbuck Creek, which have been shown to be northward, the extent of total arsenic as shown does not include wells G52S and G54S. As stated previously, arsenic is naturally occurring in groundwater and is highly sensitive to oxygen reducing conditions. The groundwater at the facility is unconfined and shallow. Movement beneath a structure (i.e., waste unit) is sufficient to cause anaerobic conditions, which can cause the arsenic concentrations to increase without any direct influence from the waste unit. Arsenic concentrations detected in downgradient wells do not necessarily indicate a direct impact from the waste unit.

The 2012 extent of ammonia has decreased significantly from the 2004 and 2007 extents (Figure G-1 in Appendix G) resulting in a reduction of the perimeter to the southwest, west, and northwest of the Northern Unit. Although there were no exceedences above the AGQS for ammonia during first quarter 2012, concentrations in wells G40S and G51S (dry at the time of sampling) were above the AGQS when last sampled. Therefore, the two wells have been included within the GMZ extent.

The occurrence of boron decreased significantly from the 2004 and 2007 extents (Figure G-3 in Appendix G). Concentrations in R03S, G34S, G35S, and G41S decreased resulting in a reduction of the perimeter to the west and northwest of the Northern Unit. Although G37S was inaccessible during the time of sampling, concentrations of arsenic (dissolved and total) were consistently below the AGQS for several sampling events; therefore, the 2012 extent of boron excludes G37S and is limited to the north of the Northern Unit (encompassing wells G40S and G51S). Although wells G40S and G51S were dry at the time of sampling, concentrations were above the AGQS when last sampled. Therefore, the two wells have been included within the GMZ extent.

Figure G-4 in Appendix G defines the extent of chloride concentrations in the Upper Zone. The extent of chloride is similar to that of ammonia, boron, and potassium. However, concentrations of total chloride exceeded the AGQS in well R42S during first quarter 2012. Exceedences of the AGQS in 2012 do not extend to well G41S and therefore the west and northwest GMZ perimeters have been reduced from the 2007 boundary. Concentrations of chloride decreased below the AGQS in well G34S and although inaccessible during the time of sampling, concentrations in well G37S were below the AGQS for several sampling events. Therefore, the 2012 perimeter excludes the two wells.

With the exception of dissolved and total nitrate in well G130, there have been no additional parameters exceeding their respective AGQSs during 2012; the revised perimeters for total potassium, total sodium, and 1,4-dichlorobenzene include well G51S (Figures G-5 through G-7 of Appendix G). Although well G51S was dry at the time of sampling, concentrations of the subject parameters were exceeding the AGQS when last sampled.

The overall horizontal extent of the Upper Zone GMZ has not changed significantly since 2007, although a significant reduction in the recorded concentrations and individual parameter extents is evident (Figures G-1 through G-7 in Appendix G). The lines depicted in Figure G-8 in Appendix G represent a compilation of total and dissolved concentrations which exceeded the AGQSs. Figure 10 identifies the actual extent of the 2012 GMZ based on the outermost extent of the parameters exceeding the AGQS within the Upper Zone. With the exception of total arsenic in wells G52S and G54S, the outermost extent incorporates all areas exhibiting concentrations above the permitted AGQSs and represents the furthest extent of those elevated concentrations. It should be noted that “clean” areas (areas where concentrations of the GMZ parameters are below the permitted AGQSs) exist within the revised GMZ extent. The revised GMZ boundaries do not constitute an increase in the size of the GMZ.

6.2 Lower Zone

In addition to determining extent, the GMZ parameters were used to verify the source of the elevated concentrations was associated with the facility and not attributable to temporal variability or off-site sources. All individual GMZ parameter extents have been shown in comparison to the 2004 and 2007 GMZ boundaries to determine whether the impacted area has increased or decreased in size. The 2007 Lower Zone GMZ extent map, originally provided as

Figure 10 of Application Log No. 2007-181, was revised in an addendum (June 2008) and was provided as Figure 2. The revised GMZ extent map from June 2008 (for both the Upper and Lower Zones) is provided herein as Figure 8. The approximated extents of parameter specific concentrations exceeding the AGQSs in the Lower Zone are contained in Appendix H.

The occurrence of dissolved ammonia and total arsenic generally dictates the shape of the horizontal extent of the Lower Zone GMZ (Figures H-1, and H-2 of Appendix H). Elevated concentrations of dissolved ammonia were noted only in well G34D during the first quarter 2012 sampling event. Although well R39S was dry at the time of sampling, dissolved ammonia concentrations were exceeding the AGQS when last sampled and well G34S is therefore encompassed by the GMZ extent. The shift in the concentration of dissolved ammonia from well G16M to well G34D may be the result of reduction and migration in the downgradient direction. Since wells G38S, G41M, and G16M are no longer exceeding the AGQS the extent of exceedence for ammonia has decreased significantly from 2007.

Total arsenic concentrations exceeded the AGQS in wells G33D, G35D, and G38S. As shown in Figure H-2 of Appendix H, exceedences of the AGQS have previously been confined to wells G41M and G38S. The increased extent of total arsenic exceedences in wells west of Kilbuck Creek (wells G33D and G35D) and east of Kilbuck Creek (wells G03M and G38S) are due to periodic fluctuations above the AGQS.

As in the 2004 and 2007 extents, boron was not detected above the AGQS west of Kilbuck Creek. Since the 2007 evaluation, concentrations have decreased in GMZ wells east of Kilbuck Creek and as a result, the 2012 GMZ boron extent excludes all GMZ wells. Similar to boron concentrations, chloride concentrations have also decreased resulting in exclusion of all GMZ wells from the 2012 chloride extent.

Although occasional exceedences of the nitrate AGQS have been recorded in Lower Zone monitoring wells during the current review period, no extent for the GMZ has been determined. The sporadic elevated concentrations are likely the result of a hydraulic connection between the groundwater and surface water of Kilbuck Creek and the associated wetland area.

The overall horizontal extent of the Lower Zone GMZ has not changed significantly since 2007 although a reduction in the recorded concentrations and individual parameter extents is evident (Figures H-1 through H-5 in Appendix H). The lines depicted in Figure H-6 in Appendix H represent a compilation of total and dissolved concentrations which exceed the AGQSs. Figure 11 identifies the actual extent of the 2012 GMZ based on the outermost extent of the parameters exceeding the AGQS within the Lower Zone. The outermost extent incorporates all areas exhibiting concentrations above the permitted AGQSs and represents the furthest extent of those elevated concentrations. It should be noted that “clean” areas (areas where concentrations of the GMZ parameters are below the permitted AGQSs) exist within the revised GMZ extent. The revised GMZ boundaries do not constitute an increase in the size of the GMZ.

6.3 Bedrock Zone

In 1995 it was determined that contamination of the bedrock had not occurred beneath or downgradient to the Northern Unit. However, as part of the 2004 GMZ evaluation, the Illinois EPA requested the area proximal to upgradient wells G09M and G09D be included in the GMZ due to elevated concentrations of several inorganic parameters and 1,4-dichlorobenzene. Based on analytical data from the current review period, concentrations have not been detected

above the AGQS in any downgradient Northern Unit Bedrock Zone wells (i.e., G16D and G41D). The GMZ extent will remain as permitted in the 2004 GMZ evaluation.

7. CONCLUSIONS AND RECOMMENDATIONS

As discussed in Section 1, the 1995 Permit Renewal incorporated the remedial actions chosen to remedy Winnebago Landfill's impacted groundwater. The GIA included in the application was directed toward assessing the potential impacts of the facility after completion of the remedial activities (final cover and leachate/gas extraction systems) and was used to evaluate the effectiveness of the remedial design. Final cover was completed in July 2001 and the necessary upgrades to the leachate/gas extraction system were completed in 2002, finalizing the approved remedial measures. The GIA stated that the existing impacted groundwater would take an estimated five to ten years to achieve background concentrations. It was inferred that this timeline would commence upon completion of the remediation systems. Therefore, the effect of the remedial measures would become apparent sometime between 2007 and 2012. Although a few parameters are still detected at concentrations above the AGQSSs, significant improvements to groundwater quality are evident as demonstrated by the decreases in individual parameter concentrations and GMZ extents. In addition, the organic constituents which prompted the remedial actions are typically not detected in groundwater downgradient of the facility. Based on the number of wells in and surrounding the Northern Unit and their respective screened intervals and parameter lists, no additional investigations are proposed at this time. Evaluation of the GMZ should continue as previously permitted in Condition VIII.23 of Permit No. 1991-138-LF, Modification 53. The GMZ shall continue to be monitored in accordance with current requirements. In the event a modification to the remedial performance monitoring program is necessitated, a permit application will be submitted identifying the subject changes.

TABLES

Table 1
Winnebago Landfill
Surface Water Exceedences
First Quarter 2007 - First Quarter 2012

| Well ID | Parameter | Units | GW List | AGQS | 1stQtr07 | 2ndQtr07 | 3rdQtr07 | 4thQtr07 | 1stQtr08 | 2ndQtr08 | 3rdQtr08 | 4thQtr08 | 1stQtr09 | 2ndQtr09 | 3rdQtr09 |
|---------|---------------------------------|-------|---------|-----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| SG1 | 1,1-Dichloroethene | ug/l | G2 | 2.5 | | < 1 | | | | < 1 | | 8 | | < 1 | |
| SG3 | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | 0.098 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 |
| SG4 | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.13 | < 0.09 | < 0.09 | < 0.09 | 0.12 | < 0.09 | < 0.09 | 0.55 | 0.18 | < 0.09 | |
| SG3 | Atrazine | ug/l | | 3 | | < 0.2 | | | | 3.9 | < 0.2 | | | | |
| SG1 | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 12 | H 16 | 7.4 | 5.6 | 11 | 12 | 8.9 | 7.2 | 8.4 | 9.5 | 11 |
| SG3 | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 13 | H 16 | 7 | 6.4 | 12 | 13 | 9.6 | 7.6 | 9 | 9.4 | 10 |
| SG4 | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | H 13 | 17 | 7.8 | 7.9 | 12 | 12 | 9.2 | 7.4 | 9 | 9.3 | |
| SG1 | Nitrate as N, total | mg/l | GMZ | 11.7389 | 12 | 17 | 7.5 | 5.7 | 11 | 13 | 9 | 7.4 | 9.6 | 10 | 11 |
| SG3 | Nitrate as N, total | mg/l | GMZ | 11.7389 | 13 | 17 | 7 | 5.9 | 12 | 14 | 9.5 | 7.5 | 9.2 | 9.9 | 10 |
| SG4 | Nitrate as N, total | mg/l | GMZ | 11.7389 | H 13 | 17 | 7.8 | 7.7 | 12 | 12 | 9.2 | 7.4 | 9 | 9.4 | |
| SG1 | pH (field) | units | G1 | 5.4 - 8.1 | 7.97 | 7.53 | 8.39 | 7.95 | 7.79 | 7.58 | 6.86 | 8.19 | 7.07 | 7.5 | 7.84 |
| SG3 | pH (field) | units | G1 | 5.4 - 8.1 | 8.07 | 7.55 | 8.62 | 7.92 | 7.9 | 8.04 | 7.16 | 8.33 | 7.56 | 7.5 | 7.83 |
| SG4 | pH (field) | units | G1 | 5.4 - 8.1 | 7.86 | 7.51 | 8.66 | 8.23 | 7.8 | 7.51 | 7.21 | 8.02 | 7.6 | 8.1 | |
| SG3 | Polychlorinated Biphenyls(PCBs) | ug/l | | 2.5 | | < 0.5 | | | | 3.9 | | | | | |

| Well ID | Parameter | Units | GW List | AGQS | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|---------|---------------------------------|-------|---------|-----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| SG1 | 1,1-Dichloroethene | ug/l | G2 | 2.5 | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| SG3 | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | < 0.09 | | < 0.09 | < 0.09 | < 0.09 | 3.1 | < 0.1 | < 0.1 | < 0.1 |
| SG4 | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | 0.85 | 3.1 | < 0.09 | 0.23 | 0.26 | < 0.1 | < 0.1 | | |
| SG3 | Atrazine | ug/l | | 3 | | | | | | | | | | |
| SG1 | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 6.1 | 8.1 | 7.1 | 7.4 | 5.7 | | 7.7 | 6.5 | | |
| SG3 | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 6 | 7.6 | | 8.2 | 6.8 | 5.9 | 7.4 | 6.7 | | 7.9 |
| SG4 | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 6 | 8.1 | 6.8 | 7.3 | 6 | 6.7 | 7.5 | 6.5 | | |
| SG1 | Nitrate as N, total | mg/l | GMZ | 11.7389 | 6 | 8.6 | 7.1 | 7.4 | 5.7 | | 7.4 | 6.5 | 8.7 | |
| SG3 | Nitrate as N, total | mg/l | GMZ | 11.7389 | 6.1 | 7.9 | | 7.7 | 7.1 | 6 | 7.7 | 6.6 | 8.9 | 7.8 |
| SG4 | Nitrate as N, total | mg/l | GMZ | 11.7389 | 6 | 8.2 | 6.8 | 7.3 | 5.8 | 6.4 | 7.5 | 6.3 | | |
| SG1 | pH (field) | units | G1 | 5.4 - 8.1 | 7.09 | 8.27 | 7.68 | 6.9 | 6.99 | | 7.95 | 7.41 | 6.95 | |
| SG3 | pH (field) | units | G1 | 5.4 - 8.1 | 7.13 | 7.82 | 7.82 | 7.59 | 8.24 | 7.3 | 8.48 | 7.36 | 7.76 | 7.07 |
| SG4 | pH (field) | units | G1 | 5.4 - 8.1 | 7.11 | 8.24 | 7.6 | 7.77 | 7.45 | 7.31 | 8.43 | 7.61 | | |
| SG3 | Polychlorinated Biphenyls(PCBs) | ug/l | | 2.5 | | | | | | | | | | |

Table 2
Winnebago Landfill
GMZ Wells and Parameters

| GMZ Wells | | |
|---|------------|------------------------|
| Upper Zone | Lower Zone | Bedrock Zone |
| (G119) | G03M | G09D |
| G130 | G16M | G09M |
| (G15S) | (G18D) | G13D |
| G17S | G33D | G13S |
| (G18S) | G34D | (G14D) |
| G33S | G35D | G16D |
| G34S | G36S | G20D |
| G35S | G37D | G41D |
| G37S | G38S | |
| G40S | (G39S) | |
| G41S | R39S | |
| G50S | G41M | |
| G51S | G52M | |
| G52S | G54M | |
| G54S | | |
| R03S | | |
| R42S | | |
| SG1+ | | |
| SG3+ | | |
| SG4+ | | |
| <p>() Well has been abandoned and/or replaced</p> <p>- G14D was abandoned in 2005</p> <p>- G15S was replaced by G51S in December 2008</p> <p>- G119 was replaced by G50S in December 2008</p> <p>- G39S was replaced by R39S in January 2009</p> <p>- G18S and G18D were abandoned July 2011</p> <p>+ Surface water collection point</p> | | |
| GMZ Parameters | | |
| Quarterly | | Annual |
| Ammonia as N, dissolved | | 1,2,3-Trichlorobenzene |
| Ammonia as N, total | | 1,2,4-Trichlorobenzene |
| Arsenic, Dissolved | | 1,4-Dichlorobenzene |
| Arsenic, total | | Ethylbenzene |
| Barium, total | | Tetrahydrofuran |
| Boron, Dissolved | | |
| Boron, total | | |
| Chloride, Dissolved | | |
| Chloride, total | | |
| Fluoride, total | | |
| Nitrate as N, dissolved | | |
| Nitrate as N, total | | |
| Potassium, total | | |
| Sodium, total | | |

Table 3
Winnebago Landfill
Northern Unit AGQS Exceedences

| Zone | Location | Well ID | Parameter | Units | GW List | Type | AGQS | 1stQtr07 | 1stQtr07re | 2ndQtr07 | 2ndQtr07re | 3rdQtr07 | 4thQtr07 | 4thQtr07re | 1stQtr08 | 1stQtr08re | 2ndQtr08 | 3rdQtr08 | 4thQtr08 |
|-------|--------------|---------|---------------------------|-------|---------|-----------|----------|----------|------------|----------|------------|----------|----------|------------|----------|------------|----------|----------|----------|
| Lower | Downgradient | G16M | Acetone | ug/l | G2 | Organic | 10 | | | F< 10 | | | | | | | < 10 | | 6 |
| Lower | Downgradient | G16M | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 3.8 | | 2.6 | | 2.3 | 2.5 | | 1.2 | | 0.35 | < 0.09 | < 0.09 |
| Lower | Downgradient | G18D | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 0.12 | | < 0.09 | | < 0.09 | < 0.09 | | < 0.09 | | 3 | 4.7 | 7.3 |
| Lower | Downgradient | G34D | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | < 0.09 | | 7 | | 1 | 0.25 | | < 0.09 | | < 0.09 | 0.28 | 0.81 |
| Lower | Downgradient | G35D | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 0.14 | | 68 | | 0.62 | 0.29 | | 3.9 | | 2.2 | 1.8 | 0.97 |
| Lower | Downgradient | G37D | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | < 0.09 | | < 0.09 | | < 0.09 | 0.15 | | 0.97 | | 1.1 | 1.4 | 2 |
| Lower | Downgradient | G38S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 24 | | 62 | | 77 | 79 | | 62 | | 48 | 43 | 38 |
| Lower | Compliance | G39S | Ammonia as N, dissolved | mg/l | G1 | Inorganic | 0.9 | 1.2 | | 1.6 | | 0.79 | 0.62 | | 0.16 | | < 0.09 | 0.25 | 0.11 |
| Lower | Downgradient | G41M | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 6.5 | | 75 | | 26 | 9.9 | | 9.7 | | 0.45 | 0.17 | 0.11 |
| Lower | Compliance | G52M | Ammonia as N, dissolved | mg/L | G1, GMZ | Inorganic | 0.9 | | | | | | | | | | | | |
| Lower | Compliance | R39S | Ammonia as N, dissolved | mg/L | G1, GMZ | Inorganic | 0.9 | | | | | | | | | | | | |
| Lower | Downgradient | G38S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | < 1 | | 1.6 | | 2.2 | 2.2 | | 2.4 | | 2.3 | 2 | 2.1 |
| Lower | Compliance | G39S | Arsenic, Dissolved | ug/l | G1 | Inorganic | 2 | 2 | | < 1 | | < 1 | < 1 | | 1.2 | | < 1 | 3.6 | 3.5 |
| Lower | Downgradient | G41M | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | < 1 | | 3.7 | | < 1 | 1.7 | | < 1 | | < 1 | < 1 | < 1 |
| Lower | Compliance | R39S | Arsenic, Dissolved | ug/L | G1, GMZ | Inorganic | 2 | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 1 | | < 1 | | 3.3 | < 1 | | < 1 | | < 1 | 1.5 | < 1 |
| Lower | Downgradient | G18D | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 2 | | 2.5 | | 51 | 4.6 | | 1.3 | | 1 | 1.5 | 1.6 |
| Lower | Downgradient | G33D | Arsenic, total | ug/l | GMZ | Inorganic | 10 | < 1 | | < 1 | | 2.5 | < 1 | | 1.5 | | 1.7 | 4.8 | 1.4 |
| Lower | Downgradient | G34D | Arsenic, total | ug/l | GMZ | Inorganic | 10 | < 1 | | 1.2 | | < 1 | < 1 | | 5 | | < 1 | 7 | 1 |
| Lower | Downgradient | G35D | Arsenic, total | ug/l | GMZ | Inorganic | 10 | < 1 | | 1.9 | | < 1 | < 1 | | 7.2 | | 1.3 | 11 | 2.8 |
| Lower | Downgradient | G38S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 1.1 | | 2.2 | | 2.1 | 2.8 | | 2.4 | | 2 | 2.2 | 2 |
| Lower | Compliance | G39S | Arsenic, total | ug/l | | Inorganic | 10 | 2 | | < 1 | | < 1 | 3.9 | | 2.1 | | 1.9 | 38 | 36 |
| Lower | Downgradient | G41M | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 94 | | 12 | | 7.1 | 7.3 | | 23 | | 2 | 5.9 | 2.8 |
| Lower | Compliance | R39S | Arsenic, total | ug/L | GMZ | Inorganic | 10 | | | | | | | | | | | | |
| Lower | Compliance | G39S | Biochemical Oxygen Demand | mg/l | | Inorganic | 4.04 | | | 4.2 | < 4 | | | | | | < 4 | | |
| Lower | Downgradient | G18D | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 47 | | 20 | | < 10 | 21 | | 75 | | 160 | 130 | 120 |
| Lower | Downgradient | G34D | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 64 | | 85 | | 72 | 79 | | 140 | | 160 | 160 | 150 |
| Lower | Downgradient | G35D | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 25 | | 410 | | 34 | 25 | | 38 | | 34 | 32 | 28 |
| Lower | Downgradient | G38S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 190 | | 360 | | 360 | 320 | | 240 | | 200 | 180 | 220 |
| Lower | Compliance | G39S | Boron, Dissolved | ug/l | G1 | Inorganic | 98 | 130 | | 110 | | 78 | 63 | | 35 | | 42 | 200 | 360 |
| Lower | Downgradient | G41M | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 73 | | 540 | | 120 | 180 | | 69 | | 36 | 30 | 70 |
| Lower | Compliance | R39S | Boron, Dissolved | ug/L | G1, GMZ | Inorganic | 98 | | | | | | | | | | | | |
| Lower | Downgradient | G18D | Boron, total | ug/l | GMZ | Inorganic | 200 | 49 | | 35 | | 230 | 37 | | 90 | | 180 | 130 | 120 |
| Lower | Downgradient | G35D | Boron, total | ug/l | GMZ | Inorganic | 200 | 29 | | 430 | | 34 | 31 | | 45 | | 35 | 42 | 25 |
| Lower | Downgradient | G38S | Boron, total | ug/l | GMZ | Inorganic | 200 | 180 | | 390 | | 340 | 350 | | 250 | | 190 | 160 | 200 |
| Lower | Compliance | G39S | Boron, total | ug/l | | Inorganic | 200 | 120 | | 120 | | 79 | 72 | | 37 | | 45 | 340 | 440 |
| Lower | Downgradient | G41M | Boron, total | ug/l | GMZ | Inorganic | 200 | 69 | | 550 | | 110 | 220 | | 78 | | 28 | 39 | 65 |
| Lower | Compliance | R39S | Boron, total | ug/L | GMZ | Inorganic | 200 | | | | | | | | | | | | |
| Lower | Downgradient | G36S | Carbon disulfide | ug/l | G2 | Organic | 5 | | | < 1 | | | | | | | < 1 | | < 1 |
| Lower | Downgradient | G38S | Chemical Oxygen Demand | mg/l | | Inorganic | 50.04 | | | 51 | 40 | | | | | | 38 | | |
| Lower | Downgradient | G41M | Chemical Oxygen Demand | mg/l | | Inorganic | 50.04 | | | 62 | 55 | | | | | | 6.9 | | |
| Lower | Downgradient | G18D | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 38 | | 47 | | 18 | 38 | | 100 | | 92 | 56 | 51 |
| Lower | Downgradient | G34D | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 120 | | 120 | | 140 | 170 | | 130 | | 110 | 74 | 60 |
| Lower | Downgradient | G35D | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 41 | | 300 | | 50 | 49 | | 65 | | 43 | 44 | 46 |
| Lower | Downgradient | G38S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 120 | | 300 | | 220 | 54 | | 140 | | 110 | 100 | 130 |
| Lower | Compliance | G39S | Chloride, Dissolved | mg/l | G1 | Inorganic | 87.511 | 110 | | 120 | | 57 | 140 | | 270 | | 18 | 140 | 250 |
| Lower | Downgradient | G41M | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 48 | | 360 | | 57 | 120 | | 45 | | 40 | 39 | 45 |
| Lower | Compliance | R39S | Chloride, Dissolved | mg/L | G1, GMZ | Inorganic | 87.511 | | | | | | | | | | | | |
| Lower | Downgradient | G18D | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 42 | | 47 | | 14 | 38 | | 110 | | 81 | 58 | 51 |
| Lower | Downgradient | G34D | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 120 | | 120 | | 140 | 170 | | 130 | | 110 | 75 | 64 |
| Lower | Downgradient | G35D | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 37 | | 310 | | 51 | 51 | | 65 | | 45 | 44 | 47 |
| Lower | Downgradient | G38S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 110 | | 300 | | 230 | 210 | | 130 | | 96 | 99 | 140 |
| Lower | Compliance | G39S | Chloride, total | mg/l | | Inorganic | 87.51186 | 100 | | 110 | | 82 | 100 | | 260 | | 16 | 210 | 230 |
| Lower | Downgradient | G41M | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 54 | | 360 | | 64 | 120 | | 45 | | 40 | 39 | 42 |
| Lower | Compliance | R39S | Chloride, total | mg/L | GMZ | Inorganic | 87.51186 | | | | | | | | | | | | |

Note: A hlighted cell indicates an exceedence of the AGQS value.

Table 3
Winnebago Landfill
Northern Unit AGQS Exceedences

| Zone | Location | Well ID | Parameter | Units | GW List | Type | AGQS | 1stQtr07 | 1stQtr07re | 2ndQtr07 | 2ndQtr07re | 3rdQtr07 | 4thQtr07 | 4thQtr07re | 1stQtr08 | 1stQtr08re | 2ndQtr08 | 3rdQtr08 | 4thQtr08 |
|-------|--------------|---------|-------------------------|-------|---------|-----------|-----------|----------|------------|----------|------------|----------|----------|------------|----------|------------|----------|----------|----------|
| Lower | Downgradient | G35D | Chromium, dissolved | ug/L | G1 | | 72 | | | | | | | | | | | < 4 | < 4 |
| Lower | Compliance | R39S | Lead, Dissolved | ug/L | G1 | Inorganic | 4 | | | | | | | | | | | | |
| Lower | Compliance | R39S | Magnesium, dissolved | mg/L | G1 | | 170.41 | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | H 13 | | 12 | | 13 | 14 | | 13 | | 12 | 10 | 9.2 |
| Lower | Downgradient | G16M | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | H 11 | | 13 | | 10 | 12 | | 11 | | 7.1 | 10 | 11 |
| Lower | Downgradient | G33D | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | | 9.6 | 11 | | 10 | 9.9 | | 9 | | 9 | 9 | 10 |
| Lower | Downgradient | G35D | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | H 12 | | 0.52 | | 9.2 | 12 | | 4.8 | | 12 | 9.5 | 8.6 |
| Lower | Downgradient | G36S | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | H 12 | | 13 | | 12 | 14 | | 13 | | 12 | 12 | 12 |
| Lower | Downgradient | G03M | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | H 12 | | 11 | | 12 | 13 | | 12 | | 12 | 10 | 9.5 |
| Lower | Downgradient | G16M | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | H 11 | | 13 | | 10 | 12 | | 11 | | 7.4 | 10 | 11 |
| Lower | Downgradient | G33D | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | | 9.7 | 10 | | 10 | 9.9 | | 9 | | 9.3 | 9 | 10 |
| Lower | Downgradient | G35D | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | H 11 | | H 0.48 | | 9.1 | 12 | | 4.8 | | 12 | 9.7 | 8.8 |
| Lower | Downgradient | G36S | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | H 13 | | 13 | | 12 | 14 | | 13 | | 12 | 12 | 12 |
| Lower | Downgradient | G03M | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.35 | | 7.78 | | 8.3 | 7.46 | | 7.83 | | 6.93 | 7.14 | 7.72 |
| Lower | Downgradient | G16M | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.49 | | 7.45 | | 7.65 | 7.05 | | 7.71 | | 6.69 | 7.5 | 7.58 |
| Lower | Downgradient | G18D | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.47 | | 7.42 | | 7.99 | 7.28 | | 7.85 | | 8.38 | 7.24 | 7.57 |
| Lower | Downgradient | G33D | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 8.08 | | 8.27 | | 8.38 | 7.34 | | 6.97 | | 6.77 | 7.56 | 7.81 |
| Lower | Downgradient | G35D | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.53 | | 7.4 | | 7.4 | 7.05 | 6.72 | 7.48 | | 6.68 | 7.24 | 7.59 |
| Lower | Downgradient | G36S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.29 | | 7.43 | | 8.12 | 7.62 | | 7.19 | | 6.88 | 6.76 | 7.69 |
| Lower | Downgradient | G37D | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.42 | | 7.33 | | 8.26 | 7.52 | | 6.85 | | 6.73 | 7.52 | 7.74 |
| Lower | Downgradient | G41M | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.53 | | 7.17 | | 8.19 | 7.22 | | 7.61 | | 7.31 | 7.21 | 7.82 |
| Lower | Downgradient | G35D | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 2.7 | | 30 | | 2.8 | 2.6 | | 6.5 | | 5.4 | 5.8 | 3.9 |
| Lower | Downgradient | G38S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 15 | | 32 | | 30 | 30 | | 26 | | 24 | 21 | 23 |
| Lower | Downgradient | G41M | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 5.7 | | 32 | | 16 | 14 | | 9.2 | | 3.7 | 3.8 | 4.2 |
| Lower | Compliance | R39S | Potassium, total | mg/L | GMZ | Inorganic | 29.00582 | | | | | | | | | | | | |
| Lower | Downgradient | G35D | Selenium, total | ug/l | | Inorganic | 4 | | | 6.1 | 1.3 | | | | | | < 1 | | |
| Lower | Downgradient | G38S | Selenium, total | ug/l | | Inorganic | 4 | | | 5 | 5.8 | | | | | | < 1 | | |
| Lower | Downgradient | G41M | Selenium, total | ug/l | | Inorganic | 4 | | | 5.6 | 5.3 | | | | | | < 1 | | |

Note: A hlighted cell indicates an exceedence of the AGQS value.

Table 3
Winnebago Landfill
Northern Unit AGQS Exceedences

| Zone | Location | Well ID | Parameter | Units | GW List | Type | AGQS | 1stQtr07 | 1stQtr07re | 2ndQtr07 | 2ndQtr07re | 3rdQtr07 | 4thQtr07 | 4thQtr07re | 1stQtr08 | 1stQtr08re | 2ndQtr08 | 3rdQtr08 | 4thQtr08 |
|-------|--------------|---------|-------------------------------|-------|---------|-----------|--------|----------|------------|----------|------------|----------|----------|------------|----------|------------|----------|----------|----------|
| Upper | Downgradient | G15S | 1,4-Dichlorobenzene | ug/l | G2 | Organic | 5 | | | 8 | | | | | | | 9 | | |
| Upper | Downgradient | G51S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | Organic | 5 | | | | | | | | | | | | |
| Upper | Downgradient | G15S | Acetone | ug/l | G2 | Organic | 10 | | | 13 | < 10 | | | | | | < 10 | | |
| Upper | Downgradient | G51S | Acetone | ug/l | G2 | Organic | 10 | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Acrylonitrile | ug/l | G2 | Organic | 10 | | | 14 | < 10 | | | | | | < 5 | | < 5 |
| Upper | Downgradient | G15S | Alkalinity, bicarbonate total | mg/l | | Inorganic | 960 | | | 600 | | | | | | | 1200 | | |
| Upper | Downgradient | G15S | Ammonia as N, dissolved | mg/l | G1 | Inorganic | 0.9 | 100 | | 80 | | 140 | 260 | | 340 | | 240 | | |
| Upper | Downgradient | G34S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 8 | | 8.7 | | 14 | 17 | | 26 | | 11 | 9.2 | 11 |
| Upper | Downgradient | G35S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 10 | | 16 | | 5.4 | 6 | | 6.2 | | 3 | 3.8 | 4.2 |
| Upper | Downgradient | G37S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | < 0.09 | | 10 | | 1 | 0.14 | | < 0.09 | | < 0.09 | < 0.09 | < 0.09 |
| Upper | Downgradient | G40S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 45 | | 23 | | 18 | 19 | | 26 | | 15 | 23 | 24 |
| Upper | Downgradient | G41S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 28 | | 35 | | 30 | 30 | | 20 | | 7.8 | 1.3 | 18 |
| Upper | Downgradient | G51S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 7.6 | | 9.6 | | 5.3 | 4.9 | | 4.1 | | 2.4 | 1.3 | 0.9 |
| Upper | Downgradient | R42S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 2.1 | | 2.3 | | 2.4 | 1.4 | | 2.1 | | 2.1 | 2.2 | 1.4 |
| Upper | Downgradient | G15S | Arsenic, Dissolved | ug/l | G1 | Inorganic | 2 | 6 | | 2.5 | | 4.5 | 9.5 | | 8.6 | | 11 | | |
| Upper | Downgradient | G18S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | < 1 | | 2.4 | | < 1 | < 1 | | < 1 | | < 1 | < 1 | < 1 |
| Upper | Downgradient | G40S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | 2 | | < 1 | | < 1 | < 1 | | < 1 | | < 1 | 1.1 | 1.7 |
| Upper | Downgradient | G41S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | 35 | | 36 | | 38 | 37 | | 27 | | 32 | 31 | 26 |
| Upper | Downgradient | G51S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | | | | | | | | | | | | |
| Upper | Compliance | G52S | Arsenic, Dissolved | ug/L | G1, GMZ | Inorganic | 2 | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | 10 | | 9.1 | | 2.7 | 2.1 | | 1.1 | | < 1 | < 1 | < 1 |
| Upper | Downgradient | R42S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | 31 | | 29 | | 42 | 21 | | 30 | | 50 | 57 | 38 |
| Upper | Downgradient | G15S | Arsenic, total | ug/l | | Inorganic | 10 | 11 | | 3 | | 17 | | | 12 | | 15 | | |
| Upper | Downgradient | G18S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 15 | | 11 | | 2.2 | 59 | | 63 | | 25 | 31 | 69 |
| Upper | Downgradient | G41S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 40 | | 40 | | 42 | 46 | | 33 | | 33 | 120 | 28 |
| Upper | Downgradient | G50S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | | | | | | | | | | | | |
| Upper | Compliance | G52S | Arsenic, total | ug/L | GMZ | Inorganic | 10 | | | | | | | | | | | | |
| Upper | Compliance | G54S | Arsenic, total | ug/L | GMZ | Inorganic | 10 | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 28 | | 9.2 | | 42 | 8.5 | | 6.7 | | 1.2 | 3.3 | 1.8 |
| Upper | Downgradient | R42S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 70 | | 46 | | 53 | 38 | | 37 | | 58 | 58 | 40 |
| Upper | Downgradient | G15S | Biochemical Oxygen Demand | mg/l | | Inorganic | 4.04 | | | < 4 | | | | | | | 8 | | |
| Upper | Downgradient | G15S | Boron, Dissolved | ug/l | G1 | Inorganic | 98 | 660 | | 400 | | 710 | 1300 | | 1400 | | 1300 | | |
| Upper | Downgradient | G18S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 83 | | 74 | | 26 | 110 | | 62 | | 56 | 94 | 100 |
| Upper | Downgradient | G34S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 140 | | 76 | | 120 | 170 | | 160 | | 97 | 72 | 78 |
| Upper | Downgradient | G37S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 160 | | 66 | | 40 | 16 | | 12 | | 26 | 35 | 36 |
| Upper | Downgradient | G40S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 220 | | 97 | | 86 | 80 | | 100 | | 98 | 140 | 180 |
| Upper | Downgradient | G41S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 360 | | 280 | | 260 | 270 | | 83 | | 77 | 65 | 130 |
| Upper | Downgradient | G50S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | | | | | | | | | | | | |
| Upper | Downgradient | R42S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 84 | | 62 | | 86 | 58 | | 78 | | 68 | 84 | 88 |
| Upper | Downgradient | G15S | Boron, total | ug/l | | Inorganic | 200 | 660 | | 400 | | 690 | | | 1700 | | 1400 | | |
| Upper | Downgradient | G18S | Boron, total | ug/l | GMZ | Inorganic | 200 | 92 | | 120 | | 34 | 250 | | 220 | | 100 | 200 | 360 |
| Upper | Downgradient | G34S | Boron, total | ug/l | GMZ | Inorganic | 200 | 150 | | 90 | | 120 | | | 220 | | 91 | 78 | 71 |
| Upper | Downgradient | G40S | Boron, total | ug/l | GMZ | Inorganic | 200 | 220 | | 95 | | 92 | 83 | | 100 | | 88 | 150 | 160 |
| Upper | Downgradient | G41S | Boron, total | ug/l | GMZ | Inorganic | 200 | 360 | | 310 | | 240 | 280 | | 95 | | 65 | 70 | 130 |
| Upper | Downgradient | G50S | Boron, total | ug/l | GMZ | Inorganic | 200 | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Boron, total | ug/l | GMZ | Inorganic | 200 | | | | | | | | | | | | |
| Upper | Compliance | G52S | Boron, total | ug/L | GMZ | Inorganic | 200 | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Carbon disulfide | ug/l | G2 | Organic | 5 | | | < 1 | | | | | | | < 1 | | 9 |
| Upper | Downgradient | G15S | Chemical Oxygen Demand | mg/l | | Inorganic | 50.04 | | | 27 | | | | | | | 310 | | |
| Upper | Downgradient | G15S | Chloride, Dissolved | mg/l | G1 | Inorganic | 87.511 | 430 | | 320 | | 520 | 890 | | 1100 | | 860 | | |
| Upper | Downgradient | G18S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 30 | | 62 | | 45 | 27 | | 17 | | 19 | 7.6 | 16 |
| Upper | Downgradient | G34S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 100 | | 44 | | 140 | 160 | | 91 | | 54 | 42 | 53 |
| Upper | Downgradient | G37S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 94 | | 40 | | 34 | 37 | | 46 | | 42 | 46 | 55 |
| Upper | Downgradient | G40S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 160 | | 75 | | 74 | 82 | | 110 | | 120 | 270 | 89 |
| Upper | Downgradient | G41S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 110 | | 120 | | 98 | 130 | | 60 | | 55 | 50 | 78 |
| Upper | Downgradient | G50S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 77 | | 90 | | 57 | 84 | | 55 | | 50 | 45 | 52 |
| Upper | Downgradient | R42S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 58 | | 45 | | 70 | 70 | | 67 | | 68 | 100 | 83 |

Note: A hlighted cell indicates an exceedence of the AGQS value.

Table 3
Winnebago Landfill
Northern Unit AGQS Exceedences

| Zone | Location | Well ID | Parameter | Units | GW List | Type | AGQS | 1stQtr07 | 1stQtr07re | 2ndQtr07 | 2ndQtr07re | 3rdQtr07 | 4thQtr07 | 4thQtr07re | 1stQtr08 | 1stQtr08re | 2ndQtr08 | 3rdQtr08 | 4thQtr08 |
|-------|--------------|---------|---------------------------------|-------|---------|-----------|-----------|----------|------------|----------|------------|----------|----------|------------|----------|------------|----------|----------|----------|
| Upper | Downgradient | G15S | Chloride, total | mg/l | | Inorganic | 87.51186 | 470 | | 320 | | 540 | | | 1100 | | 840 | | |
| Upper | Downgradient | G18S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 24 | | 57 | | 47 | 30 | | 14 | | 19 | 11 | 23 |
| Upper | Downgradient | G34S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 110 | | 58 | | 140 | 150 | | 95 | | 55 | 42 | 54 |
| Upper | Downgradient | G37S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 92 | | 39 | | 33 | 37 | | 45 | | 43 | 46 | 55 |
| Upper | Downgradient | G40S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 160 | | 77 | | 50 | 60 | | 96 | | 190 | 220 | 250 |
| Upper | Downgradient | G41S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 110 | | 120 | | 97 | 130 | | 60 | | 57 | 50 | 78 |
| Upper | Downgradient | G50S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 74 | | 90 | | 59 | 82 | | 58 | | 46 | 48 | 51 |
| Upper | Downgradient | R42S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 58 | | 45 | | 70 | 61 | | 66 | | 72 | 100 | 98 |
| Upper | Downgradient | G18S | Cobalt, total | ug/l | | Inorganic | 50 | | | 16 | | | | | | | 72 | | |
| Upper | Downgradient | R42S | Iron, Dissolved | ug/l | | Inorganic | 12189.61 | 54000 | 53000 | 49000 | 53000 | 48000 | 28000 | 11000 | 47000 | 45000 | 46000 | | |
| Upper | Downgradient | G51S | Lead, Dissolved | ug/l | G1 | Inorganic | 4 | | | | | | | | | | | | |
| Upper | Compliance | G52S | Lead, Dissolved | ug/L | G1 | Inorganic | 4 | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Magnesium, dissolved | mg/l | G1 | | 170.41 | | | | | | | | | | | | |
| Upper | Compliance | G52S | Magnesium, dissolved | mg/L | G1 | | 170.41 | | | | | | | | | | | | |
| Upper | Downgradient | G18S | Magnesium, total | mg/l | | Inorganic | 109.5 | | | 67 | | | | | | | 210 | | |
| Upper | Downgradient | G40S | Magnesium, total | mg/l | | Inorganic | 109.5 | | | 62 | | | | | | | 130 | | |
| Upper | Downgradient | R42S | Manganese, Dissolved | ug/l | | Inorganic | 1479.53 | 1200 | | 1100 | | 1600 | 650 | | 900 | | 1400 | | |
| Upper | Downgradient | G119 | Nitrate as N, dissolved | mg/l | G1 | Inorganic | 11.74 | H 13 | | | | | | | | | | | |
| Upper | Downgradient | G130 | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | 11 | | 12 | | 12 | 13 | | 12 | | 12 | 11 | 12 |
| Upper | Downgradient | G40S | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | H 6.8 | | H 12 | | H 2.9 | 1.1 | | 1.5 | | H 18 | H 1.7 | 0.63 |
| Upper | Downgradient | G119 | Nitrate as N, total | mg/l | | Inorganic | 11.7389 | H 14 | | | | | | | | | | | |
| Upper | Downgradient | G130 | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | 11 | | 11 | | 12 | 13 | | 12 | | 12 | 12 | 13 |
| Upper | Downgradient | G33S | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | 8.8 | | 8.2 | | 10 | 9.5 | | 10 | | 9.2 | 8.6 | 7.9 |
| Upper | Downgradient | G40S | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | H 7.2 | | H 12 | | H 4.7 | H 2.3 | | H 3 | | 2 | H 2.4 | 1.7 |
| Upper | Downgradient | G130 | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.2 | | 7.24 | | 8.05 | 7.45 | | 7.19 | | 7.43 | 6.8 | 7.79 |
| Upper | Downgradient | G18S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.29 | | 7.79 | | 7.33 | 7.04 | | 7.48 | | 8.14 | 6.91 | 7.46 |
| Upper | Downgradient | G33S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.6 | | 7.73 | | 8.39 | 7.27 | | 6.88 | | 6.75 | 7.94 | 8.11 |
| Upper | Downgradient | G34S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.21 | 6.99 | 7.41 | | 7.61 | 6.98 | | 7.53 | | 6.41 | 7.04 | 7.52 |
| Upper | Downgradient | G35S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.18 | | 7.48 | | 7.64 | 7.01 | | 7.69 | | 6.7 | 7.39 | 7.75 |
| Upper | Downgradient | G37S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.06 | | 7.27 | | 8.18 | 7.55 | | 6.99 | | 7.09 | 7.66 | 7.82 |
| Upper | Downgradient | G40S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 6.69 | | 7.1 | | 7.75 | 6.96 | 6.6 | 7.5 | 6.86 | 8.14 | 6.71 | 7.35 |
| Upper | Compliance | G52S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | | | | | | | | | | | | |
| Upper | Downgradient | G40S | Polychlorinated Biphenyls(PCBs) | ug/l | | Organic | 2.5 | | | < 0.5 | | | | | | | 2.8 | | |
| Upper | Downgradient | G15S | Potassium, total | mg/l | | Inorganic | 29.00582 | 59 | | 44 | | 71 | | | 150 | | 130 | | |
| Upper | Downgradient | G18S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 12 | | 12 | | 4.1 | 25 | | 37 | | 12 | 18 | 33 |
| Upper | Downgradient | G40S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 30 | | 20 | | 17 | 17 | | 21 | | 38 | 23 | 23 |
| Upper | Downgradient | G41S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 30 | | 30 | | 26 | 27 | | 16 | | 10 | 9.3 | 15 |
| Upper | Downgradient | G50S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | | | | | | | | | | | | |
| Upper | Compliance | G52S | Potassium, total | mg/L | GMZ | Inorganic | 29.00582 | | | | | | | | | | | | |
| Upper | Downgradient | G15S | Selenium, total | ug/l | | Inorganic | 4 | | | 4.8 | 6.1 | | | | | | 14 | | |
| Upper | Downgradient | G18S | Selenium, total | ug/l | | Inorganic | 4 | | | 3.1 | | | | | | | 5.2 | | |
| Upper | Downgradient | G40S | Selenium, total | ug/l | | Inorganic | 4 | | | 2.5 | | | | | | | 20 | | |
| Upper | Downgradient | G15S | Sodium, total | mg/l | | Inorganic | 164.7897 | 180 | | 100 | | 250 | | | 610 | | 480 | | |
| Upper | Downgradient | G51S | Sodium, total | mg/l | GMZ | Inorganic | 164.7897 | | | | | | | | | | | | |
| Upper | Downgradient | G15S | Specific Conductance (field) | umhos | G1 | Inorganic | 3820 | 3000 | 3670 | 3222 | | 1444 | 4100 | 539 | 4510 | 4560 | 627 | | |
| Upper | Downgradient | R42S | Sulfate, Dissolved | mg/l | G1 | Inorganic | 360 | 300 | | 380 | 270 | 290 | 150 | 140 | 130 | 160 | 190 | 240 | 150 |
| Upper | Downgradient | R42S | Sulfate, total | mg/l | | Inorganic | 179.3731 | | | 390 | 270 | | | | | | 220 | | |
| Upper | Downgradient | G51S | Tetrahydrofuran | ug/l | G2, GMZ | Organic | 42 | | | | | | | | | | | | |

Note: A hlighted cell indicates an exceedence of the AGQS value.

Table 3
Winnebago Landfill
Northern Unit AGQS Exceedences

| Zone | Location | Well ID | Parameter | Units | GW List | Type | AGQS | 1stQtr09 | 2ndQtr09 | 2ndQtr09re | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 | | | | | |
|---------|--------------|---------|---------------------------|-------|---------|-----------|-----------|----------|----------|------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|-----|-----|---|-----|---|
| Bedrock | Upgradient | G09D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | Organic | 5 | | 11 | | | 5.4 | | 11 | | 12 | | 10 | | 1.1 | | | | | | |
| Bedrock | Upgradient | G09M | 1,4-Dichlorobenzene | ug/l | G2, GMZ | Organic | 5 | < | 1 | | | 2.3 | | 1.3 | | 5.9 | | 4.2 | | 6.4 | | | | | | |
| Bedrock | Upgradient | G13S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | Organic | 5 | < | 1 | | | < | 1 | < | 1 | | 3.6 | | 12 | | 13 | | | | | |
| Bedrock | Upgradient | G09D | Acetone | ug/l | G2 | Organic | 10 | < | 5 | | | 11 | < | 5 | < | 5 | | < | 5 | | < | 5 | | | | |
| Bedrock | Upgradient | G13D | Acetone | ug/l | G2 | Organic | 10 | | 18 | < | 5 | < | 5 | | 13 | | 8.6 | | < | 5 | | < | 5 | | | |
| Bedrock | Downgradient | G16D | Acrylonitrile | ug/l | G2 | Organic | 10 | | < | 5 | | < | 5 | | < | 5 | | < | 5 | | < | 5 | | | | |
| Bedrock | Upgradient | G13D | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 15 | 70 | | 32 | 25 | 15 | 250 | 200 | 170 | 280 | 23 | 13 | 18 | 15 | | | | | |
| Bedrock | Upgradient | G13S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | < | 0.09 | 0.16 | 0.75 | 0.59 | 1.1 | 0.39 | 1.1 | 1.7 | 11 | 7 | 6 | 5.6 | 6.3 | | | | | |
| Bedrock | Upgradient | G09D | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | 1.9 | 5.5 | | 3.3 | 2.3 | 1.9 | 1.8 | 2.7 | 3.2 | 1.2 | 4.6 | 4.4 | 3.1 | 3.4 | | | | | |
| Bedrock | Upgradient | G13D | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | 3.8 | 12 | | 6.9 | 9.1 | < | 1 | 43 | 43 | 19 | 10 | 2.4 | < | 1 | 2.5 | 1.9 | | | |
| Bedrock | Upgradient | G13S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | 3.9 | < | 1 | 1.2 | 4.5 | 1.8 | < | 1 | 1.8 | 3.1 | 4.6 | 4.1 | 1.4 | 5.2 | 4.7 | | | | |
| Bedrock | Upgradient | G13D | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 61 | 14 | | | 67 | 4.8 | 58 | 57 | 22 | 61 | 5.3 | 8.2 | 16 | 18 | | | | | |
| Bedrock | Upgradient | G13S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 8.4 | 1.4 | | | 3.5 | 120 | < | 1 | 2.9 | 5.2 | 12 | 3.1 | 1.9 | 9.8 | 11 | | | | |
| Bedrock | Upgradient | G20D | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 9.1 | < | 1 | < | 1 | 14 | < | 1 | < | 1 | 3.2 | < | 1 | < | 1 | < | 1 | 4.3 | |
| Bedrock | Upgradient | G13D | Benzene | ug/l | G2 | Organic | 2.8 | | < | 1 | | < | 1 | | < | 1 | | 1.7 | | 3.7 | 2.7 | | | | | |
| Bedrock | Upgradient | G13S | Benzene | ug/l | G2 | Organic | 2.8 | | < | 1 | | 1.2 | < | 1 | 1.6 | | 4.1 | | 3.7 | | 4.7 | | | | | |
| Bedrock | Upgradient | G09M | Biochemical Oxygen Demand | mg/l | | Inorganic | 4.04 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G13D | Biochemical Oxygen Demand | mg/l | | Inorganic | 4.04 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G13S | Biochemical Oxygen Demand | mg/l | | Inorganic | 4.04 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G09D | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 42 | 44 | | 42 | 41 | 46 | 36 | 53 | 46 | 42 | 45 | 62 | 54 | 70 | | | | | |
| Bedrock | Upgradient | G13D | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 440 | 1800 | | 2700 | 1900 | 250 | 7100 | 8500 | 6600 | 5000 | 950 | 360 | 690 | 480 | | | | | |
| Bedrock | Upgradient | G13S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 160 | 81 | | 100 | 100 | 150 | 93 | 200 | 280 | 440 | 470 | 470 | 410 | 250 | | | | | |
| Bedrock | Upgradient | G13D | Boron, total | ug/l | GMZ | Inorganic | 200 | 480 | 2100 | | | 2000 | 160 | 7200 | 8500 | 7000 | 6500 | 1100 | 400 | 660 | 510 | | | | | |
| Bedrock | Upgradient | G13S | Boron, total | ug/l | GMZ | Inorganic | 200 | 170 | 80 | | | 330 | 1100 | 110 | 230 | 290 | 430 | 530 | 470 | 390 | 260 | | | | | |
| Bedrock | Upgradient | G09D | Carbon disulfide | ug/l | G2 | Organic | 5 | | < | 1 | | < | 1 | | < | 1 | 26 | < | 1 | < | 1 | | | | | |
| Bedrock | Upgradient | G13S | Carbon disulfide | ug/l | G2 | Organic | 5 | | < | 1 | | < | 1 | | < | 1 | 12 | < | 1 | < | 1 | | | | | |
| Bedrock | Upgradient | G20D | Carbon disulfide | ug/l | G2 | Organic | 5 | | < | 1 | | < | 1 | | < | 1 | P | 36 | | < | 1 | | | | | |
| Bedrock | Upgradient | G13D | Chemical Oxygen Demand | mg/l | | Inorganic | 50.04 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G13S | Chemical Oxygen Demand | mg/l | | Inorganic | 50.04 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G09D | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 97 | 94 | | 86 | 100 | 520 | 110 | 130 | 120 | 140 | 140 | 81 | 76 | 65 | | | | | |
| Bedrock | Upgradient | G09M | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 480 | 490 | | 450 | 480 | 110 | 540 | 590 | 610 | 560 | 560 | 610 | | 600 | | | | | |
| Bedrock | Upgradient | G13D | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 110 | 260 | | 180 | 190 | 170 | 830 | 720 | 530 | 350 | 200 | 200 | 220 | 160 | | | | | |
| Bedrock | Upgradient | G13S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 73 | 77 | | 54 | 72 | 67 | 58 | 92 | 110 | 120 | 150 | 170 | 190 | 120 | | | | | |
| Bedrock | Upgradient | G09D | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 70 | 95 | | 90 | 110 | 490 | 110 | 130 | 120 | 130 | 140 | 100 | 85 | 79 | | | | | |
| Bedrock | Upgradient | G09M | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 540 | 520 | | 470 | 610 | 100 | 580 | 590 | 620 | 620 | 630 | 600 | 640 | 610 | | | | | |
| Bedrock | Upgradient | G13D | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 110 | 290 | | 200 | 190 | 170 | 770 | 730 | 520 | 350 | 210 | 190 | 210 | 180 | | | | | |
| Bedrock | Upgradient | G13S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 75 | 82 | | 55 | 71 | 70 | 56 | 98 | 100 | 120 | 150 | 170 | 200 | 120 | | | | | |
| Bedrock | Upgradient | G09D | Chlorobenzene | ug/l | G2 | Organic | 5 | | 8.8 | < | 1 | 4 | | 8.8 | | 11 | | 8.5 | | 4.9 | | | | | | |
| Bedrock | Upgradient | G09M | Chlorobenzene | ug/l | G2 | Organic | 5 | | < | 1 | | 1.4 | 3.2 | < | 1 | 5.9 | 5.7 | 3.3 | | 6.6 | | | | | | |
| Bedrock | Upgradient | G13D | Chlorobenzene | ug/l | G2 | Organic | 5 | | < | 1 | | < | 1 | | 1.7 | 4 | | 6.1 | | 14 | | | | | | |
| Bedrock | Upgradient | G13S | Chlorobenzene | ug/l | G2 | Organic | 5 | | 2.5 | < | 1 | 4.1 | 1.2 | 5.9 | | 24 | | 23 | | 29 | | | | | | |
| Bedrock | Upgradient | G20D | cis-1,2-Dichloroethene | ug/l | G2 | Organic | 5 | 13 | 8.8 | 8 | | 13 | 11 | 10 | | P | 11 | | 7.4 | | 7.1 | | | | | |
| Bedrock | Upgradient | G09D | Lead, Dissolved | ug/l | G1 | Inorganic | 4 | < | 1 | < | 1 | < | 1 | < | 1 | < | 1 | < | 1 | 6.7 | < | 1 | < | 1 | < | 1 |
| Bedrock | Upgradient | G13D | Lead, Dissolved | ug/l | G1 | Inorganic | 4 | < | 1 | < | 1 | < | 1 | < | 1 | 4 | 7.8 | 1.6 | < | 1 | < | 1 | < | 1 | < | 1 |
| Bedrock | Upgradient | G13D | Magnesium, dissolved | mg/L | G1 | | 170.41 | 150 | 160 | | 110 | 140 | 33 | 190 | 160 | 130 | 120 | 110 | 110 | 120 | 110 | | | | | |
| Bedrock | Upgradient | G13D | Magnesium, total | mg/l | | Inorganic | 109.5 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G13D | Manganese, Dissolved | ug/l | | Inorganic | 1479.53 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G13S | Manganese, Dissolved | ug/l | | Inorganic | 1479.53 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G13S | Mercury, dissolved | ug/L | G1 | | 0.2 | < | 0.2 | | < | 0.2 | < | 0.2 | < | 0.2 | < | 0.2 | 0.24 | < | 0.2 | < | 0.2 | < | 0.2 | |
| Bedrock | Upgradient | G09M | Methylene Chloride | ug/l | G2 | Organic | 8 | | < | 2.5 | | < | 2.5 | | < | 2.5 | | < | 2 | | < | 2 | | | | |
| Bedrock | Downgradient | G41D | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | 9.7 | 12 | | 9.5 | 10 | 8.5 | 8.9 | 9.2 | 9.5 | 9.8 | 10 | 9.6 | 9.3 | 10 | | | | | |
| Bedrock | Downgradient | G16D | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.91 | 7.82 | | 7.57 | 7.53 | 7.45 | 7.57 | 7.7 | 7.51 | 7.44 | 8.29 | 7.48 | 8.17 | 7.24 | | | | | |
| Bedrock | Upgradient | G20D | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 8.03 | 7.25 | | 7.99 | 7.9 | 8.03 | 7.9 | 7.23 | 6.91 | 7.4 | 7.98 | 7.46 | 7.38 | 6.97 | | | | | |
| Bedrock | Downgradient | G41D | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.54 | 7.09 | | 7.48 | 7.38 | 7.91 | 7.48 | 7.52 | 6.92 | 7.27 | 7.94 | 6.88 | 7.24 | 7.21 | | | | | |
| Bedrock | Upgradient | G13D | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 85 | 190 | | | 140 | 7.2 | 340 | 330 | 270 | 230 | 79 | 98 | 87 | 81 | | | | | |
| Bedrock | Upgradient | G13S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 6.1 | 5.1 | | | 7.6 | 79 | 5.7 | 6.8 | 8 | 20 | 45 | 19 | 18 | 21 | | | | | |
| Bedrock | Upgradient | G09M | Selenium, total | ug/l | | Inorganic | 4 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G13D | Selenium, total | ug/l | | Inorganic | 4 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G09D | Sodium, total | mg/l | GMZ | Inorganic | 164.7897 | 35 | 36 | | 45 | 51 | 220 | 56 | 70 | 77 | 81 | 83 | 61 | 56 | 50 | | | | | |
| Bedrock | Upgradient | G09M | Sodium, total | mg/l | GMZ | Inorganic | 164.7897 | 210 | 210 | | 220 | 200 | 55 | 240 | 240 | 250 | 250 | 260 | 250 | 240 | 270 | | | | | |
| Bedrock | Upgradient | G13D | Sodium, total | mg/l | GMZ | Inorganic | 164.7897 | 72 | 220 | | | 160 | 52 | 730 | 610 | 500 | 450 | 92 | 44 | 65 | 63 | | | | | |
| Bedrock | Upgradient | G13D | Sulfate, Dissolved | mg/l | G1 | Inorganic | 360 | 570 | 580 | | 70 | 280 | 310 | 270 | 360 | 260 | 190 | 280 | 300 | 230 | 170 | | | | | |
| Bedrock | Upgradient | G13D | Sulfate, total | mg/l | | Inorganic | 179.3731 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G13S | Sulfate, total | mg/l | | Inorganic | 179.3731 | | | | | | | | | | | | | | | | | | | |
| Bedrock | Upgradient | G13D | Tetrahydrofuran | ug/l | G2, GMZ | Organic | 42 | | 110 | | | < | 2.5 | | 63 | | 24 | | 15 | | < | 2 | | | | |
| Bedrock | Upgradient | G13D | Vanadium, total | ug/l | | Inorganic | 100 | | 6 | | | | | | | | | | | | | | | | | |

Note: A hlighted cell indicates an exceedence of the AGQS value.

Table 3
Winnebago Landfill
Northern Unit AGQS Exceedences

| Zone | Location | Well ID | Parameter | Units | GW List | Type | AGQS | 1stQtr09 | 2ndQtr09 | 2ndQtr09re | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|---------------------------|-------|---------|-----------|----------|----------|----------|------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G16M | Acetone | ug/l | G2 | Organic | 10 | | < 5 | | | 13 | < 5 | < 5 | | < 5 | | < 5 | < 5 | < 5 | |
| Lower | Downgradient | G16M | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | < 0.09 | < 0.09 | | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G18D | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 11 | 11 | | 14 | 11 | 4 | 5.6 | 2.3 | 1.9 | 1 | 1 | | | |
| Lower | Downgradient | G34D | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 2.7 | 4.2 | | 6 | Q 7.1 | 5.6 | 2.9 | 3.1 | 3 | 5.8 | 2.6 | 2.2 | 1.9 | 1.5 |
| Lower | Downgradient | G35D | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 0.74 | 2.2 | | 2.8 | 1.8 | 4.8 | 3.4 | 0.4 | 0.31 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G37D | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 2.1 | 2.1 | | | 1.7 | 1.7 | 0.99 | 0.48 | < 0.09 | 0.44 | 0.49 | | | |
| Lower | Downgradient | G38S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 16 | 15 | | 16 | 8.6 | 7.8 | 4.5 | 1.2 | 0.22 | < 0.09 | 0.93 | 0.59 | 0.38 | < 0.1 |
| Lower | Compliance | G39S | Ammonia as N, dissolved | mg/l | G1 | Inorganic | 0.9 | < 0.09 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | < 0.09 | < 0.09 | | < 0.09 | < 0.09 | < 0.09 | < 0.09 | 2.3 | 3.6 | 2.3 | 1.5 | 1.7 | 0.28 | 0.18 |
| Lower | Compliance | G52M | Ammonia as N, dissolved | mg/L | G1, GMZ | Inorganic | 0.9 | | | | | < 0.09 | < 0.09 | < 0.09 | 0.52 | 0.39 | 0.46 | 0.33 | 1.2 | 1 | 0.87 |
| Lower | Compliance | R39S | Ammonia as N, dissolved | mg/L | G1, GMZ | Inorganic | 0.9 | | < 0.09 | | 5.5 | 21 | 25 | 42 | 40 | 27 | 3 | 15 | 12 | | |
| Lower | Downgradient | G38S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | 1.5 | 2 | | 1.9 | 2.4 | 1.2 | 1.2 | < 1 | 1.2 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Compliance | G39S | Arsenic, Dissolved | ug/l | G1 | Inorganic | 2 | 2.2 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | < 1 | < 1 | | < 1 | < 1 | < 1 | < 1 | < 1 | 1.2 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Compliance | R39S | Arsenic, Dissolved | ug/L | G1, GMZ | Inorganic | 2 | | 2.6 | | 4.6 | 2.2 | 3.6 | 2 | 1.9 | 2 | 1.4 | < 1 | < 1 | | |
| Lower | Downgradient | G03M | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 5.7 | < 1 | | < 1 | < 1 | 1.2 | 1.5 | 1.5 | < 1 | 6.8 | < 1 | < 1 | 1.6 | 14 |
| Lower | Downgradient | G18D | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 7.8 | 4.6 | | 1.8 | 2.4 | < 1 | 9.5 | 1.5 | 2.8 | 24 | 4.2 | | | |
| Lower | Downgradient | G33D | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 5.5 | 5.2 | | 3.2 | < 1 | 2 | 3.1 | 1.5 | | 19 | 11 | 1.5 | 1.2 | 21 |
| Lower | Downgradient | G34D | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 15 | 5.2 | | < 1 | < 1 | 2 | 1.1 | < 1 | < 1 | 2.5 | < 1 | < 1 | < 1 | 3.7 |
| Lower | Downgradient | G35D | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 160 | 43 | | 32 | 1.3 | 26 | 12 | 12 | 5 | 2.1 | 13 | 2.2 | 2.6 | 21 |
| Lower | Downgradient | G38S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 4.8 | 2.1 | | 5.2 | 2.6 | 5.9 | 2.1 | 1 | 1.2 | 12 | 4.3 | 2.7 | 16 | 14 |
| Lower | Compliance | G39S | Arsenic, total | ug/l | | Inorganic | 10 | 79 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 18 | 5.5 | | 9.8 | 22 | 31 | 12 | 14 | 2.5 | 9.7 | 6.7 | 11 | 1.9 | 1.1 |
| Lower | Compliance | R39S | Arsenic, total | ug/L | GMZ | Inorganic | 10 | | 3.5 | | 11 | 5.2 | 54 | 130 | 98 | 2.3 | 5 | 1.4 | 1.9 | | |
| Lower | Compliance | G39S | Biochemical Oxygen Demand | mg/l | | Inorganic | 4.04 | | | | | | | | | | | | | | |
| Lower | Downgradient | G18D | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 100 | 89 | | 85 | 62 | 56 | 31 | 33 | 32 | 28 | 21 | | | |
| Lower | Downgradient | G34D | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 110 | 97 | | 84 | 62 | 52 | 36 | 29 | 24 | 27 | 34 | 36 | 24 | 31 |
| Lower | Downgradient | G35D | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 29 | 42 | | 33 | 34 | 40 | 17 | 37 | 28 | 32 | < 10 | 22 | 16 | < 10 |
| Lower | Downgradient | G38S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 130 | 130 | | 120 | 120 | 100 | 85 | 100 | 82 | 33 | 45 | 110 | 410 | 25 |
| Lower | Compliance | G39S | Boron, Dissolved | ug/l | G1 | Inorganic | 98 | 320 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 22 | 26 | | 29 | 18 | 23 | 27 | 48 | 65 | 67 | 30 | 35 | 23 | 25 |
| Lower | Compliance | R39S | Boron, Dissolved | ug/L | G1, GMZ | Inorganic | 98 | | 380 | | 420 | 350 | 360 | 340 | 220 | 130 | 77 | 68 | 71 | | |
| Lower | Downgradient | G18D | Boron, total | ug/l | GMZ | Inorganic | 200 | 130 | 93 | | 78 | 67 | 52 | 60 | 36 | 36 | 99 | 42 | | | |
| Lower | Downgradient | G35D | Boron, total | ug/l | GMZ | Inorganic | 200 | 180 | 85 | | 52 | 34 | 52 | 40 | 34 | 26 | 26 | 19 | 21 | 23 | 32 |
| Lower | Downgradient | G38S | Boron, total | ug/l | GMZ | Inorganic | 200 | 140 | 120 | | 130 | 120 | 100 | 87 | 97 | 71 | 48 | 60 | 100 | 72 | 30 |
| Lower | Compliance | G39S | Boron, total | ug/l | | Inorganic | 200 | 470 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Boron, total | ug/l | GMZ | Inorganic | 200 | 19 | 20 | | 27 | 18 | 22 | 34 | 45 | 66 | 66 | 35 | 26 | 23 | 27 |
| Lower | Compliance | R39S | Boron, total | ug/L | GMZ | Inorganic | 200 | | 360 | | 400 | 360 | 480 | 610 | 500 | 110 | 74 | 67 | 58 | | |
| Lower | Downgradient | G36S | Carbon disulfide | ug/l | G2 | Organic | 5 | | < 1 | | | < 1 | | < 1 | | 5.8 | < 1 | < 1 | | < 1 | |
| Lower | Downgradient | G38S | Chemical Oxygen Demand | mg/l | | Inorganic | 50.04 | | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Chemical Oxygen Demand | mg/l | | Inorganic | 50.04 | | | | | | | | | | | | | | |
| Lower | Downgradient | G18D | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 53 | 53 | | 52 | 38 | 52 | 41 | 27 | 28 | 27 | 38 | | | |
| Lower | Downgradient | G34D | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 53 | 54 | | 51 | 46 | 44 | 40 | 30 | 24 | 25 | 29 | 28 | 3.1 | 26 |
| Lower | Downgradient | G35D | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 56 | 62 | | 44 | 47 | 36 | 33 | 26 | 28 | 26 | 38 | 27 | 25 | 27 |
| Lower | Downgradient | G38S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 65 | 64 | | 76 | 65 | 95 | 180 | 29 | 32 | 40 | 140 | 66 | 39 | 36 |
| Lower | Compliance | G39S | Chloride, Dissolved | mg/l | G1 | Inorganic | 87.511 | 260 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 43 | 42 | | 39 | 37 | 40 | 62 | 41 | 57 | 51 | 44 | 45 | 39 | 40 |
| Lower | Compliance | R39S | Chloride, Dissolved | mg/L | G1, GMZ | Inorganic | 87.511 | | < 1 | | 250 | 160 | 160 | 130 | 59 | 60 | 48 | 130 | 48 | | |
| Lower | Downgradient | G18D | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 54 | 61 | | 52 | 37 | 50 | 40 | 30 | 27 | 30 | 37 | | | |
| Lower | Downgradient | G34D | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 56 | 58 | | 51 | 46 | 45 | 44 | 32 | 25 | 25 | 29 | 27 | 28 | 27 |
| Lower | Downgradient | G35D | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 58 | 62 | | 45 | 52 | 36 | 34 | 27 | 29 | 26 | 38 | 31 | 26 | 29 |
| Lower | Downgradient | G38S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 65 | 59 | | 75 | 68 | 80 | 180 | 45 | 32 | 34 | 160 | 73 | 39 | 46 |
| Lower | Compliance | G39S | Chloride, total | mg/l | | Inorganic | 87.51186 | 260 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 51 | 42 | | 39 | 38 | 42 | 65 | 43 | 52 | 51 | 43 | 44 | 40 | 38 |
| Lower | Compliance | R39S | Chloride, total | mg/L | GMZ | Inorganic | 87.51186 | | < 1 | | 240 | 160 | 170 | 120 | 64 | 55 | 47 | 44 | 46 | | |

Note: A hlighted cell indicates an exceedence of the AGQS value.

Table 3
Winnebago Landfill
Northern Unit AGQS Exceedences

| Zone | Location | Well ID | Parameter | Units | GW List | Type | AGQS | 1stQtr09 | 2ndQtr09 | 2ndQtr09re | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|-------------------------|-------|---------|-----------|-----------|----------|----------|------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G35D | Chromium, dissolved | ug/L | G1 | | 72 | < 4 | < 4 | | < 4 | < 4 | < 4 | < 4 | < 4 | < 4 | 76 | < 4 | < 4 | < 4 | < 4 |
| Lower | Compliance | R39S | Lead, Dissolved | ug/L | G1 | Inorganic | 4 | | < 1 | | < 1 | < 1 | < 1 | < 1 | 30 | < 1 | < 1 | < 1 | < 1 | | |
| Lower | Compliance | R39S | Magnesium, dissolved | mg/L | G1 | | 170.41 | | 78 | | 89 | 62 | 69 | 59 | 180 | 39 | 44 | 40 | 39 | | |
| Lower | Downgradient | G03M | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | 12 | 9.6 | | 8.2 | 7.8 | 8.2 | 7.8 | 7.7 | H 7.1 | 8.3 | 9.3 | 8.8 | | 10 |
| Lower | Downgradient | G16M | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | 6.3 | 7.8 | | 9.9 | 9.9 | 6.1 | 10 | 10 | 9.6 | 6.9 | 2.5 | 4.4 | 3.9 | 4.5 |
| Lower | Downgradient | G33D | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | 11 | 12 | | H 12 | 12 | 10 | 11 | 12 | | 10 | 11 | 11 | 8 | 8.7 |
| Lower | Downgradient | G35D | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | 8.3 | 7.6 | | H 8.4 | 5 | 5.9 | 5.7 | 7.3 | 5 | 6.3 | 5.3 | 8.7 | 5.9 | 7.5 |
| Lower | Downgradient | G36S | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | 13 | 12 | | H 13 | 11 | 13 | 12 | 11 | 11 | 12 | 12 | 11 | 12 | 11 |
| Lower | Downgradient | G03M | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | 11 | 9.9 | | 7.5 | 8.2 | 8 | 7.9 | 8.1 | 7.7 | 7.8 | 9 | 9.1 | 10 | 10 |
| Lower | Downgradient | G16M | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | 6.4 | 8.9 | | 10 | 10 | 6.4 | 11 | 10 | 8.7 | 7.1 | 2.3 | 4.5 | 3.9 | 4.4 |
| Lower | Downgradient | G33D | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | 11 | 12 | | H 12 | 12 | 13 | 11 | 12 | | 10 | 11 | 11 | 8 | 8.2 |
| Lower | Downgradient | G35D | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | 8.7 | 7.7 | | H 8.5 | 5.1 | 5.8 | 5.9 | 7.6 | 5.2 | 6.3 | 5.2 | 6.6 | 7.2 | 7.1 |
| Lower | Downgradient | G36S | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | 13 | 13 | | H 13 | 12 | 12 | 12 | 12 | 12 | 12 | 12 | 11 | 12 | 11 |
| Lower | Downgradient | G03M | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.84 | 7.32 | | 7.51 | 7.53 | 7.89 | 7.42 | 7.63 | 7.43 | 7.14 | 7.81 | 6.94 | 7.88 | 6.57 |
| Lower | Downgradient | G16M | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.4 | 7.62 | | 7.55 | 7.5 | 7.26 | 7.5 | 7.57 | 7.52 | 7.4 | 8.22 | 7.41 | 7.9 | 7.76 |
| Lower | Downgradient | G18D | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.47 | 7.04 | | 7 | 7.32 | 7.7 | 7.33 | 6.73 | 7.38 | 7.17 | 7.67 | | | |
| Lower | Downgradient | G33D | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.97 | 8.18 | | 7.58 | 7.52 | 7.12 | 7.61 | 7.76 | | 7.14 | 7.78 | 7.09 | 8.48 | 8.16 |
| Lower | Downgradient | G35D | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.53 | 7.81 | | 7.46 | 7.23 | 6.74 | 7.36 | 7.52 | 7.31 | 6.27 | 7.99 | 7.25 | 7.95 | 8.37 |
| Lower | Downgradient | G36S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.62 | 7.6 | | 7.73 | 7.48 | 7.72 | 7.47 | 7.73 | 7.06 | 6.98 | 7.48 | 7.57 | 6.92 | 8.21 |
| Lower | Downgradient | G37D | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.69 | 7.6 | | 7.6 | 7.52 | 7.73 | 7.64 | 6.58 | 7.42 | 7.21 | 7.92 | | 7.92 | |
| Lower | Downgradient | G41M | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.35 | 7.15 | | 7.5 | 7.52 | 7.88 | 7.6 | 7.96 | 6.44 | 7.18 | 7.53 | 7 | 7.43 | 7.2 |
| Lower | Downgradient | G35D | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 28 | 12 | | 10 | 4.4 | 8.2 | 7.6 | 5.4 | 4 | 3 | 3.7 | 1.7 | 1.7 | 6.3 |
| Lower | Downgradient | G38S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 16 | 14 | | 16 | 12 | 12 | 10 | 8.2 | 6.9 | 5.4 | 6.6 | 6.4 | 6 | 3.2 |
| Lower | Downgradient | G41M | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 3.9 | 3.4 | | 3.2 | 2.9 | 2.7 | 2.9 | 5.8 | 5.9 | 6 | 3.1 | 3.3 | 2.2 | 2.1 |
| Lower | Compliance | R39S | Potassium, total | mg/L | GMZ | Inorganic | 29.00582 | | 3 | | 7.3 | 10 | 23 | 73 | 63 | 19 | 16 | 14 | 12 | | |
| Lower | Downgradient | G35D | Selenium, total | ug/l | | Inorganic | 4 | | | | | | | | | | | | | | |
| Lower | Downgradient | G38S | Selenium, total | ug/l | | Inorganic | 4 | | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Selenium, total | ug/l | | Inorganic | 4 | | | | | | | | | | | | | | |

Note: A hlighted cell indicates an exceedence of the AGQS value.

Table 3
Winnebago Landfill
Northern Unit AGQS Exceedences

| Zone | Location | Well ID | Parameter | Units | GW List | Type | AGQS | 1stQtr09 | 2ndQtr09 | 2ndQtr09re | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|-------------------------------|-------|---------|-----------|--------|----------|----------|------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Upper | Downgradient | G15S | 1,4-Dichlorobenzene | ug/l | G2 | Organic | 5 | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | Organic | 5 | | 3.1 | | | < 1 | | 2.4 | | 6.2 | | 6.6 | | | |
| Upper | Downgradient | G15S | Acetone | ug/l | G2 | Organic | 10 | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Acetone | ug/l | G2 | Organic | 10 | | 11 | < 5 | | < 5 | | < 5 | | 5.2 | < 5 | < 5 | | | |
| Upper | Downgradient | R03S | Acrylonitrile | ug/l | G2 | Organic | 10 | | < 5 | | | < 5 | | < 5 | | < 5 | | < 5 | | < 5 | |
| Upper | Downgradient | G15S | Alkalinity, bicarbonate total | mg/l | | Inorganic | 960 | | | | | | | | | | | | | | |
| Upper | Downgradient | G15S | Ammonia as N, dissolved | mg/l | G1 | Inorganic | 0.9 | | | | | | | | | | | | | | |
| Upper | Downgradient | G34S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 10 | 10 | | 6.6 | 4.8 | 5.6 | 3.5 | 1.4 | 0.81 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Upper | Downgradient | G35S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 3.4 | 1.2 | | 2 | 1.9 | 1.6 | 1.1 | 1 | 0.86 | 0.64 | 0.36 | 0.22 | 0.33 | < 0.1 |
| Upper | Downgradient | G37S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | < 0.09 | < 0.09 | | | < 0.09 | < 0.09 | < 0.09 | 0.34 | 0.34 | 0.38 | < 0.1 | | | |
| Upper | Downgradient | G40S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 19 | 14 | | 24 | 11 | 9.4 | 9 | | | | | | | |
| Upper | Downgradient | G41S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 4.9 | 2.5 | | 1.2 | 1.6 | 1 | 0.64 | 0.37 | 0.32 | 2.4 | 1.4 | 0.23 | < 0.1 | 0.37 |
| Upper | Downgradient | G51S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 8 | 9.2 | | 9.8 | 5.7 | 12 | 16 | 45 | 76 | 100 | 39 | 160 | | |
| Upper | Downgradient | R03S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 1.2 | R 1.2 | | 1.1 | 0.9 | 1.2 | 1.3 | 0.93 | 0.84 | 0.66 | 0.45 | 0.4 | 0.22 | < 0.1 |
| Upper | Downgradient | R42S | Ammonia as N, dissolved | mg/l | G1, GMZ | Inorganic | 0.9 | 1.7 | 2 | | 2 | 1.7 | 1.7 | 1.6 | 1.4 | 0.53 | 0.57 | 2.3 | 1.2 | 2.1 | 0.44 |
| Upper | Downgradient | G15S | Arsenic, Dissolved | ug/l | G1 | Inorganic | 2 | | | | | | | | | | | | | | |
| Upper | Downgradient | G18S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | < 1 | < 1 | | < 1 | < 1 | < 1 | | | | | | | | |
| Upper | Downgradient | G40S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | 1.6 | 2.3 | | 2.9 | 1.7 | 1.4 | 1.5 | | | | | | | |
| Upper | Downgradient | G41S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | 25 | 25 | | 23 | 19 | 17 | 16 | 13 | 16 | 13 | 8.4 | 6.4 | < 1 | < 1 |
| Upper | Downgradient | G51S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | < 1 | 2.1 | | 1.8 | 1.8 | 3.5 | 3.2 | 6.4 | 6.8 | 8.6 | 12 | 12 | | |
| Upper | Compliance | G52S | Arsenic, Dissolved | ug/L | G1, GMZ | Inorganic | 2 | | | | | 1.1 | < 1 | 3.4 | 1.2 | 1.1 | < 1 | < 1 | 2 | 3 | < 1 |
| Upper | Downgradient | R03S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | < 1 | < 1 | | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Upper | Downgradient | R42S | Arsenic, Dissolved | ug/l | G1, GMZ | Inorganic | 2 | 27 | 52 | | 52 | 40 | 28 | 36 | 31 | 12 | 7.5 | 40 | 30 | 42 | 8.2 |
| Upper | Downgradient | G15S | Arsenic, total | ug/l | | Inorganic | 10 | | | | | | | | | | | | | | |
| Upper | Downgradient | G18S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 140 | 34 | | 52 | 110 | 8.9 | | | | | | | | |
| Upper | Downgradient | G41S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 29 | 60 | | 56 | 78 | 31 | 20 | 40 | 66 | 20 | 9.6 | 8.2 | 3.4 | 12 |
| Upper | Downgradient | G50S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 720 | 96 | | 180 | 76 | 210 | | | | | | | | |
| Upper | Downgradient | G51S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 36 | 3.5 | | 68 | 30 | 64 | 28 | 120 | 56 | 46 | 21 | 65 | | |
| Upper | Compliance | G52S | Arsenic, total | ug/L | GMZ | Inorganic | 10 | | | | | 1.9 | 29 | 74 | 40 | 36 | 45 | 29 | 29 | 2 | 32 |
| Upper | Compliance | G54S | Arsenic, total | ug/L | GMZ | Inorganic | 10 | | | | | | | | | | | | | | 18 |
| Upper | Downgradient | R03S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 4.6 | < 1 | | < 1 | < 1 | 2.3 | 18 | 3.4 | < 1 | 5.6 | < 1 | 2 | 1 | 6.5 |
| Upper | Downgradient | R42S | Arsenic, total | ug/l | GMZ | Inorganic | 10 | 31 | 51 | | 50 | 48 | 36 | 40 | 42 | 14 | 6.7 | 36 | 31 | 38 | 13 |
| Upper | Downgradient | G15S | Biochemical Oxygen Demand | mg/l | | Inorganic | 4.04 | | | | | | | | | | | | | | |
| Upper | Downgradient | G15S | Boron, Dissolved | ug/l | G1 | Inorganic | 98 | | | | | | | | | | | | | | |
| Upper | Downgradient | G18S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 68 | 58 | | 92 | 110 | 59 | | | | | | | | |
| Upper | Downgradient | G34S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 60 | 63 | | 44 | 46 | 44 | 22 | 37 | 32 | 11 | 19 | 38 | 18 | 15 |
| Upper | Downgradient | G37S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 20 | 27 | | | 40 | 28 | 25 | 72 | 40 | 31 | 27 | | | |
| Upper | Downgradient | G40S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 140 | 150 | | 340 | 150 | 180 | 220 | | | | | | | |
| Upper | Downgradient | G41S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 60 | 78 | | 100 | 42 | 40 | 30 | 34 | 40 | 69 | 25 | 39 | 20 | 43 |
| Upper | Downgradient | G50S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 140 | 42 | | 45 | 53 | 48 | | | | | | | | |
| Upper | Downgradient | G51S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 96 | 74 | | 75 | 77 | 91 | 110 | 220 | 310 | 410 | 480 | 520 | | |
| Upper | Downgradient | R42S | Boron, Dissolved | ug/l | G1, GMZ | Inorganic | 98 | 77 | 80 | | 83 | 78 | 79 | 68 | 94 | 52 | 62 | 80 | 72 | 99 | 56 |
| Upper | Downgradient | G15S | Boron, total | ug/l | | Inorganic | 200 | | | | | | | | | | | | | | |
| Upper | Downgradient | G18S | Boron, total | ug/l | GMZ | Inorganic | 200 | 580 | 130 | | 220 | 490 | 86 | | | | | | | | |
| Upper | Downgradient | G34S | Boron, total | ug/l | GMZ | Inorganic | 200 | 65 | 62 | | 40 | 43 | 41 | 36 | 43 | 30 | 14 | 20 | 38 | 27 | 16 |
| Upper | Downgradient | G40S | Boron, total | ug/l | GMZ | Inorganic | 200 | 160 | 140 | | 360 | 150 | 180 | 220 | | | | | | | |
| Upper | Downgradient | G41S | Boron, total | ug/l | GMZ | Inorganic | 200 | 57 | 66 | | 96 | 39 | 40 | 36 | 31 | 38 | 66 | 29 | 27 | 28 | 38 |
| Upper | Downgradient | G50S | Boron, total | ug/l | GMZ | Inorganic | 200 | 610 | 100 | | 180 | 130 | 320 | | | | | | | | |
| Upper | Downgradient | G51S | Boron, total | ug/l | GMZ | Inorganic | 200 | 130 | 67 | | 120 | 110 | 160 | 150 | 260 | 330 | 450 | 440 | 500 | | |
| Upper | Compliance | G52S | Boron, total | ug/L | GMZ | Inorganic | 200 | | | | | 34 | 200 | 250 | 260 | 220 | 290 | 210 | 150 | 71 | 160 |
| Upper | Downgradient | G17S | Carbon disulfide | ug/l | G2 | Organic | 5 | < 1 | < 1 | | | < 1 | | | | | | | | | |
| Upper | Downgradient | G15S | Chemical Oxygen Demand | mg/l | | Inorganic | 50.04 | | | | | | | | | | | | | | |
| Upper | Downgradient | G15S | Chloride, Dissolved | mg/l | G1 | Inorganic | 87.511 | | | | | | | | | | | | | | |
| Upper | Downgradient | G18S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 48 | 70 | | 26 | 35 | 110 | | | | | | | | |
| Upper | Downgradient | G34S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 35 | 36 | | 34 | 40 | 35 | 29 | 41 | 29 | 33 | 35 | 28 | 23 | 27 |
| Upper | Downgradient | G37S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 49 | 54 | | | 57 | 50 | 47 | 36 | 32 | 36 | 33 | | | |
| Upper | Downgradient | G40S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 290 | 260 | | 290 | 210 | 200 | 190 | | | | | | | |
| Upper | Downgradient | G41S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 100 | 74 | | 70 | 42 | 42 | 52 | 55 | 44 | 59 | 39 | 37 | 28 | 50 |
| Upper | Downgradient | G50S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 120 | 35 | | 36 | 42 | 35 | | | | | | | | |
| Upper | Downgradient | G51S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 86 | 140 | | 190 | 280 | 270 | 480 | 820 | 740 | 790 | 1000 | 4.4 | | |
| Upper | Downgradient | R03S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 53 | 49 | | 48 | 41 | 45 | 40 | 45 | 42 | 40 | 43 | 43 | | 42 |
| Upper | Downgradient | R42S | Chloride, Dissolved | mg/l | G1, GMZ | Inorganic | 87.511 | 110 | 82 | | 50 | 63 | 33 | 26 | 96 | 63 | 63 | 140 | 100 | 110 | 67 |

Note: A hlighted cell indicates an exceedence of the AGQS value.

Table 3
Winnebago Landfill
Northern Unit AGQS Exceedences

| Zone | Location | Well ID | Parameter | Units | GW List | Type | AGQS | 1stQtr09 | 2ndQtr09 | 2ndQtr09re | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|---------------------------------|-------|---------|-----------|-----------|----------|----------|------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Upper | Downgradient | G15S | Chloride, total | mg/l | | Inorganic | 87.51186 | | | | | | | | | | | | | | |
| Upper | Downgradient | G18S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 48 | 70 | | 26 | 33 | 110 | | | | | | | | |
| Upper | Downgradient | G34S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 34 | 38 | | 35 | 40 | 35 | 31 | 38 | 30 | 33 | 35 | 29 | 34 | 27 |
| Upper | Downgradient | G37S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 49 | 56 | | | 60 | 51 | 47 | 36 | 32 | 35 | 33 | | | |
| Upper | Downgradient | G40S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 270 | 260 | | 300 | 210 | 180 | 180 | | | | | | | |
| Upper | Downgradient | G41S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 91 | 72 | | 68 | 45 | 45 | 54 | 53 | 43 | 59 | 39 | 39 | 31 | 32 |
| Upper | Downgradient | G50S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 140 | 38 | | 32 | 33 | 36 | | | | | | | | |
| Upper | Downgradient | G51S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 76 | 140 | | 200 | 280 | 260 | 470 | 830 | 610 | 900 | 1000 | 1200 | | |
| Upper | Downgradient | R03S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 60 | 50 | | 56 | 44 | 41 | 39 | 45 | 39 | 39 | 40 | 44 | 42 | 38 |
| Upper | Downgradient | R42S | Chloride, total | mg/l | GMZ | Inorganic | 87.51186 | 110 | 79 | | 47 | 63 | 28 | 28 | 120 | 70 | 70 | 140 | 160 | 140 | 92 |
| Upper | Downgradient | G18S | Cobalt, total | ug/l | | Inorganic | 50 | | | | | | | | | | | | | | |
| Upper | Downgradient | R42S | Iron, Dissolved | ug/l | | Inorganic | 12189.61 | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Lead, Dissolved | ug/l | G1 | Inorganic | 4 | < 1 | < 1 | | < 1 | < 1 | < 1 | < 1 | 27 | < 1 | < 1 | < 1 | < 1 | | |
| Upper | Compliance | G52S | Lead, Dissolved | ug/L | G1 | Inorganic | 4 | | | | | < 1 | < 1 | 53 | 3 | 1.2 | < 1 | < 1 | 24 | 17 | < 1 |
| Upper | Downgradient | G51S | Magnesium, dissolved | mg/l | G1 | | 170.41 | 51 | 56 | | 66 | 76 | 92 | 100 | 230 | 100 | 110 | 120 | 120 | | |
| Upper | Compliance | G52S | Magnesium, dissolved | mg/L | G1 | | 170.41 | | | | | 51 | 52 | 260 | 61 | 48 | 53 | 44 | 110 | 200 | 42 |
| Upper | Downgradient | G18S | Magnesium, total | mg/l | | Inorganic | 109.5 | | | | | | | | | | | | | | |
| Upper | Downgradient | G40S | Magnesium, total | mg/l | | Inorganic | 109.5 | | | | | | | | | | | | | | |
| Upper | Downgradient | R42S | Manganese, Dissolved | ug/l | | Inorganic | 1479.53 | | | | | | | | | | | | | | |
| Upper | Downgradient | G119 | Nitrate as N, dissolved | mg/l | G1 | Inorganic | 11.74 | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | 13 | 12 | | H 13 | 12 | 12 | 12 | 12 | 12 | 12 | 12 | 12 | 13 | 11 |
| Upper | Downgradient | G40S | Nitrate as N, dissolved | mg/l | G1, GMZ | Inorganic | 11.74 | 0.047 | < 0.02 | | < 0.02 | < 0.02 | < 0.02 | H 2 | | | | | | | |
| Upper | Downgradient | G119 | Nitrate as N, total | mg/l | | Inorganic | 11.7389 | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | 13 | 13 | | H 13 | 12 | 13 | 12 | 12 | 12 | 12 | 12 | 12 | 11 | 11 |
| Upper | Downgradient | G33S | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | 10 | 9.9 | | H 11 | 11 | 12 | 11 | 10 | | 5.9 | 5.4 | 4.6 | 5.3 | 7.6 |
| Upper | Downgradient | G40S | Nitrate as N, total | mg/l | GMZ | Inorganic | 11.7389 | 0.55 | < 0.02 | | 0.11 | < 0.02 | 3.4 | 1.3 | | | | | | | |
| Upper | Downgradient | G130 | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.62 | 7.72 | | 7.69 | 7.52 | 7.87 | 7.54 | 7.75 | 6.72 | 7.01 | 7.63 | 7.46 | 7.24 | 8.25 |
| Upper | Downgradient | G18S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.36 | 7.6 | | 7.36 | 7.2 | 7.6 | | | | | | | | |
| Upper | Downgradient | G33S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.85 | 8.08 | | 7.8 | 7.41 | 7.26 | 7.66 | 7.84 | | 7.2 | 7.96 | 7.4 | 8.16 | 9 |
| Upper | Downgradient | G34S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 6.8 | 7.77 | | 7.63 | 7.4 | 6.73 | 7.35 | 7.56 | 7.3 | 7.2 | 8.02 | 7.38 | 8.29 | 7.86 |
| Upper | Downgradient | G35S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.25 | 8.02 | | 7.61 | 7.19 | 6.91 | 7.28 | 7.57 | 7.21 | 7.28 | 7.81 | 7.11 | 7.97 | 8.99 |
| Upper | Downgradient | G37S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.69 | 7.81 | | 7.81 | 7.66 | 7.85 | 7.69 | 7.43 | 7.16 | 7.25 | 8.05 | | 8.05 | |
| Upper | Downgradient | G40S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | 7.16 | 6.97 | | 6.93 | 6.82 | 7.81 | 7.37 | | | | | | | |
| Upper | Compliance | G52S | pH (field) | units | G1 | Inorganic | 5.4 - 8.1 | | | | | 7.91 | 7.19 | 7.42 | 7.67 | 6.56 | 7.22 | 7.63 | 6.9 | 8.41 | 7.06 |
| Upper | Downgradient | G40S | Polychlorinated Biphenyls(PCBs) | ug/l | | Organic | 2.5 | | | | | | | | | | | | | | |
| Upper | Downgradient | G15S | Potassium, total | mg/l | | Inorganic | 29.00582 | | | | | | | | | | | | | | |
| Upper | Downgradient | G18S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 63 | 17 | | 24 | 77 | 12 | | | | | | | | |
| Upper | Downgradient | G40S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 21 | 20 | | 23 | 16 | 14 | 14 | | | | | | | |
| Upper | Downgradient | G41S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 7.5 | 5.8 | | 5.7 | 6.2 | 5.2 | 4.4 | 4 | 4.9 | 7.9 | 5.1 | 4.6 | 3.4 | 4.5 |
| Upper | Downgradient | G50S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 75 | 13 | | 22 | 19 | 50 | | | | | | | | |
| Upper | Downgradient | G51S | Potassium, total | mg/l | GMZ | Inorganic | 29.00582 | 13 | 15 | | 20 | 20 | 24 | 21 | 31 | 30 | 39 | 39 | 46 | | |
| Upper | Compliance | G52S | Potassium, total | mg/L | GMZ | Inorganic | 29.00582 | | | | | 3.6 | 22 | 25 | 41 | 36 | 55 | 35 | 14 | 3.7 | 24 |
| Upper | Downgradient | G15S | Selenium, total | ug/l | | Inorganic | 4 | | | | | | | | | | | | | | |
| Upper | Downgradient | G18S | Selenium, total | ug/l | | Inorganic | 4 | | | | | | | | | | | | | | |
| Upper | Downgradient | G40S | Selenium, total | ug/l | | Inorganic | 4 | | | | | | | | | | | | | | |
| Upper | Downgradient | G15S | Sodium, total | mg/l | | Inorganic | 164.7897 | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Sodium, total | mg/l | GMZ | Inorganic | 164.7897 | 55 | 48 | | 42 | 60 | 72 | 120 | 220 | 230 | 240 | 270 | 360 | | |
| Upper | Downgradient | G15S | Specific Conductance (field) | umhos | G1 | Inorganic | 3820 | | | | | | | | | | | | | | |
| Upper | Downgradient | R42S | Sulfate, Dissolved | mg/l | G1 | Inorganic | 360 | 170 | 180 | | 110 | 52 | 47 | 26 | 11 | 78 | 39 | 1.4 | 39 | 11 | 120 |
| Upper | Downgradient | R42S | Sulfate, total | mg/l | | Inorganic | 179.3731 | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Tetrahydrofuran | ug/l | G2, GMZ | Organic | 42 | | 4.3 | | | 18 | | 44 | | 61 | | 94 | | | |

Note: A hlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 1stQtr97 | 2ndQtr97 | 3rdQtr97 | 4thQtr97 | 1stQtr98 | 2ndQtr98 | 3rdQtr98 | 4thQtr98 | 1stQtr99 | 2ndQtr99 | 3rdQtr99 | 4thQtr99 | 1stQtr00 | 2ndQtr00 | 3rdQtr00 | 4thQtr00 | 1stQtr01 | 2ndQtr01 |
|---------|--------------|---------|-------------------------|-------|---------|------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Bedrock | Upgradient | G09D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G09M | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G13D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G13S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | 14 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Downgradient | G14D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Downgradient | G16D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | | | < 1 | |
| Bedrock | Upgradient | G20D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Downgradient | G41D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G09D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G09M | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G13D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G13S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | 7 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Downgradient | G14D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Downgradient | G16D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | | | < 1 | |
| Bedrock | Upgradient | G20D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Downgradient | G41D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G09D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | 1.4 | | | | 1.2 | | | 4.1 | |
| Bedrock | Upgradient | G09M | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G13D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G13S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | 2.4 | |
| Bedrock | Downgradient | G14D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | 23 | | | | 37 | | | | 25 | | | | 26 | | | 29 | |
| Bedrock | Downgradient | G16D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | | | < 1 | |
| Bedrock | Upgradient | G20D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Downgradient | G41D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | 1.9 | | | < 1 | |
| Bedrock | Upgradient | G09D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.1 | 0.12 | 0.36 | 0.55 | 0.19 | 0.194 | < 0.1 | 0.12 | < 0.1 | < 0.1 | 0.1 | 0.29 | < 0.1 | < 0.1 | 0.29 | 0.19 | 0.16 | 0.18 |
| Bedrock | Upgradient | G09M | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.21 | 0.14 | 0.27 | 0.34 | 0.49 | 0.18 | 0.46 | 0.29 | < 0.1 | < 0.1 | 0.18 | 0.31 | 0.19 | < 0.1 | 0.13 | < 0.1 | < 0.1 | < 0.1 |
| Bedrock | Upgradient | G13D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.43 | 0.3 | 0.3 | 0.97 | 0.38 | 0.372 | 0.18 | 0.32 | 0.17 | < 0.1 | < 0.1 | 0.34 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | 0.12 | < 0.1 |
| Bedrock | Upgradient | G13S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.19 | 0.13 | 0.27 | 0.63 | 0.23 | 0.235 | 0.24 | 0.24 | 0.13 | 0.18 | 0.13 | 0.4 | < 0.1 | < 0.1 | 0.1 | < 0.1 | 0.14 | 0.13 |
| Bedrock | Downgradient | G14D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 1.49 | 1.04 | 1.01 | 1.1 | 0.91 | 0.983 | 0.65 | 1.1 | 0.6 | 0.83 | 1.1 | 1.4 | 0.85 | 0.68 | 1.1 | 1.6 | 1 | 0.59 |
| Bedrock | Downgradient | G16D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | | | | | | | | | | | | | | | | | < 0.1 | |
| Bedrock | Upgradient | G20D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.05 | 0.09 | 0.14 | 0.25 | 0.09 | 0.436 | < 0.1 | < 0.061 | 0.19 | < 0.1 | < 0.1 | 0.13 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Bedrock | Downgradient | G41D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 23 | 16.3 | 34.4 | 1.16 | 0.36 | 0.221 | 10 | 0.13 | 1 | 1.2 | 39 | 33 | 37 | 92 | 74 | 47 | 47 | 45 |
| Bedrock | Upgradient | G09D | Ammonia as N, total | mg/l | GMZ | 900 | | 0.17 | | | | 0.13 | | | | < 0.1 | | | | 0.17 | | | 0.23 | |
| Bedrock | Upgradient | G09M | Ammonia as N, total | mg/l | GMZ | 900 | | 0.18 | | | | 0.198 | | | | < 0.1 | | | | 0.13 | | | < 0.1 | |
| Bedrock | Upgradient | G13D | Ammonia as N, total | mg/l | GMZ | 900 | | 0.48 | | | | 0.308 | | | | < 0.1 | | | | < 0.1 | | | < 0.1 | |
| Bedrock | Upgradient | G13S | Ammonia as N, total | mg/l | GMZ | 900 | | 0.2 | | | | 0.153 | | | | 0.18 | | | | 0.13 | | | 0.18 | |
| Bedrock | Downgradient | G14D | Ammonia as N, total | mg/l | GMZ | 900 | | 1.11 | | | | 0.906 | | | | 0.74 | | | | 0.78 | | | 0.59 | |
| Bedrock | Downgradient | G16D | Ammonia as N, total | mg/l | GMZ | 900 | | | | | | | | | | | | | | | | | < 0.1 | |
| Bedrock | Upgradient | G20D | Ammonia as N, total | mg/l | GMZ | 900 | | 0.12 | | | | 0.084 | | | | < 0.1 | | | | < 0.1 | | | < 0.1 | |
| Bedrock | Downgradient | G41D | Ammonia as N, total | mg/l | GMZ | 900 | | 16.7 | | | | 0.112 | | | | 0.41 | | | | 55 | | | 59 | |
| Bedrock | Upgradient | G09D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | < 2 | < 2 | < 2 | < 2 | < 3 | < 2 | < 3 | < 0.84 | < 3 | < 3 | < 3 | 1.4 | < 2 | 2.5 | < 2 | < 2 |
| Bedrock | Upgradient | G09M | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | < 2 | < 2 | < 2 | < 2 | < 3 | < 2 | < 3 | < 0.84 | < 3 | < 3 | < 3 | < 0.84 | < 2 | < 2 | < 2 | < 2 |
| Bedrock | Upgradient | G13D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | < 2 | < 2 | < 2 | < 2 | < 3 | < 2 | < 3 | < 0.84 | < 3 | < 3 | < 3 | 1.4 | < 2 | < 2 | < 2 | < 2 |
| Bedrock | Upgradient | G13S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | 3.4 | < 2 | 8.2 | < 2 | < 3 | < 2 | < 3 | < 0.84 | < 3 | < 3 | < 3 | 1.4 | < 2 | < 2 | < 2 | < 2 |
| Bedrock | Downgradient | G14D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | 43 | 35 | 66 | 61 | 26 | 17.4 | 42 | 72 | 67 | 32 | 110 | 94 | 67 | 22 | 12 | 21 | 56 | 16 |
| Bedrock | Downgradient | G16D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | | | | | | | | | | | | | | | | | < 2 | |
| Bedrock | Upgradient | G20D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | < 2 | < 2 | < 2 | < 2 | < 3 | < 2 | < 3 | < 0.84 | < 3 | < 3 | < 3 | < 0.84 | < 2 | < 2 | < 2 | < 2 |
| Bedrock | Downgradient | G41D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | < 2 | 2.1 | < 2 | < 2 | < 3 | < 0.53 | < 3 | < 0.84 | < 3 | < 3 | < 3 | 1.3 | < 2 | < 2 | 2.3 | < 2 |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 1stQtr97 | 2ndQtr97 | 3rdQtr97 | 4thQtr97 | 1stQtr98 | 2ndQtr98 | 3rdQtr98 | 4thQtr98 | 1stQtr99 | 2ndQtr99 | 3rdQtr99 | 4thQtr99 | 1stQtr00 | 2ndQtr00 | 3rdQtr00 | 4thQtr00 | 1stQtr01 | 2ndQtr01 |
|---------|--------------|---------|---------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Bedrock | Upgradient | G09D | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | < 2 | | | | < 3 | | | | < 3 | | | < 10 | |
| Bedrock | Upgradient | G09M | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | 2.2 | | | | < 3 | | | | < 3 | | | < 10 | |
| Bedrock | Upgradient | G13D | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | < 2 | | | | 3.9 | | | | 3.3 | | | < 10 | |
| Bedrock | Upgradient | G13S | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | < 2 | | | | < 3 | | | | < 3 | | | < 10 | |
| Bedrock | Downgradient | G14D | Arsenic, total | ug/l | GMZ | 10 | | 36 | | | | 18.2 | | | | 74 | | | | 62 | | | | 33 |
| Bedrock | Downgradient | G16D | Arsenic, total | ug/l | GMZ | 10 | | | | | | | | | | | | | | | | | < 10 | |
| Bedrock | Upgradient | G20D | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | 6.22 | | | | < 3 | | | | < 3 | | | < 10 | |
| Bedrock | Downgradient | G41D | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | < 2 | | | | < 3 | | | | < 3 | | | < 10 | |
| Bedrock | Upgradient | G09D | Barium, total | ug/l | GMZ | 225180.6 | | 130 | | | | 132 | | | | 220 | | | | 200 | | | | 290 |
| Bedrock | Upgradient | G09M | Barium, total | ug/l | GMZ | 225180.6 | | 150 | | | | 146 | | | | 180 | | | | 170 | | | | 150 |
| Bedrock | Upgradient | G13D | Barium, total | ug/l | GMZ | 225180.6 | | 140 | | | | 151 | | | | 230 | | | | 200 | | | | 190 |
| Bedrock | Upgradient | G13S | Barium, total | ug/l | GMZ | 225180.6 | | 150 | | | | 148 | | | | 150 | | | | 140 | | | | 150 |
| Bedrock | Downgradient | G14D | Barium, total | ug/l | GMZ | 225180.6 | | 370 | | | | 402 | | | | 500 | | | | 450 | | | | 740 |
| Bedrock | Downgradient | G16D | Barium, total | ug/l | GMZ | 225180.6 | | | | | | | | | | | | | | | | | | 95 |
| Bedrock | Upgradient | G20D | Barium, total | ug/l | GMZ | 225180.6 | | 71 | | | | 64 | | | | 68 | | | | 68 | | | | 81 |
| Bedrock | Downgradient | G41D | Barium, total | ug/l | GMZ | 225180.6 | | 300 | | | | 83.7 | | | | 68 | | | | 830 | | | | 460 |
| Bedrock | Upgradient | G09D | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 110 | < 110 | < 110 | < 110 | < 110 | < 110 | < 100 | 38 | < 100 | < 100 | < 100 | < 100 | < 100 | < 98 | < 98 | < 98 | < 98 | < 98 |
| Bedrock | Upgradient | G09M | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 110 | < 110 | < 110 | < 110 | < 110 | < 110 | < 100 | 21 | < 100 | < 100 | < 100 | < 100 | < 100 | < 98 | < 98 | < 98 | < 98 | < 98 |
| Bedrock | Upgradient | G13D | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 110 | < 110 | < 110 | < 110 | 120 | < 110 | 110 | 110 | < 100 | 140 | < 100 | < 100 | < 100 | < 98 | < 98 | 100 | < 98 | < 98 |
| Bedrock | Upgradient | G13S | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 110 | < 110 | < 110 | < 110 | < 110 | < 110 | 110 | 110 | 110 | 110 | < 100 | < 100 | < 100 | < 98 | < 98 | < 98 | < 98 | < 98 |
| Bedrock | Downgradient | G14D | Boron, Dissolved | ug/l | G1, GMZ | 98 | 110 | < 110 | < 110 | < 110 | < 110 | < 110 | < 100 | 96 | < 100 | 100 | 120 | 110 | 130 | DA | 120 | 110 | 110 | 120 |
| Bedrock | Downgradient | G16D | Boron, Dissolved | ug/l | G1, GMZ | 98 | | | | | | | | | | | | | | | | | | < 98 |
| Bedrock | Upgradient | G20D | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 110 | < 110 | < 110 | < 110 | < 110 | < 110 | < 100 | 22 | < 100 | < 100 | < 100 | < 100 | < 100 | < 98 | < 98 | < 98 | < 98 | < 98 |
| Bedrock | Downgradient | G41D | Boron, Dissolved | ug/l | G1, GMZ | 98 | 120 | < 110 | 190 | < 110 | < 110 | < 110 | < 100 | 23 | < 100 | < 100 | 200 | 190 | 250 | 290 | 360 | 250 | 230 | 280 |
| Bedrock | Upgradient | G09D | Boron, total | ug/l | GMZ | 200 | | < 110 | | | | < 110 | | | | < 98 | | | | < 98 | | | < 100 | |
| Bedrock | Upgradient | G09M | Boron, total | ug/l | GMZ | 200 | | < 110 | | | | < 110 | | | | < 98 | | | | < 98 | | | < 100 | |
| Bedrock | Upgradient | G13D | Boron, total | ug/l | GMZ | 200 | | < 110 | | | | < 110 | | | | 150 | | | | < 98 | | | < 100 | |
| Bedrock | Upgradient | G13S | Boron, total | ug/l | GMZ | 200 | | < 110 | | | | < 110 | | | | < 98 | | | | < 98 | | | < 100 | |
| Bedrock | Downgradient | G14D | Boron, total | ug/l | GMZ | 200 | | < 110 | | | | < 110 | | | | 100 | | | | 120 | | | | 130 |
| Bedrock | Downgradient | G16D | Boron, total | ug/l | GMZ | 200 | | | | | | | | | | | | | | | | | < 100 | |
| Bedrock | Upgradient | G20D | Boron, total | ug/l | GMZ | 200 | | < 110 | | | | < 110 | | | | < 98 | | | | < 98 | | | < 100 | |
| Bedrock | Downgradient | G41D | Boron, total | ug/l | GMZ | 200 | | < 110 | | | | < 110 | | | | < 98 | | | | 300 | | | | 300 |
| Bedrock | Upgradient | G09D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 27.3 | 11.9 | 19.1 | 21.8 | 37.9 | 23.1 | 14 | 9.2 | 11 | 18 | 190 | 31 | 24 | 31 | 34 | 35 | 37 | 38 |
| Bedrock | Upgradient | G09M | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 117 | 100 | 143 | 155 | 165 | 181 | 160 | 190 | 140 | 150 | 20 | 190 | 190 | 200 | 170 | 180 | 180 | 180 |
| Bedrock | Upgradient | G13D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 31.6 | 53.8 | 46.1 | 42.6 | 44.1 | 48.2 | 48 | 31 | < 2 | 37 | 34 | 30 | 30 | 92 | 42 | 46 | 41 | 64 |
| Bedrock | Upgradient | G13S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 45.8 | 64.7 | 58.7 | 49.2 | 48.6 | 48.3 | 44 | 36 | < 2 | 45 | 33 | 26 | 28 | 53 | 30 | 32 | 35 | 72 |
| Bedrock | Downgradient | G14D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 11.8 | 3.4 | 7.3 | 8.4 | 12.8 | 8.35 | 6.4 | 13 | 32 | 36 | 90 | 87 | 40 | 32 | 76 | 81 | 52 | 35 |
| Bedrock | Downgradient | G16D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | | | | | | | | | | | | | | | | | | 8 |
| Bedrock | Upgradient | G20D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 19.7 | 12.9 | 20.4 | 19.8 | 18.9 | 18.6 | 16 | 16 | 17 | 20 | 22 | 20 | 18 | 23 | 23 | 23 | 19 | 21 |
| Bedrock | Downgradient | G41D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 82.9 | 38.8 | 105 | 14.9 | 14.8 | 16.4 | 40 | 13 | 14 | 19 | 180 | < 2 | 180 | 210 | 200 | 140 | 18 | 150 |
| Bedrock | Upgradient | G09D | Chloride, total | mg/l | GMZ | 87.51186 | | 16.5 | | | | 26.5 | | | | 2.5 | | | | 31 | | | | 36 |
| Bedrock | Upgradient | G09M | Chloride, total | mg/l | GMZ | 87.51186 | | 112 | | | | 192 | | | | 160 | | | | 200 | | | | 180 |
| Bedrock | Upgradient | G13D | Chloride, total | mg/l | GMZ | 87.51186 | | 54.7 | | | | 45.4 | | | | 32 | | | | 91 | | | | 68 |
| Bedrock | Upgradient | G13S | Chloride, total | mg/l | GMZ | 87.51186 | | 75.5 | | | | 50.2 | | | | 20 | | | | 55 | | | | 74 |
| Bedrock | Downgradient | G14D | Chloride, total | mg/l | GMZ | 87.51186 | | 4.2 | | | | 7.71 | | | | 36 | | | | 34 | | | | 40 |
| Bedrock | Downgradient | G16D | Chloride, total | mg/l | GMZ | 87.51186 | | | | | | | | | | | | | | | | | | 8.2 |
| Bedrock | Upgradient | G20D | Chloride, total | mg/l | GMZ | 87.51186 | | 14.1 | | | | 17.1 | | | | 20 | | | | 23 | | | | 20 |
| Bedrock | Downgradient | G41D | Chloride, total | mg/l | GMZ | 87.51186 | | 42.5 | | | | 16.2 | | | | 20 | | | | 220 | | | | 160 |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 1stQtr97 | 2ndQtr97 | 3rdQtr97 | 4thQtr97 | 1stQtr98 | 2ndQtr98 | 3rdQtr98 | 4thQtr98 | 1stQtr99 | 2ndQtr99 | 3rdQtr99 | 4thQtr99 | 1stQtr00 | 2ndQtr00 | 3rdQtr00 | 4thQtr00 | 1stQtr01 | 2ndQtr01 |
|---------|--------------|---------|-------------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Bedrock | Upgradient | G09D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G09M | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G13D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G13S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Downgradient | G14D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | 5.9 | |
| Bedrock | Downgradient | G16D | Ethylbenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | | | < 1 | |
| Bedrock | Upgradient | G20D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Downgradient | G41D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Bedrock | Upgradient | G09D | Fluoride, total | mg/l | GMZ | 273.35 | | < 0.1 | | | | 0.104 | | | | 0.49 | | | | < 0.1 | | | 0.47 | |
| Bedrock | Upgradient | G09M | Fluoride, total | mg/l | GMZ | 273.35 | | < 0.1 | | | | 0.128 | | | | 0.45 | | | | < 0.1 | | | 0.48 | |
| Bedrock | Upgradient | G13D | Fluoride, total | mg/l | GMZ | 273.35 | | < 0.1 | | | | < 0.1 | | | | 0.78 | | | | < 0.1 | | | 0.47 | |
| Bedrock | Upgradient | G13S | Fluoride, total | mg/l | GMZ | 273.35 | | 0.11 | | | | < 0.1 | | | | 0.84 | | | | < 0.1 | | | 0.46 | |
| Bedrock | Downgradient | G14D | Fluoride, total | mg/l | GMZ | 273.35 | | < 0.1 | | | | 0.108 | | | | 0.82 | | | | < 0.1 | | | 0.41 | |
| Bedrock | Downgradient | G16D | Fluoride, total | mg/l | GMZ | 273.35 | | | | | | | | | | | | | | | | | 0.53 | |
| Bedrock | Upgradient | G20D | Fluoride, total | mg/l | GMZ | 273.35 | | 0.11 | | | | < 0.1 | | | | 0.64 | | | | 0.5 | | | 0.51 | |
| Bedrock | Downgradient | G41D | Fluoride, total | mg/l | GMZ | 273.35 | | 0.13 | | | | 0.125 | | | | 1 | | | | < 0.1 | | | 0.54 | |
| Bedrock | Upgradient | G09D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 1.3 | 0.93 | 0.84 | 0.84 | 0.84 | 0.53 | 0.5 | 0.28 | 0.59 | < 0.2 | 2.1 | < 0.2 | 0.22 | < 0.2 | < 0.2 | 0.79 | < 0.2 | 1.6 |
| Bedrock | Upgradient | G09M | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 0.1 | 3.25 | 3.85 | 2.29 | 1.45 | 2.33 | 2.6 | 2.3 | 2.2 | 0.9 | < 0.2 | 0.24 | < 0.2 | 1.1 | 1.7 | 2.9 | 1.3 | 1.6 |
| Bedrock | Upgradient | G13D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 1.55 | 1.12 | 2.01 | 1.16 | 0.11 | 1.74 | 0.44 | 0.25 | 0.94 | < 0.2 | < 0.2 | 0.28 | 9.6 | < 0.2 | < 0.2 | 0.3 | < 0.2 | < 0.2 |
| Bedrock | Upgradient | G13S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 0.11 | 0.16 | 0.11 | < 0.1 | < 0.1 | < 0.1 | < 0.05 | < 0.026 | < 0.2 | 0.32 | < 0.2 | 0.22 | 8.6 | < 0.2 | 0.37 | 1.8 | 1 | 0.76 |
| Bedrock | Downgradient | G14D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.05 | < 0.026 | < 0.2 | < 0.05 | < 0.2 | < 0.2 | 0.47 | < 0.2 | < 0.2 | 0.22 | < 0.2 | < 0.2 |
| Bedrock | Downgradient | G16D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | | | | | | | | | | | | | | | | | 2.2 | |
| Bedrock | Upgradient | G20D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 5.13 | 4.24 | 5.57 | 3.24 | 5.73 | 3.91 | 3.8 | 4.2 | 3.8 | 4.7 | 3.8 | 4.5 | 4.2 | 4.8 | 4.8 | 8.9 | 3.8 | 4.2 |
| Bedrock | Downgradient | G41D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 2.3 | 3.96 | 1.5 | 6.78 | 7.98 | 5.64 | 4.9 | 7.3 | 6.3 | 6.7 | 2.1 | 2.5 | 2 | 0.25 | 1.1 | 7.3 | 6.2 | 1.5 |
| Bedrock | Upgradient | G09D | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 1.27 | | | | 0.611 | | | | 0.29 | | | | < 0.2 | | | < 0.2 | |
| Bedrock | Upgradient | G09M | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 3.43 | | | | 2.1 | | | | 2.6 | | | | 1.3 | | | 1.2 | |
| Bedrock | Upgradient | G13D | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 1.11 | | | | 1.75 | | | | < 0.05 | | | | 0.24 | | | < 0.2 | |
| Bedrock | Upgradient | G13S | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 0.32 | | | | < 0.1 | | | | 0.3 | | | | < 0.2 | | | 0.74 | |
| Bedrock | Downgradient | G14D | Nitrate as N, total | mg/l | GMZ | 11.7389 | | < 0.1 | | | | 0.169 | | | | < 0.05 | | | | < 0.2 | | | < 0.2 | |
| Bedrock | Downgradient | G16D | Nitrate as N, total | mg/l | GMZ | 11.7389 | | | | | | | | | | | | | | | | | 2.2 | |
| Bedrock | Upgradient | G20D | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 4.54 | | | | 4.6 | | | | 4.6 | | | | 4.8 | | | 4.1 | |
| Bedrock | Downgradient | G41D | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 4.08 | | | | 5.77 | | | | 6.9 | | | | 0.25 | | | 1.1 | |
| Bedrock | Upgradient | G09D | Potassium, total | mg/l | GMZ | 29.00582 | | 1.5 | | | | < 2 | | | | 0.94 | | | | 0.73 | | | 0.89 | |
| Bedrock | Upgradient | G09M | Potassium, total | mg/l | GMZ | 29.00582 | | < 1.1 | | | | < 2 | | | | 0.89 | | | | 0.84 | | | 0.7 | |
| Bedrock | Upgradient | G13D | Potassium, total | mg/l | GMZ | 29.00582 | | 5.2 | | | | 4.78 | | | | 11 | | | | 5.8 | | | 4.8 | |
| Bedrock | Upgradient | G13S | Potassium, total | mg/l | GMZ | 29.00582 | | 4.8 | | | | 6.81 | | | | 5.3 | | | | 4 | | | 4 | |
| Bedrock | Downgradient | G14D | Potassium, total | mg/l | GMZ | 29.00582 | | 3.1 | | | | 2.3 | | | | 2.2 | | | | 2.3 | | | 2.3 | |
| Bedrock | Downgradient | G16D | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | | | 1.2 | |
| Bedrock | Upgradient | G20D | Potassium, total | mg/l | GMZ | 29.00582 | | 1.4 | | | | < 2 | | | | 1.6 | | | | 1.7 | | | 1.5 | |
| Bedrock | Downgradient | G41D | Potassium, total | mg/l | GMZ | 29.00582 | | 9.4 | | | | < 2 | | | | 1.9 | | | | 25 | | | 25 | |
| Bedrock | Upgradient | G09D | Sodium, total | mg/l | GMZ | 164.7897 | | 16 | | | | 16.7 | | | | 10 | | | | 10 | | | 18 | |
| Bedrock | Upgradient | G09M | Sodium, total | mg/l | GMZ | 164.7897 | | 41 | | | | 53 | | | | 57 | | | | 68 | | | 70 | |
| Bedrock | Upgradient | G13D | Sodium, total | mg/l | GMZ | 164.7897 | | 33 | | | | 33.8 | | | | 45 | | | | 37 | | | 39 | |
| Bedrock | Upgradient | G13S | Sodium, total | mg/l | GMZ | 164.7897 | | 52 | | | | 36.1 | | | | 33 | | | | 28 | | | 39 | |
| Bedrock | Downgradient | G14D | Sodium, total | mg/l | GMZ | 164.7897 | | 12 | | | | 17.1 | | | | 12 | | | | 19 | | | 19 | |
| Bedrock | Downgradient | G16D | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | | | 4.7 | |
| Bedrock | Upgradient | G20D | Sodium, total | mg/l | GMZ | 164.7897 | | 8 | | | | 6.36 | | | | 8.1 | | | | 7.6 | | | 6.7 | |
| Bedrock | Downgradient | G41D | Sodium, total | mg/l | GMZ | 164.7897 | | 28 | | | | 4.72 | | | | 6.6 | | | | 86 | | | 69 | |
| Bedrock | Upgradient | G09D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | < 5 | |
| Bedrock | Upgradient | G09M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | < 5 | |
| Bedrock | Upgradient | G13D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | < 5 | |
| Bedrock | Upgradient | G13S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | < 5 | |
| Bedrock | Downgradient | G14D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | < 5 | |
| Bedrock | Downgradient | G16D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | | | < 5 | |
| Bedrock | Upgradient | G20D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | < 5 | |
| Bedrock | Downgradient | G41D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | 6 | | | | < 5 | | | | < 5 | | | | 13 | | | 11 | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 1stQtr97 | 2ndQtr97 | 3rdQtr97 | 4thQtr97 | 1stQtr98 | 2ndQtr98 | 3rdQtr98 | 4thQtr98 | 1stQtr99 | 2ndQtr99 | 3rdQtr99 | 4thQtr99 | 1stQtr00 | 2ndQtr00 | 3rdQtr00 | 4thQtr00 | 1stQtr01 | 2ndQtr01 |
|-------|--------------|---------|-------------------------|-------|---------|------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G03M | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G16M | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G18D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G33D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G34D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G35D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G36S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G37D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G38S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Compliance | G39S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G41M | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Compliance | G52M | 1,2,3-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | 1,2,3-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | 1,2,3-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G16M | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G18D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G33D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G34D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G35D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G36S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G37D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G38S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Compliance | G39S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G41M | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Compliance | G52M | 1,2,4-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | 1,2,4-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | 1,2,4-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | 2.8 | | | 3.6 | |
| Lower | Downgradient | G16M | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | < 5 | | | | 23 | | | | 8.6 | | | < 1 | |
| Lower | Downgradient | G18D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G33D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G34D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G35D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | 2.7 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G36S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G37D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G38S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Compliance | G39S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | 4.3 | | | 3.4 | |
| Lower | Downgradient | G41M | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | 6 | | | | 6 | | | | 3.9 | | | | 5.4 | | | 5.3 | |
| Lower | Compliance | G52M | 1,4-Dichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | 1,4-Dichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | 1,4-Dichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 6.46 | 5.86 | 1.34 | 3.76 | 1.82 | 1.61 | 1.2 | 1.9 | 0.72 | 0.57 | 3.6 | 47 | 42 | 72 | 160 | 160 | 200 | 150 |
| Lower | Downgradient | G16M | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 1010 | | 0.23 | 16.6 | 9.04 | 5.98 | 4.6 | | < 0.1 | 130 | 1.3 | 1.4 | < 0.1 | 3.1 | 17 | 76 | 45 | 34 |
| Lower | Downgradient | G18D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.07 | 0.1 | 0.05 | 0.13 | 0.18 | 0.299 | 0.38 | < 0.061 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | 0.12 | 0.54 | 1.5 | 0.34 | < 0.1 |
| Lower | Downgradient | G33D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.07 | 0.17 | < 0.05 | 1.21 | 0.3 | < 0.05 | 57 | < 0.061 | < 0.1 | 0.35 | 0.67 | 0.24 | 0.15 | < 0.1 | 0.17 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G34D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.24 | 0.09 | < 0.05 | | < 0.05 | 0.107 | < 0.1 | < 0.061 | < 0.1 | < 0.1 | < 0.1 | 0.16 | < 0.1 | < 0.1 | 0.14 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G35D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 45.5 | 121 | 24.4 | 638 | 184 | 40.2 | < 0.1 | 130 | 270 | 190 | 15 | 3.8 | 3.1 | 16 | 11 | 5 | 3.1 | 4.3 |
| Lower | Downgradient | G36S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.1 | 0.16 | < 0.05 | 0.14 | 0.16 | 0.162 | 0.11 | < 0.061 | < 0.1 | | < 0.1 | < 0.1 | < 0.1 | < 0.1 | 0.16 | 0.11 | < 0.1 | < 0.1 |
| Lower | Downgradient | G37D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | | | | | | | | | 1.5 | 2.1 | 2.3 | 1.7 | 1.4 | 1.2 | | | | 1.3 |
| Lower | Downgradient | G38S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 90.9 | 91.5 | 106 | 183 | 886 | 69.2 | 68 | 110 | 74 | 58 | 62 | 120 | 85 | 53 | 44 | 50 | 63 | 46 |
| Lower | Compliance | G39S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.68 | 0.54 | 0.1 | 0.78 | 0.51 | 0.55 | 0.25 | 0.57 | 0.21 | 0.24 | 1.3 | 1.1 | 1.3 | 1.6 | 2.5 | 4.5 | 4.4 | 5 |
| Lower | Downgradient | G41M | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 144 | 153 | 152 | 237 | 190 | 164 | 170 | 130 | 0.51 | 100 | 140 | 60 | 93 | 72 | 82 | 130 | 74 | 120 |
| Lower | Compliance | G52M | Ammonia as N, dissolved | mg/L | G1, GMZ | 0.9 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Ammonia as N, dissolved | mg/L | G1, GMZ | 0.9 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Ammonia as N, dissolved | mg/L | G1, GMZ | 0.9 | | | | | | | | | | | | | | | | | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 1stQtr97 | 2ndQtr97 | 3rdQtr97 | 4thQtr97 | 1stQtr98 | 2ndQtr98 | 3rdQtr98 | 4thQtr98 | 1stQtr99 | 2ndQtr99 | 3rdQtr99 | 4thQtr99 | 1stQtr00 | 2ndQtr00 | 3rdQtr00 | 4thQtr00 | 1stQtr01 | 2ndQtr01 |
|-------|--------------|---------|---------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G03M | Ammonia as N, total | mg/l | GMZ | 900 | | 6.52 | | | | 16.1 | | | | 0.65 | | | | 72 | | | | 160 |
| Lower | Downgradient | G16M | Ammonia as N, total | mg/l | GMZ | 900 | | | | | | 4.5 | | | | 170 | | | | 3.2 | | | | 40 |
| Lower | Downgradient | G18D | Ammonia as N, total | mg/l | GMZ | 900 | | 0.12 | | | | 0.071 | | | | < 0.1 | | | | 0.41 | | | < 0.1 | |
| Lower | Downgradient | G33D | Ammonia as N, total | mg/l | GMZ | 900 | | 0.25 | | | | 0.066 | | | | < 0.1 | | | | < 0.1 | | | | < 0.1 |
| Lower | Downgradient | G34D | Ammonia as N, total | mg/l | GMZ | 900 | | 0.13 | | | | 0.098 | | | | 280 | | | | < 0.1 | | | | < 0.1 |
| Lower | Downgradient | G35D | Ammonia as N, total | mg/l | GMZ | 900 | | 129 | | | | 49.5 | | | | 140 | | | | 85 | | | | 4.7 |
| Lower | Downgradient | G36S | Ammonia as N, total | mg/l | GMZ | 900 | | 0.24 | | | | 0.171 | | | | < 0.1 | | | | < 0.1 | | | < 0.1 | |
| Lower | Downgradient | G37D | Ammonia as N, total | mg/l | GMZ | 900 | | | | | | | | | | 2.2 | | | | 1.2 | | | | 1.3 |
| Lower | Downgradient | G38S | Ammonia as N, total | mg/l | GMZ | 900 | | 105 | | | | 70 | | | | 82 | | | | 59 | | | | 48 |
| Lower | Compliance | G39S | Ammonia as N, total | mg/l | GMZ | 900 | | 0.58 | | | | 0.531 | | | | 0.31 | | | | 1.8 | | | | 4.8 |
| Lower | Downgradient | G41M | Ammonia as N, total | mg/l | GMZ | 900 | | 159 | | | | 167 | | | | 120 | | | | 81 | | | | 120 |
| Lower | Compliance | G52M | Ammonia as N, total | mg/L | GMZ | 900 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Ammonia as N, total | mg/L | GMZ | 900 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Ammonia as N, total | mg/L | GMZ | 900 | | | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | 3 | < 2 | < 2 | < 2 | < 2 | < 2 | < 3 | < 2 | < 3 | < 0.84 | < 3 | < 3 | < 3 | 1.9 | < 2 | 2.4 | 2.6 | 2.5 |
| Lower | Downgradient | G16M | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | | | < 2 | < 2 | < 2 | < 2 | < 3 | < 3 | < 3 | 3 | < 3 | < 3 | < 3 | < 3 | < 2 | < 2 | < 2 | < 2 |
| Lower | Downgradient | G18D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | < 2 | < 2 | 5.2 | < 2 | < 3 | < 2 | < 3 | < 0.84 | < 3 | < 3 | < 3 | < 0.84 | < 2 | < 2 | < 2 | < 2 |
| Lower | Downgradient | G33D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | < 2 | < 2 | < 2 | < 2 | 9 | < 0.53 | < 3 | < 0.84 | < 3 | < 3 | < 3 | < 0.84 | < 2 | < 2 | < 2 | < 2 |
| Lower | Downgradient | G34D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | < 2 | < 2 | < 2 | 3.1 | < 3 | < 0.53 | < 3 | < 0.84 | < 3 | < 3 | < 3 | < 0.84 | < 2 | < 2 | < 2 | < 2 |
| Lower | Downgradient | G35D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | < 2 | < 2 | 8.7 | 5.66 | < 3 | 14 | 14 | 13 | 9.2 | < 3 | < 3 | < 0.84 | < 2 | < 2 | < 2 | < 2 |
| Lower | Downgradient | G36S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | < 2 | 2.6 | < 2 | < 2 | < 3 | < 0.53 | < 3 | < 0.84 | < 3 | < 3 | < 3 | < 0.84 | < 2 | < 2 | < 2 | < 2 |
| Lower | Downgradient | G37D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | | | | | | | | | < 3 | < 0.84 | < 3 | < 3 | < 3 | < 0.84 | | | < 2 | |
| Lower | Downgradient | G38S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | 3.2 | 3.2 | 3.1 | 3.44 | < 3 | 3.3 | < 3 | < 0.84 | 5.2 | 6.4 | 7.6 | 5.3 | 3.4 | 5.3 | 5.7 | 4.1 |
| Lower | Compliance | G39S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 2.2 | < 2 | < 2 | < 2 | < 2 | < 2 | < 3 | < 2 | < 3 | < 0.84 | < 3 | < 3 | < 3 | < 0.84 | < 2 | < 2 | < 2 | < 2 |
| Lower | Downgradient | G41M | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | 20 | 24 | 29 | 27 | 23 | 6 | < 3 | 29 | 29 | 25 | 17 | 19 | 16 | 16 | 24 | 18 | 25 | 16 |
| Lower | Compliance | G52M | Arsenic, Dissolved | ug/L | G1, GMZ | 2 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Arsenic, Dissolved | ug/L | G1, GMZ | 2 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Arsenic, Dissolved | ug/L | G1, GMZ | 2 | | | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | < 2 | | | | < 3 | | | | < 3 | | | | < 10 |
| Lower | Downgradient | G16M | Arsenic, total | ug/l | GMZ | 10 | | 0 | | | | < 2 | | | | 5 | | | | 15 | | | | < 10 |
| Lower | Downgradient | G18D | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | < 2 | | | | < 3 | | | | < 3 | | | | < 10 |
| Lower | Downgradient | G33D | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | < 2 | | | | 4.9 | | | | 4 | | | | < 10 |
| Lower | Downgradient | G34D | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | < 2 | | | | < 3 | | | | < 3 | | | | < 10 |
| Lower | Downgradient | G35D | Arsenic, total | ug/l | GMZ | 10 | | 5 | | | | 6.55 | | | | 36 | | | | 3.1 | | | | < 10 |
| Lower | Downgradient | G36S | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | 6.66 | | | | < 3 | | | | < 3 | | | | < 10 |
| Lower | Downgradient | G37D | Arsenic, total | ug/l | GMZ | 10 | | | | | | | | | | 4.6 | | | | < 3 | | | | < 10 |
| Lower | Downgradient | G38S | Arsenic, total | ug/l | GMZ | 10 | | 3 | | | | 6.99 | | | | 6.1 | | | | 6.5 | | | | < 10 |
| Lower | Compliance | G39S | Arsenic, total | ug/l | GMZ | 10 | | < 2 | | | | 3.5 | | | | < 3 | | | | 3.5 | | | | < 10 |
| Lower | Downgradient | G41M | Arsenic, total | ug/l | GMZ | 10 | | 30 | | | | 10 | | | | 35 | | | | 38 | | | | 17 |
| Lower | Compliance | G52M | Arsenic, total | ug/L | GMZ | 10 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Arsenic, total | ug/L | GMZ | 10 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Arsenic, total | ug/L | GMZ | 10 | | | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Barium, total | ug/l | GMZ | 225180.6 | | 150 | | | | 97.9 | | | | 110 | | | | 620 | | | | 550 |
| Lower | Downgradient | G16M | Barium, total | ug/l | GMZ | 225180.6 | | 0 | | | | 374 | | | | 550 | | | | 490 | | | | 400 |
| Lower | Downgradient | G18D | Barium, total | ug/l | GMZ | 225180.6 | | < 56 | | | | < 56 | | | | 41 | | | | 41 | | | | 45 |
| Lower | Downgradient | G33D | Barium, total | ug/l | GMZ | 225180.6 | | 110 | | | | 80.1 | | | | 110 | | | | 98 | | | | 92 |
| Lower | Downgradient | G34D | Barium, total | ug/l | GMZ | 225180.6 | | < 56 | | | | < 56 | | | | 32 | | | | 33 | | | | 31 |
| Lower | Downgradient | G35D | Barium, total | ug/l | GMZ | 225180.6 | | 1200 | | | | 128 | | | | 560 | | | | 860 | | | | 230 |
| Lower | Downgradient | G36S | Barium, total | ug/l | GMZ | 225180.6 | | 170 | | | | 174 | | | | 210 | | | | 170 | | | | 160 |
| Lower | Downgradient | G37D | Barium, total | ug/l | GMZ | 225180.6 | | | | | | | | | | 98 | | | | 53 | | | | 49 |
| Lower | Downgradient | G38S | Barium, total | ug/l | GMZ | 225180.6 | | 1200 | | | | 924 | | | | 1100 | | | | 820 | | | | 810 |
| Lower | Compliance | G39S | Barium, total | ug/l | GMZ | 225180.6 | | 140 | | | | 176 | | | | 160 | | | | 210 | | | | 250 |
| Lower | Downgradient | G41M | Barium, total | ug/l | GMZ | 225180.6 | | 570 | | | | 334 | | | | 390 | | | | 440 | | | | 430 |
| Lower | Compliance | G52M | Barium, total | ug/L | GMZ | 225180.6 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Barium, total | ug/L | GMZ | 225180.6 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Barium, total | ug/L | GMZ | 225180.6 | | | | | | | | | | | | | | | | | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 1stQtr97 | 2ndQtr97 | 3rdQtr97 | 4thQtr97 | 1stQtr98 | 2ndQtr98 | 3rdQtr98 | 4thQtr98 | 1stQtr99 | 2ndQtr99 | 3rdQtr99 | 4thQtr99 | 1stQtr00 | 2ndQtr00 | 3rdQtr00 | 4thQtr00 | 1stQtr01 | 2ndQtr01 |
|-------|--------------|---------|-------------------------|-------|---------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G03M | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G16M | Ethylbenzene | ug/l | G2, GMZ | 5 | | | | | | < 5 | | | | 5.4 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G18D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G33D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G34D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G35D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G36S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G37D | Ethylbenzene | ug/l | G2, GMZ | 5 | | | | | | < 1 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G38S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Compliance | G39S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Downgradient | G41M | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 5 | | | | < 5 | | | | < 1 | | | | < 1 | | | < 1 | |
| Lower | Compliance | G52M | Ethylbenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Ethylbenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Ethylbenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Fluoride, total | mg/l | GMZ | 273.35 | | 0.13 | | | | 0.113 | | | | 0.65 | | | | < 0.1 | | | 0.49 | |
| Lower | Downgradient | G16M | Fluoride, total | mg/l | GMZ | 273.35 | | | | | | 0.116 | | | | 0.79 | | | | < 0.1 | | | 0.54 | |
| Lower | Downgradient | G18D | Fluoride, total | mg/l | GMZ | 273.35 | | < 0.1 | | | | < 0.1 | | | | 0.87 | | | | 0.47 | | | 0.49 | |
| Lower | Downgradient | G33D | Fluoride, total | mg/l | GMZ | 273.35 | | 0.15 | | | | 0.158 | | | | < 0.1 | | | | 0.47 | | | 0.48 | |
| Lower | Downgradient | G34D | Fluoride, total | mg/l | GMZ | 273.35 | | < 0.1 | | | | 0.11 | | | | < 0.1 | | | | 0.47 | | | 0.48 | |
| Lower | Downgradient | G35D | Fluoride, total | mg/l | GMZ | 273.35 | | 0.15 | | | | 0.199 | | | | < 0.1 | | | | < 0.1 | | | 0.45 | |
| Lower | Downgradient | G36S | Fluoride, total | mg/l | GMZ | 273.35 | | 0.13 | | | | 0.122 | | | | 0.77 | | | | 0.47 | | | 0.45 | |
| Lower | Downgradient | G37D | Fluoride, total | mg/l | GMZ | 273.35 | | | | | | | | | | < 0.1 | | | | 0.46 | | | 0.5 | |
| Lower | Downgradient | G38S | Fluoride, total | mg/l | GMZ | 273.35 | | 0.19 | | | | 0.188 | | | | < 0.1 | | | | 0.53 | | | 0.54 | |
| Lower | Compliance | G39S | Fluoride, total | mg/l | GMZ | 273.35 | | < 0.1 | | | | < 0.1 | | | | 0.91 | | | | < 0.1 | | | 0.45 | |
| Lower | Downgradient | G41M | Fluoride, total | mg/l | GMZ | 273.35 | | 0.16 | | | | 0.278 | | | | 0.63 | | | | < 0.1 | | | 0.55 | |
| Lower | Compliance | G52M | Fluoride, total | mg/L | GMZ | 273.35 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Fluoride, total | mg/L | GMZ | 273.35 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Fluoride, total | mg/L | GMZ | 273.35 | | | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 6.96 | 8.52 | 7.36 | 7.68 | 8.98 | 8.49 | 7.9 | 9.1 | 8.1 | 9 | < 0.2 | < 0.2 | < 0.2 | < 0.2 | < 0.2 | 0.68 | 4.6 | 7.9 |
| Lower | Downgradient | G16M | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | | | 0.58 | 1.1 | < 0.1 | 5.86 | 8.2 | | 4.8 | 0.4 | < 0.2 | < 0.2 | 0.34 | 0.58 | 2.7 | 3.6 | < 0.2 | 2.2 |
| Lower | Downgradient | G18D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 10.4 | 11.7 | 10.7 | 8.86 | 12.7 | 10.5 | 11 | 11 | 10 | 11 | 11 | 13 | 12 | 12 | 10 | 7.2 | 12 | 11 |
| Lower | Downgradient | G33D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 1.19 | 11.5 | 8.67 | 10.9 | < 0.1 | 6.58 | 0.089 | 10 | 9.4 | 12 | 7.7 | 7.8 | 5.4 | 4.5 | 4.8 | 7.5 | 7.7 | 3.3 |
| Lower | Downgradient | G34D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 0.77 | 8.67 | 4.65 | 8.32 | < 0.1 | 5.8 | 6.8 | 8.9 | 7.8 | 8.7 | 7.5 | 8.8 | 9.4 | 10 | 9.3 | 11 | 10 | 9.1 |
| Lower | Downgradient | G35D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 1.92 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | 10 | 2.1 | < 0.2 | 0.065 | < 0.2 | 3.4 | 4.5 | 1 | 3.7 | 5.3 | 5.8 | 5.3 |
| Lower | Downgradient | G36S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 9.67 | 11.1 | 11 | 11.4 | 11.5 | 9.57 | 13 | 11 | 10 | 11 | 9.3 | 7 | 6.3 | 6.8 | 8.8 | 6.6 | 7.2 | 6.5 |
| Lower | Downgradient | G37D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | | | | | | | | | 9.1 | 1 | 7.6 | 8.1 | 8.4 | 11 | | | | 9.9 |
| Lower | Downgradient | G38S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | 0.556 | < 0.05 | 0.03 | 2.3 | 0.3 | < 0.2 | 0.43 | < 0.2 | < 0.2 | < 0.2 | 0.57 | < 0.2 | 0.36 |
| Lower | Compliance | G39S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | 0.1 | < 0.1 | 0.1 | 0.037 | < 0.2 | 0.25 | < 0.2 | < 0.2 | < 0.2 | < 0.2 | < 0.2 | 12 | 0.28 | 0.31 |
| Lower | Downgradient | G41M | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 0.18 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | < 0.05 | < 0.026 | 2.1 | < 0.05 | < 0.2 | < 0.2 | < 0.2 | < 0.2 | < 0.2 | 0.44 | < 0.2 | < 0.2 |
| Lower | Compliance | G52M | Nitrate as N, dissolved | mg/L | G1, GMZ | 11.74 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Nitrate as N, dissolved | mg/L | G1, GMZ | 11.74 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Nitrate as N, dissolved | mg/L | G1, GMZ | 11.74 | | | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 8.43 | | | | 9.21 | | | | 9.5 | | | | < 0.2 | | | < 0.2 | |
| Lower | Downgradient | G16M | Nitrate as N, total | mg/l | GMZ | 11.7389 | | | | | | 6.2 | | | | 0.38 | | | | 0.68 | | | 4.1 | |
| Lower | Downgradient | G18D | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 11.9 | | | | 11.1 | | | | 11 | | | | 12 | | | 11 | |
| Lower | Downgradient | G33D | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 12.1 | | | | 7.29 | | | | 1.6 | | | | 4.4 | | | 3.4 | |
| Lower | Downgradient | G34D | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 9.17 | | | | 5.56 | | | | 6.9 | | | | 9.9 | | | 9.1 | |
| Lower | Downgradient | G35D | Nitrate as N, total | mg/l | GMZ | 11.7389 | | < 0.1 | | | | < 0.1 | | | | < 0.2 | | | | 2.2 | | | 5.4 | |
| Lower | Downgradient | G36S | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 11.6 | | | | 11 | | | | 11 | | | | 6.8 | | | 6.5 | |
| Lower | Downgradient | G37D | Nitrate as N, total | mg/l | GMZ | 11.7389 | | | | | | | | | | 8.9 | | | | 11 | | | 9.2 | |
| Lower | Downgradient | G38S | Nitrate as N, total | mg/l | GMZ | 11.7389 | | < 0.1 | | | | 0.488 | | | | 8.9 | | | | < 0.2 | | | 2.2 | |
| Lower | Compliance | G39S | Nitrate as N, total | mg/l | GMZ | 11.7389 | | 0.11 | | | | < 0.1 | | | | 0.21 | | | | < 0.2 | | | 0.3 | |
| Lower | Downgradient | G41M | Nitrate as N, total | mg/l | GMZ | 11.7389 | | < 0.1 | | | | < 0.1 | | | | < 0.05 | | | | < 0.2 | | | < 0.2 | |
| Lower | Compliance | G52M | Nitrate as N, total | mg/L | GMZ | 11.7389 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Nitrate as N, total | mg/L | GMZ | 11.7389 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Nitrate as N, total | mg/L | GMZ | 11.7389 | | | | | | | | | | | | | | | | | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 1stQtr97 | 2ndQtr97 | 3rdQtr97 | 4thQtr97 | 1stQtr98 | 2ndQtr98 | 3rdQtr98 | 4thQtr98 | 1stQtr99 | 2ndQtr99 | 3rdQtr99 | 4thQtr99 | 1stQtr00 | 2ndQtr00 | 3rdQtr00 | 4thQtr00 | 1stQtr01 | 2ndQtr01 |
|-------|--------------|---------|------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G03M | Potassium, total | mg/l | GMZ | 29.00582 | | 8 | | | | 3.42 | | | | 3.9 | | | | 38 | | | | 88 |
| Lower | Downgradient | G16M | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | 7.08 | | | | 170 | | | | 18 | | | | 18 |
| Lower | Downgradient | G18D | Potassium, total | mg/l | GMZ | 29.00582 | | 3.4 | | | | 2.34 | | | | 3 | | | | 2.8 | | | | 3 |
| Lower | Downgradient | G33D | Potassium, total | mg/l | GMZ | 29.00582 | | 2.3 | | | | < 2 | | | | 2.2 | | | | 1.2 | | | | 1.1 |
| Lower | Downgradient | G34D | Potassium, total | mg/l | GMZ | 29.00582 | | 2.5 | | | | < 2 | | | | 1.9 | | | | 1.7 | | | | 1.8 |
| Lower | Downgradient | G35D | Potassium, total | mg/l | GMZ | 29.00582 | | 65 | | | | 34 | | | | 100 | | | | 46 | | | | 7.5 |
| Lower | Downgradient | G36S | Potassium, total | mg/l | GMZ | 29.00582 | | 1.8 | | | | < 2 | | | | 1.4 | | | | 0.94 | | | | 0.86 |
| Lower | Downgradient | G37D | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | 6.7 | | | | 3.3 | | | | 2.8 |
| Lower | Downgradient | G38S | Potassium, total | mg/l | GMZ | 29.00582 | | 46 | | | | 37.8 | | | | 37 | | | | 30 | | | | 1.2 |
| Lower | Compliance | G39S | Potassium, total | mg/l | GMZ | 29.00582 | | 4.2 | | | | 5.02 | | | | 5.6 | | | | 9.4 | | | | 8.9 |
| Lower | Downgradient | G41M | Potassium, total | mg/l | GMZ | 29.00582 | | 80 | | | | 81.7 | | | | 62 | | | | 49 | | | | 58 |
| Lower | Compliance | G52M | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Sodium, total | mg/l | GMZ | 164.7897 | | 17 | | | | 10.9 | | | | 12 | | | | 150 | | | | 260 |
| Lower | Downgradient | G16M | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | 14.6 | | | | 470 | | | | 28 | | | | 37 |
| Lower | Downgradient | G18D | Sodium, total | mg/l | GMZ | 164.7897 | | 9.1 | | | | 9.17 | | | | 8.6 | | | | 9.3 | | | | 11 |
| Lower | Downgradient | G33D | Sodium, total | mg/l | GMZ | 164.7897 | | 9.1 | | | | 5.92 | | | | 7.3 | | | | 5.3 | | | | 5.3 |
| Lower | Downgradient | G34D | Sodium, total | mg/l | GMZ | 164.7897 | | 6.2 | | | | 5.83 | | | | 6.1 | | | | 6.3 | | | | 6.5 |
| Lower | Downgradient | G35D | Sodium, total | mg/l | GMZ | 164.7897 | | 160 | | | | 28.1 | | | | 18 | | | | 140 | | | | 28 |
| Lower | Downgradient | G36S | Sodium, total | mg/l | GMZ | 164.7897 | | 9.8 | | | | 9.25 | | | | 11 | | | | 4.6 | | | | 5.2 |
| Lower | Downgradient | G37D | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | 9.8 | | | | 8.5 | | | | 8 |
| Lower | Downgradient | G38S | Sodium, total | mg/l | GMZ | 164.7897 | | 99 | | | | 57.8 | | | | 83 | | | | 52 | | | | 4.7 |
| Lower | Compliance | G39S | Sodium, total | mg/l | GMZ | 164.7897 | | 45 | | | | 42 | | | | 45 | | | | 47 | | | | 58 |
| Lower | Downgradient | G41M | Sodium, total | mg/l | GMZ | 164.7897 | | 180 | | | | 164 | | | | 150 | | | | 100 | | | | 140 |
| Lower | Compliance | G52M | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | 21 | | | | 43 |
| Lower | Downgradient | G16M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | < 5 | | | | 59 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G18D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G33D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G34D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G35D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | 27 | | | | < 5 | | | | 16 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G36S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G37D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G38S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | 13 | | | | 12 | | | | 18 | | | | < 5 | | | | < 5 |
| Lower | Compliance | G39S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | 6 | | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G41M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | 37 | | | | 30 | | | | 22 | | | | 14 | | | | 21 |
| Lower | Compliance | G52M | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | | | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 1stQtr97 | 2ndQtr97 | 3rdQtr97 | 4thQtr97 | 1stQtr98 | 2ndQtr98 | 3rdQtr98 | 4thQtr98 | 1stQtr99 | 2ndQtr99 | 3rdQtr99 | 4thQtr99 | 1stQtr00 | 2ndQtr00 | 3rdQtr00 | 4thQtr00 | 1stQtr01 | 2ndQtr01 |
|-------|--------------|---------|------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Upper | Downgradient | G119 | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | | | 12 | |
| Upper | Downgradient | G130 | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | | | 7.9 | |
| Upper | Downgradient | G15S | Potassium, total | mg/l | GMZ | 29.00582 | | 57 | | | | 60.9 | | | | 56 | | | | 60 | | | 59 | |
| Upper | Downgradient | G17S | Potassium, total | mg/l | GMZ | 29.00582 | | 2 | | | | 3.61 | | | | 6.4 | | | | 10 | | | 6.1 | |
| Upper | Downgradient | G18S | Potassium, total | mg/l | GMZ | 29.00582 | | 7.3 | | | | 15.9 | | | | 15 | | | | K 69 | | | | |
| Upper | Downgradient | G33S | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | | | 3.3 | |
| Upper | Downgradient | G34S | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | 17 | | | | 31 | | | 11 | |
| Upper | Downgradient | G35S | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | 24 | | | | 21 | | | 20 | |
| Upper | Downgradient | G37S | Potassium, total | mg/l | GMZ | 29.00582 | | 2.7 | | | | 2.51 | | | | 12 | | | | 12 | | | 5.1 | |
| Upper | Downgradient | G40S | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | 30.2 | | | | 30 | | | | 16 | | | 18 | |
| Upper | Downgradient | G41S | Potassium, total | mg/l | GMZ | 29.00582 | | 84 | | | | 54.8 | | | | 100 | | | | 33 | | | 52 | |
| Upper | Downgradient | G50S | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | | | | |
| Upper | Compliance | G52S | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | | | | |
| Upper | Compliance | G54S | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Potassium, total | mg/l | GMZ | 29.00582 | | 18 | | | | 14 | | | | 23 | | | | 87 | | | 91 | |
| Upper | Downgradient | R42S | Potassium, total | mg/l | GMZ | 29.00582 | | 3.4 | | | | 3.74 | | | | 18 | | | | 2.5 | | | 1.2 | |
| Upper | Downgradient | G119 | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | | | 8.8 | |
| Upper | Downgradient | G130 | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | | | 7.2 | |
| Upper | Downgradient | G15S | Sodium, total | mg/l | GMZ | 164.7897 | | 170 | | | | 175 | | | | 170 | | | | 190 | | | 130 | |
| Upper | Downgradient | G17S | Sodium, total | mg/l | GMZ | 164.7897 | | 18 | | | | 27.2 | | | | 30 | | | | 23 | | | 10 | |
| Upper | Downgradient | G18S | Sodium, total | mg/l | GMZ | 164.7897 | | 55 | | | | 76.1 | | | | 41 | | | | K 350 | | | | |
| Upper | Downgradient | G33S | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | | | 6.1 | |
| Upper | Downgradient | G34S | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | 48 | | | | 32 | | | 14 | |
| Upper | Downgradient | G35S | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | 20 | | | | 24 | | | 22 | |
| Upper | Downgradient | G37S | Sodium, total | mg/l | GMZ | 164.7897 | | 4.7 | | | | 4.56 | | | | 6.1 | | | | 11 | | | 7 | |
| Upper | Downgradient | G40S | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | 89.1 | | | | 63 | | | | 63 | | | 44 | |
| Upper | Downgradient | G41S | Sodium, total | mg/l | GMZ | 164.7897 | | 190 | | | | 116 | | | | 280 | | | | 51 | | | 120 | |
| Upper | Downgradient | G50S | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | | | | |
| Upper | Compliance | G52S | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | | | | |
| Upper | Compliance | G54S | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Sodium, total | mg/l | GMZ | 164.7897 | | 37 | | | | 44.7 | | | | 43 | | | | 160 | | | 160 | |
| Upper | Downgradient | R42S | Sodium, total | mg/l | GMZ | 164.7897 | | 43 | | | | 71.8 | | | | 72 | | | | 55 | | | 54 | |
| Upper | Downgradient | G119 | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | | | < 5 | |
| Upper | Downgradient | G130 | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | | | < 5 | |
| Upper | Downgradient | G15S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | 51 | | | | 39 | | | | 34 | | | | 29 | | | 22 | |
| Upper | Downgradient | G17S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | < 5 | |
| Upper | Downgradient | G18S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | 21 | | | | < 5 | | | | 240 | | | | |
| Upper | Downgradient | G33S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | | | < 5 | |
| Upper | Downgradient | G34S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | < 5 | | | | < 5 | | | < 5 | |
| Upper | Downgradient | G35S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | < 5 | | | | < 5 | | | < 5 | |
| Upper | Downgradient | G37S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 | | | < 5 | |
| Upper | Downgradient | G40S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | < 5 | | | | < 5 | | | | < 5 | | | < 5 | |
| Upper | Downgradient | G41S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | 23 | | | | 26 | | | | 48 | | | | 5.9 | | | 13 | |
| Upper | Downgradient | G50S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | | | | |
| Upper | Compliance | G52S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | | | | |
| Upper | Compliance | G54S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 5 | | | | < 5 | | | | < 5 | | | | 29 | | | 28 | |
| Upper | Downgradient | R42S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | 10 | | | | 6 | | | | < 5 | | | | < 5 | | | < 5 | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr01 | 4thQtr01 | 1stQtr02 | 2ndQtr02 | 3rdQtr02 | 4thQtr02 | 1stQtr03 | 2ndQtr03 | 2ndQtr03re | 3rdQtr03 | 4thQtr03 | 1stQtr04 | 2ndQtr04 | 2ndQtr04re | 3rdQtr04 | 3rdQtr04re |
|---------|--------------|---------|---------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|------------|----------|----------|----------|----------|------------|----------|------------|
| Bedrock | Upgradient | G09D | Arsenic, total | ug/l | GMZ | 10 | | | | 1 | | | | 1 | | | | | 2 | | | |
| Bedrock | Upgradient | G09M | Arsenic, total | ug/l | GMZ | 10 | | | | < 1 | | | | < 1 | | | | | < 1 | | | |
| Bedrock | Upgradient | G13D | Arsenic, total | ug/l | GMZ | 10 | | | | < 1 | | | | < 1 | | < 1 | < 1 | 1.2 | < 1 | | 1 | |
| Bedrock | Upgradient | G13S | Arsenic, total | ug/l | GMZ | 10 | | | | < 1 | | | | 1.9 | | 1.8 | 3.4 | 2.4 | 1.6 | | 2.4 | |
| Bedrock | Downgradient | G14D | Arsenic, total | ug/l | GMZ | 10 | | | | 12 | | | | 18 | 12 | | | | 5.7 | | | |
| Bedrock | Downgradient | G16D | Arsenic, total | ug/l | GMZ | 10 | | | | < 1 | | | | < 1 | | | | | 1.6 | | | |
| Bedrock | Upgradient | G20D | Arsenic, total | ug/l | GMZ | 10 | | | | < 1 | | | | < 1 | | | | | 1.2 | | | |
| Bedrock | Downgradient | G41D | Arsenic, total | ug/l | GMZ | 10 | | | | < 1 | | | | < 1 | | | | | < 1 | | | |
| Bedrock | Upgradient | G09D | Barium, total | ug/l | GMZ | 225180.6 | | | | 350 | | | | 440 | | | | | 440 | | | |
| Bedrock | Upgradient | G09M | Barium, total | ug/l | GMZ | 225180.6 | | | | 130 | | | | 120 | | | | | 110 | | | |
| Bedrock | Upgradient | G13D | Barium, total | ug/l | GMZ | 225180.6 | | | | 160 | | | | 170 | | 160 | 160 | 160 | 140 | | 150 | |
| Bedrock | Upgradient | G13S | Barium, total | ug/l | GMZ | 225180.6 | | | | 240 | | | | 170 | | 200 | 160 | 170 | 190 | | 220 | |
| Bedrock | Downgradient | G14D | Barium, total | ug/l | GMZ | 225180.6 | | | | 700 | | | | 840 | | | | | 540 | | | |
| Bedrock | Downgradient | G16D | Barium, total | ug/l | GMZ | 225180.6 | | | | 86 | | | | 94 | | | | | 120 | | | |
| Bedrock | Upgradient | G20D | Barium, total | ug/l | GMZ | 225180.6 | | | | 94 | | | | 89 | | | | | 89 | | | |
| Bedrock | Downgradient | G41D | Barium, total | ug/l | GMZ | 225180.6 | | | | 82 | | | | 50 | | | | | 60 | | | |
| Bedrock | Upgradient | G09D | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 98 | 40 | 49 | 55 | 57 | 64 | 40 | 55 | | 32 | 52 | 29 | 35 | | 62 | |
| Bedrock | Upgradient | G09M | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 98 | 40 | 38 | 33 | 39 | 37 | 30 | 21 | | 14 | 43 | 33 | 27 | | 31 | |
| Bedrock | Upgradient | G13D | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 98 | 120 | 140 | 95 | 110 | 120 | 80 | 90 | | 83 | 79 | 88 | 63 | | 65 | |
| Bedrock | Upgradient | G13S | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 98 | 140 | 250 | 83 | 120 | 140 | 120 | 120 | | 110 | 130 | 88 | 100 | 100 | 82 | |
| Bedrock | Downgradient | G14D | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 120 | 160 | 140 | 120 | 110 | 120 | 110 | 110 | | 84 | 110 | 90 | 98 | | 91 | |
| Bedrock | Downgradient | G16D | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 98 | 23 | 32 | 21 | 24 | 21 | 20 | 13 | | < 10 | 21 | < 10 | < 10 | | 14 | |
| Bedrock | Upgradient | G20D | Boron, Dissolved | ug/l | G1, GMZ | 98 | < 98 | 21 | 26 | 25 | 39 | 29 | 40 | 18 | | 11 | 26 | < 10 | 15 | | 24 | |
| Bedrock | Downgradient | G41D | Boron, Dissolved | ug/l | G1, GMZ | 98 | 230 | 220 | 12 | 100 | 31 | 14 | 10 | 18 | | 10 | 26 | < 10 | < 10 | | 12 | |
| Bedrock | Upgradient | G09D | Boron, total | ug/l | GMZ | 200 | | | | 45 | | | | 39 | | | | | 30 | | | |
| Bedrock | Upgradient | G09M | Boron, total | ug/l | GMZ | 200 | | | | 33 | | | | 20 | | | | | 41 | | | |
| Bedrock | Upgradient | G13D | Boron, total | ug/l | GMZ | 200 | | | | 89 | | | | 78 | | 95 | 79 | 150 | 68 | | 68 | |
| Bedrock | Upgradient | G13S | Boron, total | ug/l | GMZ | 200 | | | | 84 | | | | 120 | | 110 | 120 | 200 | 98 | | 88 | |
| Bedrock | Downgradient | G14D | Boron, total | ug/l | GMZ | 200 | | | | 100 | | | | 97 | | | | | 110 | | | |
| Bedrock | Downgradient | G16D | Boron, total | ug/l | GMZ | 200 | | | | 17 | | | | 11 | | | | | < 10 | | | |
| Bedrock | Upgradient | G20D | Boron, total | ug/l | GMZ | 200 | | | | 28 | | | | 21 | | | | | 40 | | | |
| Bedrock | Downgradient | G41D | Boron, total | ug/l | GMZ | 200 | | | | 110 | | | | 13 | | | | | < 10 | | | |
| Bedrock | Upgradient | G09D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 68 | 52 | 10 | 33 | 54 | 26 | 24 | 170 | | 26 | 26 | 40 | 51 | | 22 | |
| Bedrock | Upgradient | G09M | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 180 | 160 | 160 | 180 | 37 | 140 | 160 | 170 | | 200 | 190 | 190 | 220 | 250 | 250 | |
| Bedrock | Upgradient | G13D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 64 | 74 | 69 | 59 | 37 | 30 | 51 | 38 | | 70 | 68 | 59 | 86 | | 93 | 100 |
| Bedrock | Upgradient | G13S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 69 | 40 | 79 | Q 43 | 42 | 31 | 36 | 39 | | 39 | 43 | 46 | 38 | | 60 | |
| Bedrock | Downgradient | G14D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 41 | 38 | 38 | 32 | 63 | 51 | 41 | 40 | | 37 | 41 | 32 | 41 | | 38 | |
| Bedrock | Downgradient | G16D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 8.4 | 7.3 | 7.4 | 7.7 | 7.2 | 7.4 | 8.2 | 9.4 | | 9.1 | 12 | 10 | 10 | | 11 | |
| Bedrock | Upgradient | G20D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 20 | 17 | 15 | 18 | 20 | 26 | 29 | 28 | | 22 | 35 | 27 | 32 | | 24 | |
| Bedrock | Downgradient | G41D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 95 | 62 | 36 | 36 | 17 | 13 | 16 | 20 | | 17 | 28 | 23 | 24 | | 17 | |
| Bedrock | Upgradient | G09D | Chloride, total | mg/l | GMZ | 87.51186 | | | | 33 | | | | 170 | 69 | | | | 49 | | | |
| Bedrock | Upgradient | G09M | Chloride, total | mg/l | GMZ | 87.51186 | | | | 190 | | | | 170 | 170 | | | | 220 | 220 | | |
| Bedrock | Upgradient | G13D | Chloride, total | mg/l | GMZ | 87.51186 | | | | 59 | | | | 60 | | 66 | 76 | 61 | 85 | | 92 | |
| Bedrock | Upgradient | G13S | Chloride, total | mg/l | GMZ | 87.51186 | | | | 50 | | | | 32 | | 38 | 43 | 49 | 33 | | 70 | |
| Bedrock | Downgradient | G14D | Chloride, total | mg/l | GMZ | 87.51186 | | | | 35 | | | | 42 | | | | | 36 | | | |
| Bedrock | Downgradient | G16D | Chloride, total | mg/l | GMZ | 87.51186 | | | | 7.3 | | | | 9.2 | | | | | 10 | | | |
| Bedrock | Upgradient | G20D | Chloride, total | mg/l | GMZ | 87.51186 | | | | 18 | | | | 29 | | | | | 34 | | | |
| Bedrock | Downgradient | G41D | Chloride, total | mg/l | GMZ | 87.51186 | | | | 38 | | | | 18 | | | | | 23 | | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr01 | 4thQtr01 | 1stQtr02 | 2ndQtr02 | 3rdQtr02 | 4thQtr02 | 1stQtr03 | 2ndQtr03 | 2ndQtr03re | 3rdQtr03 | 4thQtr03 | 1stQtr04 | 2ndQtr04 | 2ndQtr04re | 3rdQtr04 | 3rdQtr04re |
|-------|--------------|---------|------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|------------|----------|----------|----------|----------|------------|----------|------------|
| Lower | Downgradient | G03M | Potassium, total | mg/l | GMZ | 29.00582 | | | | 63 | | | | 13 | | | | | 5.8 | | | |
| Lower | Downgradient | G16M | Potassium, total | mg/l | GMZ | 29.00582 | | | | 10 | | | | 19 | | | | | 14 | | | |
| Lower | Downgradient | G18D | Potassium, total | mg/l | GMZ | 29.00582 | | | | 2.6 | | | | 3.4 | | | | | 3.5 | | | |
| Lower | Downgradient | G33D | Potassium, total | mg/l | GMZ | 29.00582 | | | | 0.7 | | | | 0.92 | | | | | 4.8 | | | |
| Lower | Downgradient | G34D | Potassium, total | mg/l | GMZ | 29.00582 | | | | 1.6 | | | | 2.9 | | | | | 5.3 | | | |
| Lower | Downgradient | G35D | Potassium, total | mg/l | GMZ | 29.00582 | | | | 24 | | | | 25 | | | | | 10 | | | |
| Lower | Downgradient | G36S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 0.65 | | | | 0.94 | | | | | 0.9 | | | |
| Lower | Downgradient | G37D | Potassium, total | mg/l | GMZ | 29.00582 | | | | 2 | | | | 2.2 | | | | | 2.7 | | | |
| Lower | Downgradient | G38S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 25 | | | | 12 | | | | | 29 | | | |
| Lower | Compliance | G39S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 8.6 | | | | 9.5 | | | | | 8.9 | | | |
| Lower | Downgradient | G41M | Potassium, total | mg/l | GMZ | 29.00582 | | | | 49 | | | | 10 | | | | | 2.9 | | | |
| Lower | Compliance | G52M | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Sodium, total | mg/l | GMZ | 164.7897 | | | | 170 | | | | 17 | | | | | 13 | | | |
| Lower | Downgradient | G16M | Sodium, total | mg/l | GMZ | 164.7897 | | | | 14 | | | | 27 | | | | | 20 | | | |
| Lower | Downgradient | G18D | Sodium, total | mg/l | GMZ | 164.7897 | | | | 10 | | | | 11 | | | | | 8 | | | |
| Lower | Downgradient | G33D | Sodium, total | mg/l | GMZ | 164.7897 | | | | 3.9 | | | | 4.3 | | | | | 6.6 | | | |
| Lower | Downgradient | G34D | Sodium, total | mg/l | GMZ | 164.7897 | | | | 6.1 | | | | 4.1 | | | | | 3.3 | | | |
| Lower | Downgradient | G35D | Sodium, total | mg/l | GMZ | 164.7897 | | | | 83 | | | | 25 | | | | | 14 | | | |
| Lower | Downgradient | G36S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 4.1 | | | | 9.8 | | | | | 11 | | | |
| Lower | Downgradient | G37D | Sodium, total | mg/l | GMZ | 164.7897 | | | | 7.6 | | | | 9.4 | | | | | 9.9 | | | |
| Lower | Downgradient | G38S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 97 | | | | 44 | | | | | 94 | | | |
| Lower | Compliance | G39S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 47 | | | | 47 | | | | | 45 | | | |
| Lower | Downgradient | G41M | Sodium, total | mg/l | GMZ | 164.7897 | | | | 160 | | | | 16 | | | | | 13 | | | |
| Lower | Compliance | G52M | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | 34 | | | | < 5 | | | | | < 5 | | | |
| Lower | Downgradient | G16M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Lower | Downgradient | G18D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Lower | Downgradient | G33D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Lower | Downgradient | G34D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Lower | Downgradient | G35D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | 18 | | | | < 5 | | | | | < 5 | | | |
| Lower | Downgradient | G36S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Lower | Downgradient | G37D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Lower | Downgradient | G38S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | 10 | | | | 12 | 22 | | | | 17 | | | |
| Lower | Compliance | G39S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Lower | Downgradient | G41M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | 32 | | | | < 5 | | | | | < 5 | | | |
| Lower | Compliance | G52M | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr01 | 4thQtr01 | 1stQtr02 | 2ndQtr02 | 3rdQtr02 | 4thQtr02 | 1stQtr03 | 2ndQtr03 | 2ndQtr03re | 3rdQtr03 | 4thQtr03 | 1stQtr04 | 2ndQtr04 | 2ndQtr04re | 3rdQtr04 | 3rdQtr04re |
|-------|--------------|---------|------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|------------|----------|----------|----------|----------|------------|----------|------------|
| Upper | Downgradient | G119 | Potassium, total | mg/l | GMZ | 29.00582 | | | | 0.76 | | | | 1.5 | | | | | 1.2 | | | |
| Upper | Downgradient | G130 | Potassium, total | mg/l | GMZ | 29.00582 | | | | 0.56 | | | | 0.74 | | | | | 0.78 | | | |
| Upper | Downgradient | G15S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 48 | | | | 110 | | | | | 83 | | | |
| Upper | Downgradient | G17S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 1.4 | | | | 2.2 | | | | | 1.9 | | | |
| Upper | Downgradient | G18S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 34 | | | | 51 | | | | | 74 | | | |
| Upper | Downgradient | G33S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 0.61 | | | | 0.65 | | | | | 0.61 | | | |
| Upper | Downgradient | G34S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 4.8 | | | | 5.1 | | | | | 11 | | | |
| Upper | Downgradient | G35S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 19 | | | | 27 | | | | | 20 | | | |
| Upper | Downgradient | G37S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 3.1 | | | | 4.8 | | | | | 5.1 | | | |
| Upper | Downgradient | G40S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 16 | | | | 19 | | | | | 22 | | | |
| Upper | Downgradient | G41S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 53 | | | | 56 | | | | | 46 | | | |
| Upper | Downgradient | G50S | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | | |
| Upper | Compliance | G52S | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | | |
| Upper | Compliance | G54S | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 81 | | | | 44 | | | | | 25 | | | |
| Upper | Downgradient | R42S | Potassium, total | mg/l | GMZ | 29.00582 | | | | 0.61 | | | | 0.63 | | | | | 1 | | | |
| Upper | Downgradient | G119 | Sodium, total | mg/l | GMZ | 164.7897 | | | | 5.4 | | | | 7.6 | | | | | 6.9 | | | |
| Upper | Downgradient | G130 | Sodium, total | mg/l | GMZ | 164.7897 | | | | 4.5 | | | | 4.6 | | | | | 9.3 | | | |
| Upper | Downgradient | G15S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 140 | | | | 350 | | | | | 240 | | | |
| Upper | Downgradient | G17S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 20 | | | | 19 | | | | | 10 | | | |
| Upper | Downgradient | G18S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 22 | | | | 30 | | | | | 22 | | | |
| Upper | Downgradient | G33S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 4.5 | | | | 4.2 | | | | | 4.4 | | | |
| Upper | Downgradient | G34S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 12 | | | | 42 | | | | | 30 | | | |
| Upper | Downgradient | G35S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 42 | | | | 61 | | | | | 39 | | | |
| Upper | Downgradient | G37S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 15 | | | | 25 | | | | | 45 | | | |
| Upper | Downgradient | G40S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 45 | | | | 52 | | | | | 62 | | | |
| Upper | Downgradient | G41S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 150 | | | | 95 | | | | | 51 | | | |
| Upper | Downgradient | G50S | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | | |
| Upper | Compliance | G52S | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | | |
| Upper | Compliance | G54S | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 210 | | | | 58 | | | | | 30 | | | |
| Upper | Downgradient | R42S | Sodium, total | mg/l | GMZ | 164.7897 | | | | 50 | | | | 29 | | | | | 43 | | | |
| Upper | Downgradient | G119 | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Upper | Downgradient | G130 | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Upper | Downgradient | G15S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | 91 | | | | 85 | 74 | | | | 56 | | | |
| Upper | Downgradient | G17S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Upper | Downgradient | G18S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Upper | Downgradient | G33S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Upper | Downgradient | G34S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Upper | Downgradient | G35S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |
| Upper | Downgradient | G37S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | 8 | | | |
| Upper | Downgradient | G40S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | 8 | | | |
| Upper | Downgradient | G41S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | 26 | | | | 9 | 10 | | | | < 5 | | | |
| Upper | Downgradient | G50S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | | |
| Upper | Compliance | G52S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | | |
| Upper | Compliance | G54S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | 34 | | | | 6 | < 5 | | | | < 5 | | | |
| Upper | Downgradient | R42S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 5 | | | | < 5 | | | | | < 5 | | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 4thQtr04 | 1stQtr05 | 2ndQtr05 | 3rdQtr05 | 4thQtr05 | 1stQtr06 | 2ndQtr06 | 3rdQtr06 | 4thQtr06 | 1stQtr07 | 2ndQtr07 | 3rdQtr07 | 4thQtr07 | 1stQtr08 | 2ndQtr08 |
|-------|--------------|---------|------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G03M | Potassium, total | mg/l | GMZ | 29.00582 | | | 5.2 | | 3.7 | 3.9 | 2.8 | 4.4 | 3.4 | 2.8 | 2.9 | 3.2 | 2.6 | 2.5 | 2.3 |
| Lower | Downgradient | G16M | Potassium, total | mg/l | GMZ | 29.00582 | | | 7.8 | | 7.6 | 7.4 | 7 | 5.9 | 4.8 | 5.6 | 4.6 | 4.5 | 4.3 | 2.6 | 2.1 |
| Lower | Downgradient | G18D | Potassium, total | mg/l | GMZ | 29.00582 | | | 3.5 | | 2.6 | 3.5 | 3.5 | 3.5 | 3.2 | 3.4 | 4 | 24 | 5 | 3.8 | 7.8 |
| Lower | Downgradient | G33D | Potassium, total | mg/l | GMZ | 29.00582 | | | 1.2 | | 0.8 | 4.3 | 1.2 | 1.3 | 1.6 | 0.8 | B 1 | 1.4 | 0.82 | 1.6 | 1 |
| Lower | Downgradient | G34D | Potassium, total | mg/l | GMZ | 29.00582 | | | 4.9 | | 2.4 | 1.9 | 2.7 | 8.4 | 3.8 | 2.7 | 6.8 | 3.6 | 3.3 | 6.2 | 4.3 |
| Lower | Downgradient | G35D | Potassium, total | mg/l | GMZ | 29.00582 | | | 8.2 | | 3.6 | 3.8 | 3.5 | 3.2 | 2.7 | 2.7 | 30 | 2.8 | 2.6 | 6.5 | 5.4 |
| Lower | Downgradient | G36S | Potassium, total | mg/l | GMZ | 29.00582 | | | 1.1 | | 0.9 | 1.1 | 1.3 | 1.4 | 1 | 1.2 | B 1.3 | 1.2 | 1.1 | 1.1 | 1.1 |
| Lower | Downgradient | G37D | Potassium, total | mg/l | GMZ | 29.00582 | | | 1.6 | | 6.5 | 11 | 2.9 | 3.6 | 2.9 | 2.9 | 3.8 | 4 | 4 | 5.7 | 4.2 |
| Lower | Downgradient | G38S | Potassium, total | mg/l | GMZ | 29.00582 | | | 32 | | 38 | 37 | 26 | 10 | 18 | 15 | 32 | 30 | 30 | 26 | 24 |
| Lower | Compliance | G39S | Potassium, total | mg/l | GMZ | 29.00582 | | | 9.3 | | 9.3 | 6.4 | 2 | 9.1 | 6.8 | 6.7 | 5.2 | 4 | 7.4 | 4 | 2.4 |
| Lower | Downgradient | G41M | Potassium, total | mg/l | GMZ | 29.00582 | | | 22 | | 3.6 | 2.4 | 2.2 | 15 | 28 | 5.7 | 32 | 16 | 14 | 9.2 | 3.7 |
| Lower | Compliance | G52M | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Sodium, total | mg/l | GMZ | 164.7897 | | | 14 | | 15 | 16 | 14 | 15 | 16 | 14 | 17 | 17 | 15 | 15 | 14 |
| Lower | Downgradient | G16M | Sodium, total | mg/l | GMZ | 164.7897 | | | 15 | | 18 | 16 | 18 | 17 | 16 | 15 | 14 | 18 | 15 | 11 | 12 |
| Lower | Downgradient | G18D | Sodium, total | mg/l | GMZ | 164.7897 | | | 8.5 | | 10 | 11 | 10 | 11 | 18 | 16 | 15 | 15 | 12 | 39 | 47 |
| Lower | Downgradient | G33D | Sodium, total | mg/l | GMZ | 164.7897 | | | 6.3 | | 5.5 | 6.3 | 6.3 | 6.7 | 5.9 | 5.4 | 6.5 | 6.6 | 6 | 16 | 5.6 |
| Lower | Downgradient | G34D | Sodium, total | mg/l | GMZ | 164.7897 | | | 31 | | 20 | 23 | 32 | 50 | 28 | 32 | 45 | 37 | 44 | 58 | 61 |
| Lower | Downgradient | G35D | Sodium, total | mg/l | GMZ | 164.7897 | | | 26 | | 14 | 15 | 14 | 29 | 12 | 15 | 140 | 18 | 14 | 21 | 16 |
| Lower | Downgradient | G36S | Sodium, total | mg/l | GMZ | 164.7897 | | | 12 | | 11 | 13 | 13 | 12 | 11 | 12 | 12 | 11 | 12 | 12 | 12 |
| Lower | Downgradient | G37D | Sodium, total | mg/l | GMZ | 164.7897 | | | 11 | | 15 | 54 | 20 | 20 | 22 | 21 | 24 | 24 | 22 | 24 | 21 |
| Lower | Downgradient | G38S | Sodium, total | mg/l | GMZ | 164.7897 | | | 120 | | 110 | 90 | 53 | 62 | 74 | 45 | 120 | 88 | 85 | 58 | 53 |
| Lower | Compliance | G39S | Sodium, total | mg/l | GMZ | 164.7897 | | | 51 | | 60 | 87 | 59 | 56 | 56 | 52 | 59 | 33 | 41 | 94 | 16 |
| Lower | Downgradient | G41M | Sodium, total | mg/l | GMZ | 164.7897 | | | 85 | | 15 | 14 | 18 | 53 | 96 | 17 | 160 | 18 | 61 | 15 | 15 |
| Lower | Compliance | G52M | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | |
| Lower | Downgradient | G03M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G16M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | F< 5 | | | | < 5 |
| Lower | Downgradient | G18D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G33D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G34D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G35D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | 18 | | | | < 5 |
| Lower | Downgradient | G36S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G37D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G38S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | 29 | | | | 8 | | | | < 5 | | | | < 5 |
| Lower | Compliance | G39S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Lower | Downgradient | G41M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | 15 | | | | < 5 | | | | 22 | | | | < 5 |
| Lower | Compliance | G52M | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | |
| Lower | Compliance | G54M | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 4thQtr04 | 1stQtr05 | 2ndQtr05 | 3rdQtr05 | 4thQtr05 | 1stQtr06 | 2ndQtr06 | 3rdQtr06 | 4thQtr06 | 1stQtr07 | 2ndQtr07 | 3rdQtr07 | 4thQtr07 | 1stQtr08 | 2ndQtr08 |
|-------|--------------|---------|------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Upper | Downgradient | G119 | Potassium, total | mg/l | GMZ | 29.00582 | | | 0.92 | | 1.8 | 2 | 1 | 1.7 | 2.1 | 1.4 | | | | | |
| Upper | Downgradient | G130 | Potassium, total | mg/l | GMZ | 29.00582 | | | 1.2 | | 1.3 | 1.2 | 1.2 | 1.7 | 1.1 | 1.2 | 1.4 | 1.4 | 1.3 | 1.2 | 1.1 |
| Upper | Downgradient | G15S | Potassium, total | mg/l | GMZ | 29.00582 | | | 59 | | 100 | 96 | 65 | 110 | 48 | 59 | 44 | 71 | | 150 | 130 |
| Upper | Downgradient | G17S | Potassium, total | mg/l | GMZ | 29.00582 | | | 2.1 | | 4.5 | 2.3 | 2.2 | 3.6 | 3.6 | 2.8 | 1.9 | 3 | 3.8 | 3.6 | 1.7 |
| Upper | Downgradient | G18S | Potassium, total | mg/l | GMZ | 29.00582 | | | 82 | | 18 | 27 | 7.7 | 19 | 24 | 12 | 12 | 4.1 | 25 | 37 | 12 |
| Upper | Downgradient | G33S | Potassium, total | mg/l | GMZ | 29.00582 | | | 0.8 | | 0.9 | 1.2 | 0.83 | 0.9 | 0.92 | 0.72 | B 0.79 | 1 | 0.82 | 1.4 | 0.8 |
| Upper | Downgradient | G34S | Potassium, total | mg/l | GMZ | 29.00582 | | | 11 | | 15 | 15 | 12 | 11 | 11 | 11 | 9.1 | 12 | 13 | 19 | 10 |
| Upper | Downgradient | G35S | Potassium, total | mg/l | GMZ | 29.00582 | | | 21 | | 16 | 16 | 13 | 16 | 15 | 14 | 14 | 6.2 | 11 | 9.6 | 6 |
| Upper | Downgradient | G37S | Potassium, total | mg/l | GMZ | 29.00582 | | | 5.4 | | 12 | 4 | 11 | 11 | 11 | 12 | 7.7 | 3.8 | 2.9 | 2 | 2.2 |
| Upper | Downgradient | G40S | Potassium, total | mg/l | GMZ | 29.00582 | | | 26 | | 26 | 28 | 27 | 22 | 24 | 30 | 20 | 17 | 17 | 21 | 38 |
| Upper | Downgradient | G41S | Potassium, total | mg/l | GMZ | 29.00582 | | | 49 | | 50 | 38 | 32 | 32 | 36 | 30 | 30 | 26 | 27 | 16 | 10 |
| Upper | Downgradient | G50S | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | |
| Upper | Compliance | G52S | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | |
| Upper | Compliance | G54S | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Potassium, total | mg/l | GMZ | 29.00582 | | | 14 | | 12 | 13 | 13 | 14 | 12 | 11 | 11 | 8.9 | 8.1 | 6.5 | 5.9 |
| Upper | Downgradient | R42S | Potassium, total | mg/l | GMZ | 29.00582 | | | 1.2 | | 0.6 | 0.74 | 1.8 | 1.6 | 1.3 | 1.5 | 1.4 | 4.3 | 1.2 | 1.3 | 1.2 |
| Upper | Downgradient | G119 | Sodium, total | mg/l | GMZ | 164.7897 | | | 5 | | 8 | 9.4 | 5 | 8.4 | 8.5 | 6.6 | | | | | |
| Upper | Downgradient | G130 | Sodium, total | mg/l | GMZ | 164.7897 | | | 12 | | 12 | 10 | 12 | 12 | 10 | 11 | 14 | 10 | 12 | 11 | 11 |
| Upper | Downgradient | G15S | Sodium, total | mg/l | GMZ | 164.7897 | | | 140 | | 330 | 310 | 180 | 230 | 120 | 180 | 100 | 250 | | 610 | 480 |
| Upper | Downgradient | G17S | Sodium, total | mg/l | GMZ | 164.7897 | | | 12 | | 15 | 13 | 14 | 18 | 21 | 17 | 9.4 | 14 | 14 | 11 | 6.3 |
| Upper | Downgradient | G18S | Sodium, total | mg/l | GMZ | 164.7897 | | | 28 | | 27 | 17 | 14 | 11 | 9.4 | 14 | 36 | 12 | 23 | 16 | 14 |
| Upper | Downgradient | G33S | Sodium, total | mg/l | GMZ | 164.7897 | | | 5 | | 5.4 | 6 | 6 | 5.7 | 5.5 | 5.4 | 4.7 | 5.7 | 5.2 | 6 | 6.2 |
| Upper | Downgradient | G34S | Sodium, total | mg/l | GMZ | 164.7897 | | | 33 | | 53 | 42 | 26 | 27 | 32 | 53 | 27 | 50 | 61 | 51 | 23 |
| Upper | Downgradient | G35S | Sodium, total | mg/l | GMZ | 164.7897 | | | 26 | | 17 | 17 | 19 | 20 | 18 | 16 | 18 | 34 | 15 | 14 | 11 |
| Upper | Downgradient | G37S | Sodium, total | mg/l | GMZ | 164.7897 | | | 32 | | 48 | 15 | 65 | 42 | 48 | 52 | 24 | 10 | 9.8 | 13 | 14 |
| Upper | Downgradient | G40S | Sodium, total | mg/l | GMZ | 164.7897 | | | 83 | | 87 | 97 | 90 | 68 | 77 | 75 | 42 | 40 | 42 | 48 | 120 |
| Upper | Downgradient | G41S | Sodium, total | mg/l | GMZ | 164.7897 | | | 90 | | 74 | 51 | 36 | 41 | 65 | 60 | 58 | 48 | 59 | 26 | 22 |
| Upper | Downgradient | G50S | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | |
| Upper | Compliance | G52S | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | |
| Upper | Compliance | G54S | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Sodium, total | mg/l | GMZ | 164.7897 | | | 28 | | 24 | 25 | 27 | 25 | 21 | 24 | 35 | 22 | 28 | 20 | 17 |
| Upper | Downgradient | R42S | Sodium, total | mg/l | GMZ | 164.7897 | | | 70 | | 29 | 33 | 75 | 75 | 65 | 68 | 63 | 58 | 56 | 60 | 54 |
| Upper | Downgradient | G119 | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | | | | | |
| Upper | Downgradient | G130 | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | | | | | T< 5 |
| Upper | Downgradient | G15S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | 12 | | | | 20 | | | | < 5 | | | | 36 |
| Upper | Downgradient | G17S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Upper | Downgradient | G18S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Upper | Downgradient | G33S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | F< 5 | | | | < 5 |
| Upper | Downgradient | G34S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | F< 5 | | | | < 5 |
| Upper | Downgradient | G35S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Upper | Downgradient | G37S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Upper | Downgradient | G40S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | 12 | | | | < 5 | | | | < 5 |
| Upper | Downgradient | G41S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | 6 | | | | < 5 | | | | < 5 | | | | < 5 |
| Upper | Downgradient | G50S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G51S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | |
| Upper | Compliance | G52S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | |
| Upper | Compliance | G54S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |
| Upper | Downgradient | R42S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | < 5 | | | | < 5 | | | | < 5 | | | | < 5 |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr08 | 4thQtr08 | 1stQtr09 | 2ndQtr09 | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|-------------------------|-------|---------|------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G03M | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G16M | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G18D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Lower | Downgradient | G33D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | | | < 1 | | < 1 | |
| Lower | Downgradient | G34D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G35D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G36S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G37D | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Lower | Downgradient | G38S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G39S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G52M | 1,2,3-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G54M | 1,2,3-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | 1,2,3-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Lower | Downgradient | G03M | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G16M | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G18D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Lower | Downgradient | G33D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | | | < 1 | | < 1 | |
| Lower | Downgradient | G34D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G35D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G36S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G37D | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Lower | Downgradient | G38S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G39S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G52M | 1,2,4-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G54M | 1,2,4-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | 1,2,4-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Lower | Downgradient | G03M | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G16M | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G18D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Lower | Downgradient | G33D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G34D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G35D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G36S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G37D | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Lower | Downgradient | G38S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G39S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G52M | 1,4-Dichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G54M | 1,4-Dichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | 1,4-Dichlorobenzene | ug/L | G2, GMZ | 5 | | | | 1.5 | | 1.9 | | 1.4 | | 1.7 | | < 1 | | | |
| Lower | Downgradient | G03M | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G16M | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G18D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 4.7 | 7.3 | 11 | 11 | 14 | 11 | 4 | 5.6 | 2.3 | 1.9 | 1 | 1 | | | |
| Lower | Downgradient | G33D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G34D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.28 | 0.81 | 2.7 | 4.2 | 6 | Q 7.1 | 5.6 | 2.9 | 3.1 | 3 | 5.8 | 2.6 | 2.2 | 1.9 | 1.5 |
| Lower | Downgradient | G35D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 1.8 | 0.97 | 0.74 | 2.2 | 2.8 | 1.8 | 4.8 | 3.4 | 0.4 | 0.31 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G36S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 | |
| Lower | Downgradient | G37D | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 1.4 | 2 | 2.1 | 2.1 | | 1.7 | 1.7 | 0.99 | 0.48 | < 0.09 | 0.44 | 0.49 | | | |
| Lower | Downgradient | G38S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 43 | 38 | 16 | 15 | 16 | 8.6 | 7.8 | 4.5 | 1.2 | 0.22 | < 0.09 | 0.93 | 0.59 | 0.38 | < 0.1 |
| Lower | Compliance | G39S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.25 | 0.11 | < 0.09 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 0.17 | 0.11 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | 2.3 | 3.6 | 2.3 | 1.5 | 1.7 | 0.28 | 0.18 |
| Lower | Compliance | G52M | Ammonia as N, dissolved | mg/L | G1, GMZ | 0.9 | | | | | | < 0.09 | < 0.09 | < 0.09 | 0.52 | 0.39 | 0.46 | 0.33 | 1.2 | 1 | 0.87 |
| Lower | Compliance | G54M | Ammonia as N, dissolved | mg/L | G1, GMZ | 0.9 | | | | | | | | | | | | | | | < 0.1 |
| Lower | Compliance | R39S | Ammonia as N, dissolved | mg/L | G1, GMZ | 0.9 | | | | < 0.09 | 5.5 | 21 | 25 | 42 | 40 | 27 | 3 | 15 | 12 | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr08 | 4thQtr08 | 1stQtr09 | 2ndQtr09 | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|---------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G03M | Ammonia as N, total | mg/l | GMZ | 900 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | 0.09 | < 0.09 | < 0.09 | < 0.09 | 0.13 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G16M | Ammonia as N, total | mg/l | GMZ | 900 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G18D | Ammonia as N, total | mg/l | GMZ | 900 | 4.6 | 7 | 10 | 11 | 14 | 9.9 | 4 | 5.1 | 2.2 | 0.83 | 1.2 | 0.97 | | | |
| Lower | Downgradient | G33D | Ammonia as N, total | mg/l | GMZ | 900 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G34D | Ammonia as N, total | mg/l | GMZ | 900 | 0.41 | 0.88 | 2.4 | 4.4 | 4.5 | 6.7 | 4.7 | 2.8 | 2.9 | 3.1 | 2.9 | 2.4 | 2 | 1.8 | 1.3 |
| Lower | Downgradient | G35D | Ammonia as N, total | mg/l | GMZ | 900 | 1.8 | 0.96 | 0.82 | 2.2 | 2.6 | 1.7 | 4.8 | 3.3 | 0.4 | 0.34 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G36S | Ammonia as N, total | mg/l | GMZ | 900 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | 2 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Lower | Downgradient | G37D | Ammonia as N, total | mg/l | GMZ | 900 | 1.3 | 2 | 1.6 | 2.1 | | 1.7 | 1.2 | 0.87 | 0.43 | < 0.09 | 0.31 | 0.51 | | | |
| Lower | Downgradient | G38S | Ammonia as N, total | mg/l | GMZ | 900 | 40 | 38 | 15 | 14 | 16 | 8.6 | 5.5 | 4.7 | 1.2 | < 0.09 | < 0.09 | 1.1 | 0.78 | 0.35 | < 0.1 |
| Lower | Compliance | G39S | Ammonia as N, total | mg/l | GMZ | 900 | 0.27 | 0.13 | < 0.09 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Ammonia as N, total | mg/l | GMZ | 900 | 0.098 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | 2 | 3.6 | 5.9 | 1.5 | 1.4 | 0.3 | 0.18 |
| Lower | Compliance | G52M | Ammonia as N, total | mg/L | GMZ | 900 | | | | | | < 0.09 | < 0.09 | < 0.09 | 0.51 | 0.4 | 0.43 | < 0.1 | 1.1 | 0.99 | 0.83 |
| Lower | Compliance | G54M | Ammonia as N, total | mg/L | GMZ | 900 | | | | | | | | | | | | | | | < 0.1 |
| Lower | Compliance | R39S | Ammonia as N, total | mg/L | GMZ | 900 | | | | < 0.09 | 5 | 22 | 11 | 15 | 36 | 28 | 17 | 16 | 11 | | |
| Lower | Downgradient | G03M | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Downgradient | G16M | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Downgradient | G18D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | | | |
| Lower | Downgradient | G33D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Downgradient | G34D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Downgradient | G35D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Downgradient | G36S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Downgradient | G37D | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | | < 1 | < 1 | < 1 | < 1 | 1.4 | < 1 | < 1 | | | |
| Lower | Downgradient | G38S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | 2 | 2.1 | 1.5 | 2 | 1.9 | 2.4 | 1.2 | 1.2 | < 1 | 1.2 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Compliance | G39S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | 3.6 | 3.5 | 2.2 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | 1.2 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Compliance | G52M | Arsenic, Dissolved | ug/L | G1, GMZ | 2 | | | | | | 1.2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Compliance | G54M | Arsenic, Dissolved | ug/L | G1, GMZ | 2 | | | | | | | | | | | | | | | < 1 |
| Lower | Compliance | R39S | Arsenic, Dissolved | ug/L | G1, GMZ | 2 | | | | 2.6 | 4.6 | 2.2 | 3.6 | 2 | 1.9 | 2 | 1.4 | < 1 | < 1 | | |
| Lower | Downgradient | G03M | Arsenic, total | ug/l | GMZ | 10 | 1.5 | < 1 | 5.7 | < 1 | < 1 | < 1 | 1.2 | 1.5 | 1.5 | < 1 | 6.8 | < 1 | < 1 | 1.6 | 14 |
| Lower | Downgradient | G16M | Arsenic, total | ug/l | GMZ | 10 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | 1.6 |
| Lower | Downgradient | G18D | Arsenic, total | ug/l | GMZ | 10 | 1.5 | 1.6 | 7.8 | 4.6 | 1.8 | 2.4 | < 1 | 9.5 | 1.5 | 2.8 | 24 | 4.2 | | | |
| Lower | Downgradient | G33D | Arsenic, total | ug/l | GMZ | 10 | 4.8 | 1.4 | 5.5 | 5.2 | 3.2 | < 1 | 2 | 3.1 | 1.5 | | 19 | 11 | 1.5 | 1.2 | 21 |
| Lower | Downgradient | G34D | Arsenic, total | ug/l | GMZ | 10 | 7 | 1 | 15 | 5.2 | < 1 | < 1 | 2 | 1.1 | < 1 | < 1 | 2.5 | < 1 | < 1 | < 1 | 3.7 |
| Lower | Downgradient | G35D | Arsenic, total | ug/l | GMZ | 10 | 11 | 2.8 | 160 | 43 | 32 | 1.3 | 26 | 12 | 12 | 5 | 2.1 | 13 | 2.2 | 2.6 | 21 |
| Lower | Downgradient | G36S | Arsenic, total | ug/l | GMZ | 10 | < 1 | < 1 | 2.8 | < 1 | < 1 | < 1 | 1.1 | < 1 | 1 | < 1 | 2.1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Downgradient | G37D | Arsenic, total | ug/l | GMZ | 10 | 1.1 | < 1 | 3.4 | < 1 | | < 1 | 2.7 | < 1 | < 1 | < 1 | 1.6 | < 1 | | | |
| Lower | Downgradient | G38S | Arsenic, total | ug/l | GMZ | 10 | 2.2 | 2 | 4.8 | 2.1 | 5.2 | 2.6 | 5.9 | 2.1 | 1 | 1.2 | 12 | 4.3 | 2.7 | 16 | 14 |
| Lower | Compliance | G39S | Arsenic, total | ug/l | GMZ | 10 | 38 | 36 | 79 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Arsenic, total | ug/l | GMZ | 10 | 5.9 | 2.8 | 18 | 5.5 | 9.8 | 22 | 31 | 12 | 14 | 2.5 | 9.7 | 6.7 | 11 | 1.9 | 1.1 |
| Lower | Compliance | G52M | Arsenic, total | ug/L | GMZ | 10 | | | | | | 2 | 1.3 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Lower | Compliance | G54M | Arsenic, total | ug/L | GMZ | 10 | | | | | | | | | | | | | | | < 1 |
| Lower | Compliance | R39S | Arsenic, total | ug/L | GMZ | 10 | | | | 3.5 | 11 | 5.2 | 54 | 130 | 98 | 2.3 | 5 | 1.4 | 1.9 | | |
| Lower | Downgradient | G03M | Barium, total | ug/l | GMZ | 225180.6 | 160 | 150 | 220 | 130 | 160 | 150 | 150 | 150 | 140 | 140 | 220 | 140 | 140 | 140 | 290 |
| Lower | Downgradient | G16M | Barium, total | ug/l | GMZ | 225180.6 | 170 | 180 | 110 | 150 | 140 | 150 | 140 | 130 | 120 | 130 | 120 | 120 | 110 | 120 | 150 |
| Lower | Downgradient | G18D | Barium, total | ug/l | GMZ | 225180.6 | 97 | 120 | 190 | 140 | 120 | 130 | 96 | 170 | 74 | 96 | 370 | 110 | | | |
| Lower | Downgradient | G33D | Barium, total | ug/l | GMZ | 225180.6 | 130 | 110 | 120 | 130 | 120 | 110 | 120 | 120 | 110 | | 200 | 160 | 110 | 110 | 210 |
| Lower | Downgradient | G34D | Barium, total | ug/l | GMZ | 225180.6 | 160 | 91 | 260 | 170 | 85 | 92 | 120 | 88 | 69 | 68 | 100 | 64 | 65 | 69 | 120 |
| Lower | Downgradient | G35D | Barium, total | ug/l | GMZ | 225180.6 | 230 | 180 | 1500 | 460 | 350 | 200 | 310 | 270 | 220 | 190 | 130 | 210 | 170 | 160 | 290 |
| Lower | Downgradient | G36S | Barium, total | ug/l | GMZ | 225180.6 | 220 | 220 | 270 | 220 | 220 | 240 | 240 | 230 | 230 | 220 | 240 | 220 | 220 | 220 | 220 |
| Lower | Downgradient | G37D | Barium, total | ug/l | GMZ | 225180.6 | 74 | 66 | 110 | 70 | | 61 | 78 | 56 | 52 | 44 | 64 | 46 | | | |
| Lower | Downgradient | G38S | Barium, total | ug/l | GMZ | 225180.6 | 570 | 760 | 550 | 470 | 540 | 450 | 560 | 480 | 290 | 250 | 370 | 400 | 350 | 410 | 410 |
| Lower | Compliance | G39S | Barium, total | ug/l | GMZ | 225180.6 | 760 | 640 | 1400 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Barium, total | ug/l | GMZ | 225180.6 | 140 | 140 | 130 | 120 | 120 | 120 | 110 | 120 | 170 | 230 | 230 | 170 | 180 | 150 | 150 |
| Lower | Compliance | G52M | Barium, total | ug/L | GMZ | 225180.6 | | | | | | 68 | 65 | 48 | 52 | 51 | 61 | 40 | 53 | 48 | 49 |
| Lower | Compliance | G54M | Barium, total | ug/L | GMZ | 225180.6 | | | | | | | | | | | | | | | 85 |
| Lower | Compliance | R39S | Barium, total | ug/L | GMZ | 225180.6 | | | | 130 | 280 | 280 | 1200 | 1700 | 1600 | 240 | 200 | 170 | 170 | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr08 | 4thQtr08 | 1stQtr09 | 2ndQtr09 | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|---------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G03M | Boron, Dissolved | ug/l | G1, GMZ | 98 | 21 | 28 | 24 | 21 | 22 | 21 | 18 | 12 | 26 | 20 | 20 | 22 | 31 | 19 | 18 |
| Lower | Downgradient | G16M | Boron, Dissolved | ug/l | G1, GMZ | 98 | 19 | 20 | 16 | 19 | 15 | 13 | 10 | < 10 | 10 | 12 | 13 | 10 | 24 | 15 | 15 |
| Lower | Downgradient | G18D | Boron, Dissolved | ug/l | G1, GMZ | 98 | 130 | 120 | 100 | 89 | 85 | 62 | 56 | 31 | 33 | 32 | 28 | 21 | | | |
| Lower | Downgradient | G33D | Boron, Dissolved | ug/l | G1, GMZ | 98 | 10 | 14 | < 10 | 14 | < 10 | < 10 | < 10 | < 10 | < 10 | | < 10 | 11 | 11 | 14 | 14 |
| Lower | Downgradient | G34D | Boron, Dissolved | ug/l | G1, GMZ | 98 | 160 | 150 | 110 | 97 | 84 | 62 | 52 | 36 | 29 | 24 | 27 | 34 | 36 | 24 | 31 |
| Lower | Downgradient | G35D | Boron, Dissolved | ug/l | G1, GMZ | 98 | 32 | 28 | 29 | 42 | 33 | 34 | 40 | 17 | 37 | 28 | 32 | < 10 | 22 | 16 | < 10 |
| Lower | Downgradient | G36S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 16 | 16 | 14 | 12 | 10 | 12 | 14 | < 10 | 22 | 14 | 15 | 14 | 21 | 12 | 12 |
| Lower | Downgradient | G37D | Boron, Dissolved | ug/l | G1, GMZ | 98 | 52 | 58 | 50 | 41 | | 25 | 21 | 14 | 30 | 21 | 20 | 14 | | | |
| Lower | Downgradient | G38S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 180 | 220 | 130 | 130 | 120 | 120 | 100 | 85 | 100 | 82 | 33 | 45 | 110 | 410 | 25 |
| Lower | Compliance | G39S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 200 | 360 | 320 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Boron, Dissolved | ug/l | G1, GMZ | 98 | 30 | 70 | 22 | 26 | 29 | 18 | 23 | 27 | 48 | 65 | 67 | 30 | 35 | 23 | 25 |
| Lower | Compliance | G52M | Boron, Dissolved | ug/L | G1, GMZ | 98 | | | | | | 46 | 50 | 36 | 57 | 39 | 25 | 29 | 35 | 24 | 28 |
| Lower | Compliance | G54M | Boron, Dissolved | ug/L | G1, GMZ | 98 | | | | | | | | | | | | | | | < 10 |
| Lower | Compliance | R39S | Boron, Dissolved | ug/L | G1, GMZ | 98 | | | | 380 | 420 | 350 | 360 | 340 | 220 | 130 | 77 | 68 | 71 | | |
| Lower | Downgradient | G03M | Boron, total | ug/l | GMZ | 200 | 26 | 16 | 36 | 16 | 23 | 19 | 27 | 22 | 15 | 25 | 41 | 22 | 17 | 23 | 53 |
| Lower | Downgradient | G16M | Boron, total | ug/l | GMZ | 200 | 24 | 20 | 19 | 20 | < 10 | 31 | 15 | 12 | < 10 | < 10 | 16 | 13 | 18 | 22 | 20 |
| Lower | Downgradient | G18D | Boron, total | ug/l | GMZ | 200 | 130 | 120 | 130 | 93 | 78 | 67 | 52 | 60 | 36 | 36 | 99 | 42 | | | |
| Lower | Downgradient | G33D | Boron, total | ug/l | GMZ | 200 | 22 | < 10 | 20 | 20 | < 10 | < 10 | 14 | 25 | 15 | | 23 | 26 | 21 | 22 | 31 |
| Lower | Downgradient | G34D | Boron, total | ug/l | GMZ | 200 | 180 | 130 | 160 | 110 | 75 | 62 | 55 | 52 | 36 | 23 | 30 | 35 | 37 | 31 | 38 |
| Lower | Downgradient | G35D | Boron, total | ug/l | GMZ | 200 | 42 | 25 | 180 | 85 | 52 | 34 | 52 | 40 | 34 | 26 | 26 | 19 | 21 | 23 | 32 |
| Lower | Downgradient | G36S | Boron, total | ug/l | GMZ | 200 | 20 | < 10 | 17 | 10 | < 10 | 14 | 15 | 15 | < 10 | 15 | 20 | 22 | 11 | 19 | 15 |
| Lower | Downgradient | G37D | Boron, total | ug/l | GMZ | 200 | 65 | 47 | 61 | 41 | | 23 | 28 | 22 | 25 | 16 | 20 | 19 | | | |
| Lower | Downgradient | G38S | Boron, total | ug/l | GMZ | 200 | 160 | 200 | 140 | 120 | 130 | 120 | 100 | 87 | 97 | 71 | 48 | 60 | 100 | 72 | 30 |
| Lower | Compliance | G39S | Boron, total | ug/l | GMZ | 200 | 340 | 440 | 470 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Boron, total | ug/l | GMZ | 200 | 39 | 65 | 19 | 20 | 27 | 18 | 22 | 34 | 45 | 66 | 66 | 35 | 26 | 23 | 27 |
| Lower | Compliance | G52M | Boron, total | ug/L | GMZ | 200 | | | | | | 40 | 50 | 37 | 48 | 39 | 30 | 24 | 26 | 28 | 30 |
| Lower | Compliance | G54M | Boron, total | ug/L | GMZ | 200 | | | | | | | | | | | | | | | 11 |
| Lower | Compliance | R39S | Boron, total | ug/L | GMZ | 200 | | | | 360 | 400 | 360 | 480 | 610 | 500 | 110 | 74 | 67 | 58 | | |
| Lower | Downgradient | G03M | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 43 | 42 | 50 | 42 | 41 | 35 | 36 | 37 | 38 | 37 | 35 | 37 | 39 | | 40 |
| Lower | Downgradient | G16M | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 35 | 37 | 18 | 38 | 38 | 38 | 32 | 27 | 27 | 26 | 26 | 41 | 32 | 25 | 27 |
| Lower | Downgradient | G18D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 56 | 51 | 53 | 53 | 52 | 38 | 52 | 41 | 27 | 28 | 27 | 38 | | | |
| Lower | Downgradient | G33D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 18 | 22 | 25 | 28 | 35 | 30 | 22 | 25 | 25 | | 22 | 22 | 25 | 28 | 24 |
| Lower | Downgradient | G34D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 74 | 60 | 53 | 54 | 51 | 46 | 44 | 40 | 30 | 24 | 25 | 29 | 28 | 3.1 | 26 |
| Lower | Downgradient | G35D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 44 | 46 | 56 | 62 | 44 | 47 | 36 | 33 | 26 | 28 | 26 | 38 | 27 | 25 | 27 |
| Lower | Downgradient | G36S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 38 | 42 | 43 | 46 | 47 | 43 | 48 | 50 | 43 | 46 | 47 | 46 | 46 | 46 | 47 |
| Lower | Downgradient | G37D | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 37 | 40 | 54 | 48 | | 32 | 31 | 30 | 25 | 5.7 | 18 | 16 | | | |
| Lower | Downgradient | G38S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 100 | 130 | 65 | 64 | 76 | 65 | 95 | 180 | 29 | 32 | 40 | 140 | 66 | 39 | 36 |
| Lower | Compliance | G39S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 140 | 250 | 260 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 39 | 45 | 43 | 42 | 39 | 37 | 40 | 62 | 41 | 57 | 51 | 44 | 45 | 39 | 40 |
| Lower | Compliance | G52M | Chloride, Dissolved | mg/L | G1, GMZ | 87.511 | | | | | | 54 | 45 | 31 | 28 | 25 | 15 | 17 | 18 | | 15 |
| Lower | Compliance | G54M | Chloride, Dissolved | mg/L | G1, GMZ | 87.511 | | | | | | | | | | | | | | | 17 |
| Lower | Compliance | R39S | Chloride, Dissolved | mg/L | G1, GMZ | 87.511 | | | | < 1 | 250 | 160 | 160 | 130 | 59 | 60 | 48 | 130 | 48 | | |
| Lower | Downgradient | G03M | Chloride, total | mg/l | GMZ | 87.51186 | 43 | 44 | 43 | 43 | 41 | 37 | 39 | 37 | 37 | 39 | 36 | 38 | 35 | 41 | 38 |
| Lower | Downgradient | G16M | Chloride, total | mg/l | GMZ | 87.51186 | 35 | 36 | 18 | 40 | 41 | 40 | 34 | 28 | 27 | 22 | 26 | 39 | 31 | 26 | 23 |
| Lower | Downgradient | G18D | Chloride, total | mg/l | GMZ | 87.51186 | 58 | 51 | 54 | 61 | 52 | 37 | 50 | 40 | 30 | 27 | 30 | 37 | | | |
| Lower | Downgradient | G33D | Chloride, total | mg/l | GMZ | 87.51186 | 18 | 22 | 25 | 28 | 34 | 30 | 34 | 24 | 25 | | 22 | 24 | 23 | 27 | 25 |
| Lower | Downgradient | G34D | Chloride, total | mg/l | GMZ | 87.51186 | 75 | 64 | 56 | 58 | 51 | 46 | 45 | 44 | 32 | 25 | 25 | 29 | 27 | 28 | 27 |
| Lower | Downgradient | G35D | Chloride, total | mg/l | GMZ | 87.51186 | 44 | 47 | 58 | 62 | 45 | 52 | 36 | 34 | 27 | 29 | 26 | 38 | 31 | 26 | 29 |
| Lower | Downgradient | G36S | Chloride, total | mg/l | GMZ | 87.51186 | 38 | 41 | 42 | 50 | 47 | 46 | 47 | 48 | 45 | 47 | 47 | 47 | 45 | 45 | 43 |
| Lower | Downgradient | G37D | Chloride, total | mg/l | GMZ | 87.51186 | 39 | 41 | 43 | 46 | | 33 | 31 | 32 | 25 | 13 | 22 | 17 | | | |
| Lower | Downgradient | G38S | Chloride, total | mg/l | GMZ | 87.51186 | 99 | 140 | 65 | 59 | 75 | 68 | 80 | 180 | 45 | 32 | 34 | 160 | 73 | 39 | 46 |
| Lower | Compliance | G39S | Chloride, total | mg/l | GMZ | 87.51186 | 210 | 230 | 260 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Chloride, total | mg/l | GMZ | 87.51186 | 39 | 42 | 51 | 42 | 39 | 38 | 42 | 65 | 43 | 52 | 51 | 43 | 44 | 40 | 38 |
| Lower | Compliance | G52M | Chloride, total | mg/L | GMZ | 87.51186 | | | | | | 55 | 45 | 30 | 28 | 25 | 15 | 21 | 16 | 17 | 15 |
| Lower | Compliance | G54M | Chloride, total | mg/L | GMZ | 87.51186 | | | | | | | | | | | | | | | 14 |
| Lower | Compliance | R39S | Chloride, total | mg/L | GMZ | 87.51186 | | | | < 1 | 240 | 160 | 170 | 120 | 64 | 55 | 47 | 44 | 46 | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr08 | 4thQtr08 | 1stQtr09 | 2ndQtr09 | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|-------------------------|-------|---------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G03M | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G16M | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G18D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Lower | Downgradient | G33D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | | | < 1 | | < 1 | |
| Lower | Downgradient | G34D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G35D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G36S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Downgradient | G37D | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Lower | Downgradient | G38S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G39S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G52M | Ethylbenzene | ug/L | G2, GMZ | 5 | | | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Lower | Compliance | G54M | Ethylbenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Ethylbenzene | ug/L | G2, GMZ | 5 | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Lower | Downgradient | G03M | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 2.5 | < 2.5 | < 2.5 | 0.253 |
| Lower | Downgradient | G16M | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.27 | 0.26 | 0.38 | 0.29 |
| Lower | Downgradient | G18D | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.34 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | | | |
| Lower | Downgradient | G33D | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.38 | < 0.25 | < 0.25 | 0.42 | < 0.25 | | < 0.25 | < 0.25 | 0.25 | 0.37 | 0.282 |
| Lower | Downgradient | G34D | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.34 | < 0.25 | < 0.25 | 0.39 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.32 | < 0.25 |
| Lower | Downgradient | G35D | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.37 | < 0.25 | 0.44 | 0.4 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.26 | < 0.25 | 0.289 |
| Lower | Downgradient | G36S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | 0.3 | < 0.25 | 0.36 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 |
| Lower | Downgradient | G37D | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | 0.26 | < 0.25 | | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | | | |
| Lower | Downgradient | G38S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | 0.3 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 |
| Lower | Compliance | G39S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 2.5 | < 0.25 | 0.25 |
| Lower | Compliance | G52M | Fluoride, total | mg/L | GMZ | 273.35 | | | | | | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 2.5 | < 0.25 |
| Lower | Compliance | G54M | Fluoride, total | mg/L | GMZ | 273.35 | | | | | | | | | | | | | | | 0.273 |
| Lower | Compliance | R39S | Fluoride, total | mg/L | GMZ | 273.35 | | | | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | | |
| Lower | Downgradient | G03M | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 10 | 9.2 | 12 | 9.6 | 8.2 | 7.8 | 8.2 | 7.8 | 7.7 | H 7.1 | 8.3 | 9.3 | 8.8 | | 10 |
| Lower | Downgradient | G16M | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 10 | 11 | 6.3 | 7.8 | 9.9 | 9.9 | 6.1 | 10 | 10 | 9.6 | 6.9 | 2.5 | 4.4 | 3.9 | 4.5 |
| Lower | Downgradient | G18D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 3.3 | 3.2 | 3.5 | 3.1 | H 3.5 | 4.4 | H 8.2 | 6 | 6.6 | H 5 | 5.4 | 5.5 | | | |
| Lower | Downgradient | G33D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 9 | 10 | 11 | 12 | H 12 | 12 | 10 | 11 | 12 | | 10 | 11 | 11 | 8 | 8.7 |
| Lower | Downgradient | G34D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 6.9 | 7 | 8.3 | 7.8 | H 6.6 | 6.8 | 7.7 | 7.1 | 3 | 2.3 | 3.4 | 4.9 | 3.8 | 0.34 | 4.5 |
| Lower | Downgradient | G35D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 9.5 | 8.6 | 8.3 | 7.6 | H 8.4 | 5 | 5.9 | 5.7 | 7.3 | 5 | 6.3 | 5.3 | 8.7 | 5.9 | 7.5 |
| Lower | Downgradient | G36S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 12 | 12 | 13 | 12 | H 13 | 11 | 13 | 12 | 11 | 11 | 12 | 12 | 11 | 12 | 11 |
| Lower | Downgradient | G37D | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 9.1 | 9.8 | 9.2 | 10 | | 9 | 9.3 | 7.8 | 2.9 | 1.1 | 1.7 | 1.8 | | | |
| Lower | Downgradient | G38S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 0.98 | H 0.29 | 0.58 | 0.13 | 0.37 | 0.074 | 0.15 | 0.047 | 0.23 | 0.32 | 1.9 | 0.72 | 0.48 | 1.4 | 1.9 |
| Lower | Compliance | G39S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 0.18 | < 0.02 | 0.1 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 5.4 | 3.3 | 6.5 | 5.8 | 5.8 | 6.8 | 8.4 | 6.5 | 7 | 5.2 | 7.3 | 9.5 | 7.8 | 9.4 | 9.2 |
| Lower | Compliance | G52M | Nitrate as N, dissolved | mg/L | G1, GMZ | 11.74 | | | | | | 5.3 | 8.9 | 8.4 | H 4.9 | 4.4 | 1.8 | 2.1 | 1.3 | | 1.3 |
| Lower | Compliance | G54M | Nitrate as N, dissolved | mg/L | G1, GMZ | 11.74 | | | | | | | | | | | | | | | 2.9 |
| Lower | Compliance | R39S | Nitrate as N, dissolved | mg/L | G1, GMZ | 11.74 | | | | 0.037 | < 0.02 | 0.09 | < 0.2 | 0.087 | 0.048 | H 0.089 | 0.36 | 0.36 | 0.04 | | |
| Lower | Downgradient | G03M | Nitrate as N, total | mg/l | GMZ | 11.7389 | 10 | 9.5 | 11 | 9.9 | 7.5 | 8.2 | 8 | 7.9 | 8.1 | 7.7 | 7.8 | 9 | 9.1 | 10 | 10 |
| Lower | Downgradient | G16M | Nitrate as N, total | mg/l | GMZ | 11.7389 | 10 | 11 | 6.4 | 8.9 | 10 | 10 | 6.4 | 11 | 10 | 8.7 | 7.1 | 2.3 | 4.5 | 3.9 | 4.4 |
| Lower | Downgradient | G18D | Nitrate as N, total | mg/l | GMZ | 11.7389 | 3.1 | 3.1 | 7.8 | 3.1 | 3.7 | 4.3 | H 8.2 | 5.8 | 7.4 | H 4.3 | 5.8 | 5.4 | | | |
| Lower | Downgradient | G33D | Nitrate as N, total | mg/l | GMZ | 11.7389 | 9 | 10 | 11 | 12 | H 12 | 12 | 13 | 11 | 12 | | 10 | 11 | 11 | 8 | 8.2 |
| Lower | Downgradient | G34D | Nitrate as N, total | mg/l | GMZ | 11.7389 | 6.9 | 7.3 | 8.8 | 8.2 | H 7.1 | 6.9 | 8.2 | 7.1 | 4 | 2.7 | 3.1 | 4.4 | 4.6 | 4.5 | 5 |
| Lower | Downgradient | G35D | Nitrate as N, total | mg/l | GMZ | 11.7389 | 9.7 | 8.8 | 8.7 | 7.7 | H 8.5 | 5.1 | 5.8 | 5.9 | 7.6 | 5.2 | 6.3 | 5.2 | 6.6 | 7.2 | 7.1 |
| Lower | Downgradient | G36S | Nitrate as N, total | mg/l | GMZ | 11.7389 | 12 | 12 | 13 | 13 | H 13 | 12 | 12 | 12 | 12 | 12 | 12 | 12 | 11 | 12 | 11 |
| Lower | Downgradient | G37D | Nitrate as N, total | mg/l | GMZ | 11.7389 | 7.5 | 9.9 | 10 | 11 | | 9.1 | 9.2 | 7.9 | 3.2 | 1.9 | 4.3 | 1.8 | | | |
| Lower | Downgradient | G38S | Nitrate as N, total | mg/l | GMZ | 11.7389 | 0.7 | 0.26 | 2.4 | 0.44 | 0.2 | 0.07 | 5.5 | 0.048 | 0.49 | 0.42 | H 2 | 0.41 | 0.35 | 0.82 | 2.3 |
| Lower | Compliance | G39S | Nitrate as N, total | mg/l | GMZ | 11.7389 | 0.079 | 0.051 | 0.21 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Nitrate as N, total | mg/l | GMZ | 11.7389 | 5.3 | 3.5 | 4.9 | 6.4 | 5.6 | 6.7 | 8.6 | 6.6 | 6.8 | 4.9 | 7.4 | 9.8 | 8 | 9.5 | 9.5 |
| Lower | Compliance | G52M | Nitrate as N, total | mg/L | GMZ | 11.7389 | | | | | | 5.3 | 9 | 8.6 | H 4.8 | 4.2 | 1.8 | 2.2 | 1.3 | 1.3 | 1.3 |
| Lower | Compliance | G54M | Nitrate as N, total | mg/L | GMZ | 11.7389 | | | | | | | | | | | | | | | 2.8 |
| Lower | Compliance | R39S | Nitrate as N, total | mg/L | GMZ | 11.7389 | | | | 0.027 | 0.092 | 0.12 | < 0.2 | < 0.02 | < 0.02 | H 0.22 | 0.6 | 0.36 | 0.06 | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr08 | 4thQtr08 | 1stQtr09 | 2ndQtr09 | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Lower | Downgradient | G03M | Potassium, total | mg/l | GMZ | 29.00582 | 2.5 | 2.4 | 4.7 | 2.2 | 2.5 | 2.6 | 2.5 | 3.2 | 2.4 | 2.4 | 3.6 | 2.5 | 2.4 | 2.4 | 4.6 |
| Lower | Downgradient | G16M | Potassium, total | mg/l | GMZ | 29.00582 | 1.9 | 1.9 | 1.7 | 1.6 | 1.6 | 1.8 | 1.3 | 1.1 | 1.1 | 1.2 | 1.4 | 1.5 | 1.1 | 1.3 | 3.6 |
| Lower | Downgradient | G18D | Potassium, total | mg/l | GMZ | 29.00582 | 7.8 | 9.3 | 13 | 13 | 12 | 11 | 9.2 | 11 | 5.7 | 6.4 | 14 | 6.1 | | | |
| Lower | Downgradient | G33D | Potassium, total | mg/l | GMZ | 29.00582 | 2.2 | 1.1 | 2 | 2.2 | 1.7 | 1 | 1.5 | 1.6 | 1.2 | | 5 | 3.8 | 1.4 | 1.2 | 6.5 |
| Lower | Downgradient | G34D | Potassium, total | mg/l | GMZ | 29.00582 | 8.3 | 5.8 | 13 | 12 | 7.6 | 7.6 | 8.6 | 6.7 | 5.9 | 5.7 | 7.2 | 5.1 | 4.3 | 4.3 | 7.8 |
| Lower | Downgradient | G35D | Potassium, total | mg/l | GMZ | 29.00582 | 5.8 | 3.9 | 28 | 12 | 10 | 4.4 | 8.2 | 7.6 | 5.4 | 4 | 3 | 3.7 | 1.7 | 1.7 | 6.3 |
| Lower | Downgradient | G36S | Potassium, total | mg/l | GMZ | 29.00582 | 1.4 | 1.3 | 3 | 1.7 | 1.6 | 1.5 | 1.4 | 1.4 | 1.3 | 1.3 | 1.8 | 1.3 | 1.2 | 1.3 | 1.7 |
| Lower | Downgradient | G37D | Potassium, total | mg/l | GMZ | 29.00582 | 5.1 | 4.6 | 7.5 | 5.1 | | 4.3 | 5.1 | 4.1 | 3.3 | 4.1 | 4 | 2.7 | | | |
| Lower | Downgradient | G38S | Potassium, total | mg/l | GMZ | 29.00582 | 21 | 23 | 16 | 14 | 16 | 12 | 12 | 10 | 8.2 | 6.9 | 5.4 | 6.6 | 6.4 | 6 | 3.2 |
| Lower | Compliance | G39S | Potassium, total | mg/l | GMZ | 29.00582 | 16 | 13 | 17 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Potassium, total | mg/l | GMZ | 29.00582 | 3.8 | 4.2 | 3.9 | 3.4 | 3.2 | 2.9 | 2.7 | 2.9 | 5.8 | 5.9 | 6 | 3.1 | 3.3 | 2.2 | 2.1 |
| Lower | Compliance | G52M | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | 4.4 | 3.4 | 2.8 | 3.4 | 3.4 | 4.2 | 2.7 | 3.7 | 3.6 | 3.7 |
| Lower | Compliance | G54M | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | 0.91 |
| Lower | Compliance | R39S | Potassium, total | mg/L | GMZ | 29.00582 | | | | 3 | 7.3 | 10 | 23 | 73 | 63 | 19 | 16 | 14 | 12 | | |
| Lower | Downgradient | G03M | Sodium, total | mg/l | GMZ | 164.7897 | 16 | 17 | 16 | 14 | 16 | 15 | 15 | 15 | 15 | 15 | 15 | 15 | 15 | 16 | 15 |
| Lower | Downgradient | G16M | Sodium, total | mg/l | GMZ | 164.7897 | 12 | 12 | 5.3 | 11 | 12 | 12 | 12 | 7.4 | 7.5 | 7.7 | 8.2 | 18 | 13 | 9.7 | 9.4 |
| Lower | Downgradient | G18D | Sodium, total | mg/l | GMZ | 164.7897 | 29 | 23 | 24 | 22 | 22 | 16 | 24 | 15 | 11 | 11 | 9.6 | 12 | | | |
| Lower | Downgradient | G33D | Sodium, total | mg/l | GMZ | 164.7897 | 5.7 | 5.7 | 6.7 | 7.4 | 11 | 9.9 | 9 | Q | 6.8 | 7.3 | 6.4 | 6 | 7 | 11 | 8.6 |
| Lower | Downgradient | G34D | Sodium, total | mg/l | GMZ | 164.7897 | 49 | 38 | 24 | 23 | 23 | 21 | 19 | 16 | 14 | 12 | 11 | 12 | 12 | 11 | 13 |
| Lower | Downgradient | G35D | Sodium, total | mg/l | GMZ | 164.7897 | 15 | 15 | 23 | 18 | 16 | 19 | 16 | 14 | 12 | 12 | 12 | 13 | 13 | 11 | 11 |
| Lower | Downgradient | G36S | Sodium, total | mg/l | GMZ | 164.7897 | 12 | 14 | 13 | 14 | 16 | 15 | 16 | 18 | 18 | 17 | 17 | 18 | 17 | 18 | 16 |
| Lower | Downgradient | G37D | Sodium, total | mg/l | GMZ | 164.7897 | 18 | 20 | 21 | 16 | | 11 | 10 | 10 | 10 | 10 | 7.6 | 6.4 | | | |
| Lower | Downgradient | G38S | Sodium, total | mg/l | GMZ | 164.7897 | 39 | 54 | 43 | 35 | 31 | 30 | 28 | 64 | 28 | 18 | 15 | 56 | 50 | 19 | 15 |
| Lower | Compliance | G39S | Sodium, total | mg/l | GMZ | 164.7897 | 57 | 85 | 75 | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Sodium, total | mg/l | GMZ | 164.7897 | 14 | 24 | 16 | 14 | 15 | 15 | 14 | 24 | 19 | 26 | 22 | 17 | 18 | 16 | 17 |
| Lower | Compliance | G52M | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | 25 | 20 | 14 | 14 | 13 | 10 | 8 | 8.7 | 9.3 | 9.7 |
| Lower | Compliance | G54M | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | 4.9 |
| Lower | Compliance | R39S | Sodium, total | mg/L | GMZ | 164.7897 | | | | 94 | 100 | 84 | 62 | 68 | 34 | 26 | 21 | 18 | 19 | | |
| Lower | Downgradient | G03M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Lower | Downgradient | G16M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Lower | Downgradient | G18D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | 9.2 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | | |
| Lower | Downgradient | G33D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | | | < 2 | | < 2 | |
| Lower | Downgradient | G34D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | 19 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Lower | Downgradient | G35D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Lower | Downgradient | G36S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | 6.7 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Lower | Downgradient | G37D | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | | |
| Lower | Downgradient | G38S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | 14 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Lower | Compliance | G39S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | 20 | | | | | | | | | | | | | |
| Lower | Downgradient | G41M | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Lower | Compliance | G52M | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Lower | Compliance | G54M | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | |
| Lower | Compliance | R39S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | 19 | | 20 | | 13 | | < 2.5 | | < 2 | | | |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr08 | 4thQtr08 | 1stQtr09 | 2ndQtr09 | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|-------------------------|-------|---------|------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Upper | Downgradient | G119 | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G15S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G18S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G33S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | | | < 1 | | < 1 | |
| Upper | Downgradient | G34S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G35S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G37S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Upper | Downgradient | G40S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | | | | | | |
| Upper | Downgradient | G41S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G50S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G51S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Upper | Compliance | G52S | 1,2,3-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Compliance | G54S | 1,2,3-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | R42S | 1,2,3-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G119 | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G15S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G18S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G33S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | | | < 1 | | < 1 | |
| Upper | Downgradient | G34S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G35S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G37S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Upper | Downgradient | G40S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | | | | | | |
| Upper | Downgradient | G41S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G50S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G51S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Upper | Compliance | G52S | 1,2,4-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Compliance | G54S | 1,2,4-Trichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | R42S | 1,2,4-Trichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G119 | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G15S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G18S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G33S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | | | < 1 | | < 1 | |
| Upper | Downgradient | G34S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G35S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G37S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Upper | Downgradient | G40S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | 3.5 | | 4 | | 2.6 | | < 1 | | | | | | | |
| Upper | Downgradient | G41S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G50S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G51S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | | | 3.1 | | < 1 | | 2.4 | | 6.2 | | 6.6 | | | |
| Upper | Compliance | G52S | 1,4-Dichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Compliance | G54S | 1,4-Dichlorobenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | R42S | 1,4-Dichlorobenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G119 | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Upper | Downgradient | G15S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | | | | | | | | |
| Upper | Downgradient | G18S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | 0.19 | < 0.09 | | | | | | | | |
| Upper | Downgradient | G33S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Upper | Downgradient | G34S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 9.2 | 11 | 10 | 10 | 6.6 | 4.8 | 5.6 | 3.5 | 1.4 | 0.81 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Upper | Downgradient | G35S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 3.8 | 4.2 | 3.4 | 1.2 | 2 | 1.9 | 1.6 | 1.1 | 1 | 0.86 | 0.64 | 0.36 | 0.22 | 0.33 | < 0.1 |
| Upper | Downgradient | G37S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | | < 0.09 | < 0.09 | < 0.09 | 0.34 | 0.34 | 0.38 | < 0.1 | | | |
| Upper | Downgradient | G40S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 23 | 24 | 19 | 14 | 24 | 11 | 9.4 | 9 | | | | | | | |
| Upper | Downgradient | G41S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 1.3 | 18 | 4.9 | 2.5 | 1.2 | 1.6 | 1 | 0.64 | 0.37 | 0.32 | 2.4 | 1.4 | 0.23 | < 0.1 | 0.37 |
| Upper | Downgradient | G50S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | | | 0.18 | < 0.09 | 0.28 | < 0.09 | < 0.09 | | | | | | | | |
| Upper | Downgradient | G51S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | | | 8 | 9.2 | 9.8 | 5.7 | 12 | 16 | 45 | 76 | 100 | 39 | 160 | | |
| Upper | Compliance | G52S | Ammonia as N, dissolved | mg/L | G1, GMZ | 0.9 | | | | | | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Upper | Compliance | G54S | Ammonia as N, dissolved | mg/L | G1, GMZ | 0.9 | | | | | | | | | | | | | | | < 0.1 |
| Upper | Downgradient | R03S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 1.3 | 0.9 | 1.2 | R 1.2 | 1.1 | 0.9 | 1.2 | 1.3 | 0.93 | 0.84 | 0.66 | 0.45 | 0.4 | 0.22 | < 0.1 |
| Upper | Downgradient | R42S | Ammonia as N, dissolved | mg/l | G1, GMZ | 0.9 | 2.2 | 1.4 | 1.7 | 2 | 2 | 1.7 | 1.7 | 1.6 | 1.4 | 0.53 | 0.57 | 2.3 | 1.2 | 2.1 | 0.44 |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr08 | 4thQtr08 | 1stQtr09 | 2ndQtr09 | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|---------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Upper | Downgradient | G119 | Ammonia as N, total | mg/l | GMZ | 900 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Ammonia as N, total | mg/l | GMZ | 900 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Upper | Downgradient | G15S | Ammonia as N, total | mg/l | GMZ | 900 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Ammonia as N, total | mg/l | GMZ | 900 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | | | | | | | | |
| Upper | Downgradient | G18S | Ammonia as N, total | mg/l | GMZ | 900 | < 0.09 | Q 0.11 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | | | | | | | | |
| Upper | Downgradient | G33S | Ammonia as N, total | mg/l | GMZ | 900 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | | < 0.09 | < 0.1 | < 0.1 | < 0.1 | < 0.1 |
| Upper | Downgradient | G34S | Ammonia as N, total | mg/l | GMZ | 900 | 9.1 | 11 | 10 | 10 | 6.6 | 4.7 | 5.4 | 3.5 | 1.3 | 0.76 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | 25 |
| Upper | Downgradient | G35S | Ammonia as N, total | mg/l | GMZ | 900 | 3.8 | 4 | 3.4 | 1.2 | 2 | 1.9 | 1.6 | 1.1 | 1 | 0.86 | 0.62 | 0.39 | 0.23 | 0.3 | < 0.1 |
| Upper | Downgradient | G37S | Ammonia as N, total | mg/l | GMZ | 900 | < 0.09 | < 0.09 | < 0.09 | < 0.09 | | < 0.09 | < 0.09 | < 0.09 | 0.68 | 0.34 | 0.38 | < 0.1 | | | |
| Upper | Downgradient | G40S | Ammonia as N, total | mg/l | GMZ | 900 | 22 | 23 | 18 | 14 | 24 | 12 | 7.1 | 9.6 | | | | | | | |
| Upper | Downgradient | G41S | Ammonia as N, total | mg/l | GMZ | 900 | 1.2 | 19 | 4.7 | 2.5 | 1.2 | 1.6 | 1 | 0.66 | 0.28 | 0.32 | 2.3 | 1.4 | 0.19 | < 0.1 | 0.37 |
| Upper | Downgradient | G50S | Ammonia as N, total | mg/l | GMZ | 900 | | | < 0.09 | < 0.09 | 0.11 | 0.47 | < 0.09 | | | | | | | | |
| Upper | Downgradient | G51S | Ammonia as N, total | mg/l | GMZ | 900 | | | 5.9 | 9.6 | 8.8 | 7.8 | 5 | 16 | 4.6 | 77 | 100 | 290 | 180 | | |
| Upper | Compliance | G52S | Ammonia as N, total | mg/L | GMZ | 900 | | | | | | < 0.09 | < 0.09 | <Q 0.09 | < 0.09 | < 0.09 | < 0.09 | < 0.1 | < 0.1 | < 0.1 | Q3 0.17 |
| Upper | Compliance | G54S | Ammonia as N, total | mg/L | GMZ | 900 | | | | | | | | | | | | | | | < 0.1 |
| Upper | Downgradient | R03S | Ammonia as N, total | mg/l | GMZ | 900 | 1.3 | 0.97 | 1.2 | 1 | 1.2 | 0.93 | 1.1 | 1.2 | 0.93 | 0.86 | 0.61 | 0.5 | 0.34 | 0.21 | 0.16 |
| Upper | Downgradient | R42S | Ammonia as N, total | mg/l | GMZ | 900 | 2.2 | 1.5 | 1.8 | 1.9 | 1.9 | 1.8 | 1.8 | 1.6 | 1.7 | 0.54 | 1 | 2.3 | 1.7 | 2.2 | 0.51 |
| Upper | Downgradient | G119 | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Upper | Downgradient | G15S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | | | | | | | | |
| Upper | Downgradient | G18S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | | | | | | | | |
| Upper | Downgradient | G33S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | | < 1 | < 1 | < 1 | < 1 | < 1 |
| Upper | Downgradient | G34S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Upper | Downgradient | G35S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Upper | Downgradient | G37S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | | | |
| Upper | Downgradient | G40S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | 1.1 | 1.7 | 1.6 | 2.3 | 2.9 | 1.7 | 1.4 | 1.5 | | | | | | | |
| Upper | Downgradient | G41S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | 31 | 26 | 25 | 25 | 23 | 19 | 17 | 16 | 13 | 16 | 13 | 8.4 | 6.4 | < 1 | < 1 |
| Upper | Downgradient | G50S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | | | 1.2 | 1 | 1.2 | < 1 | 1.1 | | | | | | | | |
| Upper | Downgradient | G51S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | | | < 1 | 2.1 | 1.8 | 1.8 | 3.5 | 3.2 | 6.4 | 6.8 | 8.6 | 12 | 12 | | |
| Upper | Compliance | G52S | Arsenic, Dissolved | ug/L | G1, GMZ | 2 | | | | | | 1.1 | < 1 | 3.4 | 1.2 | 1.1 | < 1 | < 1 | 2 | 3 | < 1 |
| Upper | Compliance | G54S | Arsenic, Dissolved | ug/L | G1, GMZ | 2 | | | | | | | | | | | | | | | < 1 |
| Upper | Downgradient | R03S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Upper | Downgradient | R42S | Arsenic, Dissolved | ug/l | G1, GMZ | 2 | 57 | 38 | 27 | 52 | 52 | 40 | 28 | 36 | 31 | 12 | 7.5 | 40 | 30 | 42 | 8.2 |
| Upper | Downgradient | G119 | Arsenic, total | ug/l | GMZ | 10 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Arsenic, total | ug/l | GMZ | 10 | < 1 | < 1 | 1.2 | < 1 | < 1 | < 1 | 1.4 | < 1 | < 1 | < 1 | 3.2 | < 1 | < 1 | < 1 | < 1 |
| Upper | Downgradient | G15S | Arsenic, total | ug/l | GMZ | 10 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Arsenic, total | ug/l | GMZ | 10 | 1 | 1.4 | 1.2 | 1.2 | 1.2 | 1.7 | 2.4 | | | | | | | | |
| Upper | Downgradient | G18S | Arsenic, total | ug/l | GMZ | 10 | 31 | 69 | 140 | 34 | 52 | 110 | 8.9 | | | | | | | | |
| Upper | Downgradient | G33S | Arsenic, total | ug/l | GMZ | 10 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | | 8.2 | < 1 | < 1 | < 1 | 2 |
| Upper | Downgradient | G34S | Arsenic, total | ug/l | GMZ | 10 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | 7.6 | < 1 | < 1 | < 1 | 2 |
| Upper | Downgradient | G35S | Arsenic, total | ug/l | GMZ | 10 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 |
| Upper | Downgradient | G37S | Arsenic, total | ug/l | GMZ | 10 | < 1 | < 1 | < 1 | < 1 | | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | < 1 | | | |
| Upper | Downgradient | G40S | Arsenic, total | ug/l | GMZ | 10 | 1.3 | 1.2 | 1.7 | 2.6 | 5 | 2.3 | 2.2 | 2 | | | | | | | |
| Upper | Downgradient | G41S | Arsenic, total | ug/l | GMZ | 10 | 120 | 28 | 29 | 60 | 56 | 78 | 31 | 20 | 40 | 66 | 20 | 9.6 | 8.2 | 3.4 | 12 |
| Upper | Downgradient | G50S | Arsenic, total | ug/l | GMZ | 10 | | | 720 | 96 | 180 | 76 | 210 | | | | | | | | |
| Upper | Downgradient | G51S | Arsenic, total | ug/l | GMZ | 10 | | | 36 | 3.5 | 68 | 30 | 64 | 28 | 120 | 56 | 46 | 21 | 65 | | |
| Upper | Compliance | G52S | Arsenic, total | ug/L | GMZ | 10 | | | | | | 1.9 | 29 | 74 | 40 | 36 | 45 | 29 | 29 | 2 | 32 |
| Upper | Compliance | G54S | Arsenic, total | ug/L | GMZ | 10 | | | | | | | | | | | | | | | 18 |
| Upper | Downgradient | R03S | Arsenic, total | ug/l | GMZ | 10 | 3.3 | 1.8 | 4.6 | < 1 | < 1 | < 1 | 2.3 | 18 | 3.4 | < 1 | 5.6 | < 1 | 2 | 1 | 6.5 |
| Upper | Downgradient | R42S | Arsenic, total | ug/l | GMZ | 10 | 58 | 40 | 31 | 51 | 50 | 48 | 36 | 40 | 42 | 14 | 6.7 | 36 | 31 | 38 | 13 |
| Upper | Downgradient | G119 | Barium, total | ug/l | GMZ | 225180.6 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Barium, total | ug/l | GMZ | 225180.6 | 170 | 180 | 200 | 160 | 160 | 160 | 210 | 170 | 170 | 170 | 180 | 150 | 150 | 160 | 150 |
| Upper | Downgradient | G15S | Barium, total | ug/l | GMZ | 225180.6 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Barium, total | ug/l | GMZ | 225180.6 | 60 | 76 | 63 | 59 | 69 | 89 | 75 | | | | | | | | |
| Upper | Downgradient | G18S | Barium, total | ug/l | GMZ | 225180.6 | 500 | 1200 | 2100 | 720 | 1100 | 2800 | 1100 | | | | | | | | |
| Upper | Downgradient | G33S | Barium, total | ug/l | GMZ | 225180.6 | 73 | 73 | 81 | 66 | 68 | 80 | 85 | 78 | 71 | | 330 | 85 | 91 | 72 | 140 |
| Upper | Downgradient | G34S | Barium, total | ug/l | GMZ | 225180.6 | 160 | 180 | 160 | 150 | 140 | 150 | 140 | 120 | 100 | 110 | 200 | 85 | 82 | 73 | 130 |
| Upper | Downgradient | G35S | Barium, total | ug/l | GMZ | 225180.6 | 180 | 210 | 180 | 120 | 130 | 190 | 160 | 150 | 140 | 170 | 170 | 110 | 110 | 100 | 110 |
| Upper | Downgradient | G37S | Barium, total | ug/l | GMZ | 225180.6 | 43 | 50 | 49 | 46 | | 64 | 87 | 50 | 78 | 96 | 63 | 51 | | | |
| Upper | Downgradient | G40S | Barium, total | ug/l | GMZ | 225180.6 | 530 | 550 | 550 | 500 | 630 | 480 | 450 | 400 | | | | | | | |
| Upper | Downgradient | G41S | Barium, total | ug/l | GMZ | 225180.6 | 180 | 220 | 140 | 130 | 140 | 120 | 110 | 90 | 83 | 85 | 110 | 77 | 85 | 100 | 130 |
| Upper | Downgradient | G50S | Barium, total | ug/l | GMZ | 225180.6 | | | 2900 | 510 | 790 | 700 | 1200 | | | | | | | | |
| Upper | Downgradient | G51S | Barium, total | ug/l | GMZ | 225180.6 | | | 330 | 240 | 560 | 540 | 640 | 600 | 1400 | 930 | 1100 | 1000 | 1300 | | |
| Upper | Compliance | G52S | Barium, total | ug/L | GMZ | 225180.6 | | | | | | 74 | 520 | 800 | 710 | 560 | 860 | 540 | 340 | 68 | 380 |
| Upper | Compliance | G54S | Barium, total | ug/L | GMZ | 225180.6 | | | | | | | | | | | | | | | 720 |
| Upper | Downgradient | R03S | Barium, total | ug/l | GMZ | 225180.6 | 170 | 160 | 180 | 160 | 180 | 170 | 170 | 200 | 170 | 160 | 160 | 150 | 160 | 170 | 180 |
| Upper | Downgradient | R42S | Barium, total | ug/l | GMZ | 225180.6 | 470 | 400 | 340 | 330 | 320 | 420 | 380 | 330 | 530 | 540 | 450 | 940 | 740 | 840 | 470 |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr08 | 4thQtr08 | 1stQtr09 | 2ndQtr09 | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|---------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Upper | Downgradient | G119 | Boron, Dissolved | ug/l | G1, GMZ | 98 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Boron, Dissolved | ug/l | G1, GMZ | 98 | 19 | 21 | 15 | 15 | 16 | 11 | 14 | 11 | 21 | 14 | 12 | 11 | 18 | 11 | < 10 |
| Upper | Downgradient | G15S | Boron, Dissolved | ug/l | G1, GMZ | 98 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 22 | 43 | 35 | 15 | 22 | 33 | 32 | | | | | | | | |
| Upper | Downgradient | G18S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 94 | 100 | 68 | 58 | 92 | 110 | 59 | | | | | | | | |
| Upper | Downgradient | G33S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 11 | 15 | 13 | < 10 | < 10 | < 10 | < 10 | < 10 | 15 | | 11 | 16 | 29 | 15 | 15 |
| Upper | Downgradient | G34S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 72 | 78 | 60 | 63 | 44 | 46 | 44 | 22 | 37 | 32 | 11 | 19 | 38 | 18 | 15 |
| Upper | Downgradient | G35S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 39 | 56 | 31 | 20 | 18 | 40 | 30 | 13 | 24 | 36 | 20 | 12 | 41 | 13 | 14 |
| Upper | Downgradient | G37S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 35 | 36 | 20 | 27 | | 40 | 28 | 25 | 72 | 40 | 31 | 27 | | | |
| Upper | Downgradient | G40S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 140 | 180 | 140 | 150 | 340 | 150 | 180 | 220 | | | | | | | |
| Upper | Downgradient | G41S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 65 | 130 | 60 | 78 | 100 | 42 | 40 | 30 | 34 | 40 | 69 | 25 | 39 | 20 | 43 |
| Upper | Downgradient | G50S | Boron, Dissolved | ug/l | G1, GMZ | 98 | | | 140 | 42 | 45 | 53 | 48 | | | | | | | | |
| Upper | Downgradient | G51S | Boron, Dissolved | ug/l | G1, GMZ | 98 | | | 96 | 74 | 75 | 77 | 91 | 110 | 220 | 310 | 410 | 480 | 520 | | |
| Upper | Compliance | G52S | Boron, Dissolved | ug/L | G1, GMZ | 98 | | | | | | 41 | 62 | 65 | 68 | 59 | 70 | 65 | 28 | 68 | 70 |
| Upper | Compliance | G54S | Boron, Dissolved | ug/L | G1, GMZ | 98 | | | | | | | | | | | | | | < 10 | |
| Upper | Downgradient | R03S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 38 | 40 | 45 | 43 | 36 | 37 | 37 | 25 | 41 | 33 | 29 | 32 | 37 | 28 | 26 |
| Upper | Downgradient | R42S | Boron, Dissolved | ug/l | G1, GMZ | 98 | 84 | 88 | 77 | 80 | 83 | 78 | 79 | 68 | 94 | 52 | 62 | 80 | 72 | 99 | 56 |
| Upper | Downgradient | G119 | Boron, total | ug/l | GMZ | 200 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Boron, total | ug/l | GMZ | 200 | 22 | 17 | 15 | 12 | < 10 | 17 | 19 | 12 | < 10 | 20 | 18 | 15 | < 10 | 15 | 11 |
| Upper | Downgradient | G15S | Boron, total | ug/l | GMZ | 200 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Boron, total | ug/l | GMZ | 200 | 33 | 41 | 26 | 14 | 20 | 42 | 44 | | | | | | | | |
| Upper | Downgradient | G18S | Boron, total | ug/l | GMZ | 200 | 200 | 360 | 580 | 130 | 220 | 490 | 86 | | | | | | | | |
| Upper | Downgradient | G33S | Boron, total | ug/l | GMZ | 200 | 14 | < 10 | 10 | 12 | < 10 | < 10 | 14 | 18 | 15 | | 30 | 18 | 47 | 20 | 20 |
| Upper | Downgradient | G34S | Boron, total | ug/l | GMZ | 200 | 78 | 71 | 65 | 62 | 40 | 43 | 41 | 36 | 43 | 30 | 14 | 20 | 38 | 27 | 16 |
| Upper | Downgradient | G35S | Boron, total | ug/l | GMZ | 200 | 42 | 50 | 41 | 21 | 13 | 36 | 31 | 28 | 28 | 27 | 16 | 15 | 29 | 15 | 11 |
| Upper | Downgradient | G37S | Boron, total | ug/l | GMZ | 200 | 53 | 28 | 18 | 28 | | 37 | 29 | 31 | 61 | 34 | 35 | 30 | | | |
| Upper | Downgradient | G40S | Boron, total | ug/l | GMZ | 200 | 150 | 160 | 160 | 140 | 360 | 150 | 180 | 220 | | | | | | | |
| Upper | Downgradient | G41S | Boron, total | ug/l | GMZ | 200 | 70 | 130 | 57 | 66 | 96 | 39 | 40 | 36 | 31 | 38 | 66 | 29 | 27 | 28 | 38 |
| Upper | Downgradient | G50S | Boron, total | ug/l | GMZ | 200 | | | 610 | 100 | 180 | 130 | 320 | | | | | | | | |
| Upper | Downgradient | G51S | Boron, total | ug/l | GMZ | 200 | | | 130 | 67 | 120 | 110 | 160 | 150 | 260 | 330 | 450 | 440 | 500 | | |
| Upper | Compliance | G52S | Boron, total | ug/L | GMZ | 200 | | | | | | 34 | 200 | 250 | 260 | 220 | 290 | 210 | 150 | 71 | 160 |
| Upper | Compliance | G54S | Boron, total | ug/L | GMZ | 200 | | | | | | | | | | | | | | | 72 |
| Upper | Downgradient | R03S | Boron, total | ug/l | GMZ | 200 | 41 | 30 | 46 | 31 | 34 | 31 | 35 | 32 | 25 | 30 | 39 | 31 | 25 | 32 | 29 |
| Upper | Downgradient | R42S | Boron, total | ug/l | GMZ | 200 | 86 | 65 | 85 | 66 | 79 | 100 | 98 | 85 | 98 | 47 | 53 | 85 | 67 | 100 | 60 |
| Upper | Downgradient | G119 | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 34 | 39 | 45 | 47 | 48 | 43 | 46 | 49 | 37 | 40 | 30 | 30 | 37 | 36 | 25 |
| Upper | Downgradient | G15S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 22 | 48 | 8.4 | 11 | 14 | 7.4 | 6.3 | | | | | | | | |
| Upper | Downgradient | G18S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 7.6 | 16 | 48 | 70 | 26 | 35 | 110 | | | | | | | | |
| Upper | Downgradient | G33S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 14 | 16 | 28 | 27 | 21 | 25 | 31 | | 27 | 26 | | 36 | 32 | 23 | 27 |
| Upper | Downgradient | G34S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 42 | 53 | 35 | 36 | 34 | 40 | 35 | 29 | 41 | 29 | 33 | 35 | 28 | 23 | 27 |
| Upper | Downgradient | G35S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 37 | 34 | 32 | 26 | 26 | 44 | 34 | 27 | 21 | 19 | 35 | 34 | 21 | 21 | 27 |
| Upper | Downgradient | G37S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 46 | 55 | 49 | 54 | | 57 | 50 | 47 | 36 | 32 | 36 | 33 | | | |
| Upper | Downgradient | G40S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 270 | 89 | 290 | 260 | 290 | 210 | 200 | 190 | | | | | | | |
| Upper | Downgradient | G41S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 50 | 78 | 100 | 74 | 70 | 42 | 42 | 52 | 55 | 44 | 59 | 39 | 37 | 28 | 50 |
| Upper | Downgradient | G50S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | | | 120 | 35 | 36 | 42 | 35 | | | | | | | | |
| Upper | Downgradient | G51S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | | | 86 | 140 | 190 | 280 | 270 | 480 | 820 | 740 | 790 | 1000 | 4.4 | | |
| Upper | Compliance | G52S | Chloride, Dissolved | mg/L | G1, GMZ | 87.511 | | | | | | 65 | 75 | 52 | 53 | 45 | 41 | 42 | 38 | | 34 |
| Upper | Compliance | G54S | Chloride, Dissolved | mg/L | G1, GMZ | 87.511 | | | | | | | | | | | | | | | 19 |
| Upper | Downgradient | R03S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 45 | 52 | 53 | 49 | 48 | 41 | 45 | 40 | 45 | 42 | 40 | 43 | 43 | | 42 |
| Upper | Downgradient | R42S | Chloride, Dissolved | mg/l | G1, GMZ | 87.511 | 100 | 83 | 110 | 82 | 50 | 63 | 33 | 26 | 96 | 63 | 63 | 140 | 100 | 110 | 67 |
| Upper | Downgradient | G119 | Chloride, total | mg/l | GMZ | 87.51186 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Chloride, total | mg/l | GMZ | 87.51186 | 33 | 40 | 45 | 48 | 48 | 45 | 52 | 49 | 38 | 43 | 30 | 30 | 41 | 2.9 | 24 |
| Upper | Downgradient | G15S | Chloride, total | mg/l | GMZ | 87.51186 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Chloride, total | mg/l | GMZ | 87.51186 | 21 | 44 | 7.5 | 9.6 | 14 | 7.7 | 5.9 | | | | | | | | |
| Upper | Downgradient | G18S | Chloride, total | mg/l | GMZ | 87.51186 | 11 | 23 | 48 | 70 | 26 | 33 | 110 | | | | | | | | |
| Upper | Downgradient | G33S | Chloride, total | mg/l | GMZ | 87.51186 | 16 | 16 | 27 | 28 | 22 | 27 | 32 | 30 | 26 | | 37 | 31 | 21 | 29 | 27 |
| Upper | Downgradient | G34S | Chloride, total | mg/l | GMZ | 87.51186 | 42 | 54 | 34 | 38 | 35 | 40 | 35 | 31 | 38 | 30 | 33 | 35 | 29 | 34 | 27 |
| Upper | Downgradient | G35S | Chloride, total | mg/l | GMZ | 87.51186 | 39 | 35 | 34 | 26 | 27 | 44 | 35 | 28 | 21 | 18 | 35 | 34 | 21 | 21 | 24 |
| Upper | Downgradient | G37S | Chloride, total | mg/l | GMZ | 87.51186 | 46 | 55 | 49 | 56 | | 60 | 51 | 47 | 36 | 32 | 35 | 33 | | | |
| Upper | Downgradient | G40S | Chloride, total | mg/l | GMZ | 87.51186 | 220 | 250 | 270 | 260 | 300 | 210 | 180 | 180 | | | | | | | |
| Upper | Downgradient | G41S | Chloride, total | mg/l | GMZ | 87.51186 | 50 | 78 | 91 | 72 | 68 | 45 | 45 | 54 | 53 | 43 | 59 | 39 | 39 | 31 | 32 |
| Upper | Downgradient | G50S | Chloride, total | mg/l | GMZ | 87.51186 | | | 140 | 38 | 32 | 33 | 36 | | | | | | | | |
| Upper | Downgradient | G51S | Chloride, total | mg/l | GMZ | 87.51186 | | | 76 | 140 | 200 | 280 | 260 | 470 | 830 | 610 | 900 | 1000 | 1200 | | |
| Upper | Compliance | G52S | Chloride, total | mg/L | GMZ | 87.51186 | | | | | | 68 | 72 | 55 | 47 | 48 | 45 | 43 | 42 | 36 | 35 |
| Upper | Compliance | G54S | Chloride, total | mg/L | GMZ | 87.51186 | | | | | | | | | | | | | | | 17 |
| Upper | Downgradient | R03S | Chloride, total | mg/l | GMZ | 87.51186 | 48 | 51 | 60 | 50 | 56 | 44 | 41 | 39 | 45 | 39 | 39 | 40 | 44 | 42 | 38 |
| Upper | Downgradient | R42S | Chloride, total | mg/l | GMZ | 87.51186 | 100 | 98 | 110 | 79 | 47 | 63 | 28 | 28 | 120 | 70 | 70 | 140 | 160 | 140 | 92 |

Note: A highlighted cell indicates an exceedence of the AGQS value.

Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr08 | 4thQtr08 | 1stQtr09 | 2ndQtr09 | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|-------------------------|-------|---------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Upper | Downgradient | G119 | Ethylbenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G15S | Ethylbenzene | ug/l | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G18S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G33S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | | | < 1 | | < 1 | |
| Upper | Downgradient | G34S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G35S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G37S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Upper | Downgradient | G40S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | | | | | | |
| Upper | Downgradient | G41S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G50S | Ethylbenzene | ug/l | G2, GMZ | 5 | | | | < 1 | | < 1 | | | | | | | | | |
| Upper | Downgradient | G51S | Ethylbenzene | ug/l | G2, GMZ | 5 | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | | |
| Upper | Compliance | G52S | Ethylbenzene | ug/L | G2, GMZ | 5 | | | | | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Compliance | G54S | Ethylbenzene | ug/L | G2, GMZ | 5 | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | R42S | Ethylbenzene | ug/l | G2, GMZ | 5 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | | < 1 | |
| Upper | Downgradient | G119 | Fluoride, total | mg/l | GMZ | 273.35 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.41 | < 0.25 | 0.4 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 |
| Upper | Downgradient | G15S | Fluoride, total | mg/l | GMZ | 273.35 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.3 | < 0.25 | < 0.25 | | | | | | | | |
| Upper | Downgradient | G18S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | 0.26 | < 0.25 | 0.38 | < 0.25 | < 0.25 | | | | | | | | |
| Upper | Downgradient | G33S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.4 | < 0.25 | < 0.25 | 0.42 | 0.26 | | < 0.25 | < 0.25 | 0.26 | 0.4 | 0.311 |
| Upper | Downgradient | G34S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.44 | < 0.25 | 0.25 | 0.25 | < 0.25 | < 0.25 | 0.28 | < 0.25 | 0.311 |
| Upper | Downgradient | G35S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.31 | 0.27 | 0.351 |
| Upper | Downgradient | G37S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | 0.3 | < 0.25 | | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | | | |
| Upper | Downgradient | G40S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | | | | | | | |
| Upper | Downgradient | G41S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.264 |
| Upper | Downgradient | G50S | Fluoride, total | mg/l | GMZ | 273.35 | | | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | | | | | | | |
| Upper | Downgradient | G51S | Fluoride, total | mg/l | GMZ | 273.35 | | | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | | |
| Upper | Compliance | G52S | Fluoride, total | mg/L | GMZ | 273.35 | | | | | | < 0.25 | < 0.25 | 0.45 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.32 | < 2.5 |
| Upper | Compliance | G54S | Fluoride, total | mg/L | GMZ | 273.35 | | | | | | | | | | | | | | | 0.291 |
| Upper | Downgradient | R03S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.25 | < 0.25 | < 2.5 | < 0.25 |
| Upper | Downgradient | R42S | Fluoride, total | mg/l | GMZ | 273.35 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | < 0.25 | 0.39 | 0.49 | < 0.25 | < 0.25 | 0.25 | < 0.25 | < 0.25 | 0.27 | < 0.25 |
| Upper | Downgradient | G119 | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 11 | 12 | 13 | 12 | H 13 | 12 | 12 | 12 | 12 | 12 | 12 | 12 | 12 | 13 | 11 |
| Upper | Downgradient | G15S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 2.9 | 1.9 | 0.83 | 2.2 | 1.5 | 1.4 | 2.1 | | | | | | | | |
| Upper | Downgradient | G18S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 1.8 | 0.45 | 3 | 3 | 1.7 | 1.6 | H 2.5 | | | | | | | | |
| Upper | Downgradient | G33S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 7.4 | 7.5 | 9.6 | 9 | H 9.3 | 10 | 10 | 9.4 | 10 | | 5.7 | 5.6 | 6.1 | 5.6 | 7.5 |
| Upper | Downgradient | G34S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 4.3 | 5.7 | 3.6 | 3.8 | H 4.3 | 3.2 | 2.6 | 5.5 | 6.3 | 5.6 | 7.1 | 5.4 | 5.8 | 5.4 | 6.6 |
| Upper | Downgradient | G35S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 2.3 | 1.2 | 3.7 | 3.3 | H 3.3 | H 0.8 | 2.3 | 2 | 0.4 | 2.2 | 3.4 | 8.5 | 0.07 | 5 | 7.4 |
| Upper | Downgradient | G37S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | 5 | 5.3 | 5.3 | 4.6 | | 6.5 | 4.6 | 7.6 | 3.1 | 0.84 | 1.6 | 2.7 | | | |
| Upper | Downgradient | G40S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | H 1.7 | 0.63 | 0.047 | < 0.02 | < 0.02 | < 0.02 | < 0.02 | H 2 | | | | | | | |
| Upper | Downgradient | G41S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | < 0.02 | < 0.02 | 0.032 | < 0.02 | 0.083 | 0.069 | 0.044 | 0.048 | 0.036 | < 0.02 | 0.029 | < 0.02 | < 0.02 | 2.5 | 4.6 |
| Upper | Downgradient | G50S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | | | 0.12 | 3.2 | 3.1 | 0.52 | 0.88 | | | | | | | | |
| Upper | Downgradient | G51S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | | | 0.25 | 0.085 | 0.42 | 2.7 | < 0.2 | 0.57 | 0.054 | H 0.19 | 0.098 | 0.2 | H 0.09 | | |
| Upper | Compliance | G52S | Nitrate as N, dissolved | mg/L | G1, GMZ | 11.74 | | | | | | 2.3 | 6.5 | 2.8 | 4 | 5.2 | 6.1 | 5.6 | 5.9 | | 4.4 |
| Upper | Compliance | G54S | Nitrate as N, dissolved | mg/L | G1, GMZ | 11.74 | | | | | | | | | | | | | | | 4.2 |
| Upper | Downgradient | R03S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | H 3.1 | 3.2 | 2.2 | 3.9 | 3.3 | 3.9 | H 11 | H 3.7 | H 3 | H 2.4 | H 3.4 | 3.6 | H 3.5 | | 3.5 |
| Upper | Downgradient | R42S | Nitrate as N, dissolved | mg/l | G1, GMZ | 11.74 | < 0.02 | H 0.45 | 0.034 | < 0.02 | 0.093 | 0.12 | 0.071 | 0.065 | 0.065 | 0.55 | 0.31 | < 0.02 | < 0.02 | < 0.02 | 0.2 |
| Upper | Downgradient | G119 | Nitrate as N, total | mg/l | GMZ | 11.7389 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Nitrate as N, total | mg/l | GMZ | 11.7389 | 12 | 13 | 13 | 13 | H 13 | 12 | 13 | 12 | 12 | 12 | 12 | 12 | 12 | 11 | 11 |
| Upper | Downgradient | G15S | Nitrate as N, total | mg/l | GMZ | 11.7389 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Nitrate as N, total | mg/l | GMZ | 11.7389 | 2.8 | 2 | 0.77 | 2.3 | 1.5 | 1.4 | 2 | | | | | | | | |
| Upper | Downgradient | G18S | Nitrate as N, total | mg/l | GMZ | 11.7389 | 2.1 | 0.19 | 2.6 | 2.2 | 1.4 | 1.8 | H 2.6 | | | | | | | | |
| Upper | Downgradient | G33S | Nitrate as N, total | mg/l | GMZ | 11.7389 | 8.6 | 7.9 | 10 | 9.9 | H 11 | 11 | 12 | 11 | 10 | | 5.9 | 5.4 | 4.6 | 5.3 | 7.6 |
| Upper | Downgradient | G34S | Nitrate as N, total | mg/l | GMZ | 11.7389 | 4.4 | 6.1 | 3.6 | 6.4 | H 4.4 | 3.2 | 3.6 | 5.8 | 6.2 | 5.6 | 7.2 | 5.4 | 6.4 | 5.6 | 6.6 |
| Upper | Downgradient | G35S | Nitrate as N, total | mg/l | GMZ | 11.7389 | 2.2 | 1.2 | 4 | 3.4 | H 3.4 | H 0.66 | 2.3 | 2 | 0.32 | 2.2 | 3.3 | 8.6 | 0.15 | 4.4 | 6.1 |
| Upper | Downgradient | G37S | Nitrate as N, total | mg/l | GMZ | 11.7389 | 5 | 5.2 | 5.2 | 4.7 | | 6.8 | 4.8 | 7.8 | 3.7 | 0.85 | 1.6 | 2.8 | | | |
| Upper | Downgradient | G40S | Nitrate as N, total | mg/l | GMZ | 11.7389 | H 2.4 | 1.7 | 0.55 | < 0.02 | 0.11 | < 0.02 | 3.4 | 1.3 | | | | | | | |
| Upper | Downgradient | G41S | Nitrate as N, total | mg/l | GMZ | 11.7389 | 0.098 | 0.061 | 4.6 | 0.03 | 0.076 | 0.064 | 0.098 | < 0.02 | 0.96 | < 0.02 | 0.032 | 0.07 | 0.06 | 2.9 | 3.2 |
| Upper | Downgradient | G50S | Nitrate as N, total | mg/l | GMZ | 11.7389 | | | < 0.02 | 3.6 | 3.2 | 0.92 | 1 | | | | | | | | |
| Upper | Downgradient | G51S | Nitrate as N, total | mg/l | GMZ | 11.7389 | | | 0.31 | 0.074 | 0.17 | 0.4 | < 0.2 | 0.74 | < 0.02 | H 0.55 | 0.089 | 0.08 | H 0.17 | | |
| Upper | Compliance | G52S | Nitrate as N, total | mg/L | GMZ | 11.7389 | | | | | | 2.2 | 7 | 4.1 | 5.5 | 6.7 | 6.1 | 6.4 | 5.4 | 4.3 | 3.9 |
| Upper | Compliance | G54S | Nitrate as N, total | mg/L | GMZ | 11.7389 | | | | | | | | | | | | | | | 2.6 |
| Upper | Downgradient | R03S | Nitrate as N, total | mg/l | GMZ | 11.7389 | H 2.9 | 3.3 | 2 | 4 | 3.9 | 4 | H 5.4 | H 3.7 | H 3.3 | H 2.9 | H 3.5 | 4 | H 3.9 | 4.3 | 5.6 |
| Upper | Downgradient | R42S | Nitrate as N, total | mg/l | GMZ | 11.7389 | < 0.02 | 0.041 | < 0.02 | < 0.02 | 0.14 | 0.068 | 0.063 | 0.061 | 0.046 | 0.16 | 0.39 | < 0.02 | < 0.02 | < 0.02 | 0.46 |

Note: A highlighted cell indicates an exceedence of the AGQS value.


Table 4
Winnebago Landfill
Historical Northern Unit GMZ Analytical Data

| Zone | Location | Well ID | Parameter | Units | GW List | AGQS | 3rdQtr08 | 4thQtr08 | 1stQtr09 | 2ndQtr09 | 3rdQtr09 | 4thQtr09 | 1stQtr10 | 2ndQtr10 | 3rdQtr10 | 4thQtr10 | 1stQtr11 | 2ndQtr11 | 3rdQtr11 | 4thQtr11 | 1stQtr12 |
|-------|--------------|---------|------------------|-------|---------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Upper | Downgradient | G119 | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Potassium, total | mg/l | GMZ | 29.00582 | 1.4 | 1.6 | 2.2 | 1.3 | 1.6 | 1.4 | 2.5 | 1.4 | 1.3 | 1.5 | 2.1 | 1 | 1.1 | 1.2 | 1.4 |
| Upper | Downgradient | G15S | Potassium, total | mg/l | GMZ | 29.00582 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Potassium, total | mg/l | GMZ | 29.00582 | 2.1 | 3.6 | 3 | 2.4 | 3.3 | 4.3 | 3.4 | | | | | | | | |
| Upper | Downgradient | G18S | Potassium, total | mg/l | GMZ | 29.00582 | 18 | 33 | 63 | 17 | 24 | 77 | 12 | | | | | | | | |
| Upper | Downgradient | G33S | Potassium, total | mg/l | GMZ | 29.00582 | 1 | 1.5 | 1.9 | 1.2 | 1.4 | 1.3 | 2.1 | 1.6 | 1.4 | | 6.8 | 1.8 | 1.9 | 1.4 | 4.1 |
| Upper | Downgradient | G34S | Potassium, total | mg/l | GMZ | 29.00582 | 8.3 | 9.4 | 9.6 | 9 | 8.1 | 8.2 | 7 | 5.9 | 4.4 | 3.8 | 4.4 | 1.7 | 2.4 | 2 | 2.8 |
| Upper | Downgradient | G35S | Potassium, total | mg/l | GMZ | 29.00582 | 7 | 7.6 | 6.5 | 4.2 | 4.8 | 5.6 | 4.4 | 3.6 | 3.7 | 3.9 | 3 | 2.2 | 1.8 | 2.2 | 1.9 |
| Upper | Downgradient | G37S | Potassium, total | mg/l | GMZ | 29.00582 | 3.2 | 2.9 | 2 | 1.8 | | 3.2 | 2.6 | 3.1 | 6.3 | 4.9 | 3.7 | 2.7 | | | |
| Upper | Downgradient | G40S | Potassium, total | mg/l | GMZ | 29.00582 | 23 | 23 | 21 | 20 | 23 | 16 | 14 | 14 | | | | | | | |
| Upper | Downgradient | G41S | Potassium, total | mg/l | GMZ | 29.00582 | 9.3 | 15 | 7.5 | 5.8 | 5.7 | 6.2 | 5.2 | 4.4 | 4 | 4.9 | 7.9 | 5.1 | 4.6 | 3.4 | 4.5 |
| Upper | Downgradient | G50S | Potassium, total | mg/l | GMZ | 29.00582 | | | 75 | 13 | 22 | 19 | 50 | | | | | | | | |
| Upper | Downgradient | G51S | Potassium, total | mg/l | GMZ | 29.00582 | | | 13 | 15 | 20 | 20 | 24 | 21 | 31 | 30 | 39 | 39 | 46 | | |
| Upper | Compliance | G52S | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | 3.6 | 22 | 25 | 41 | 36 | 55 | 35 | 14 | 3.7 | 24 |
| Upper | Compliance | G54S | Potassium, total | mg/L | GMZ | 29.00582 | | | | | | | | | | | | | | | 14 |
| Upper | Downgradient | R03S | Potassium, total | mg/l | GMZ | 29.00582 | 4.8 | 4.3 | 4.9 | 4.5 | 4.5 | 4.2 | 4.1 | 4.5 | 3.8 | 3.7 | 3.8 | 3.7 | 3.8 | 3.4 | 3.7 |
| Upper | Downgradient | R42S | Potassium, total | mg/l | GMZ | 29.00582 | 1.7 | 1.4 | 1.5 | 1.6 | 1.4 | 1.4 | 1.5 | 1.3 | 1.5 | 0.78 | 0.71 | 1.4 | 1.1 | 1.4 | 1.3 |
| Upper | Downgradient | G119 | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Sodium, total | mg/l | GMZ | 164.7897 | 12 | 11 | 14 | 13 | 16 | 16 | 14 | 16 | 12 | 13 | 10 | 7.8 | 10 | 9.8 | 6.9 |
| Upper | Downgradient | G15S | Sodium, total | mg/l | GMZ | 164.7897 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Sodium, total | mg/l | GMZ | 164.7897 | 8.2 | 20 | 15 | 8.9 | 16 | 21 | 12 | | | | | | | | |
| Upper | Downgradient | G18S | Sodium, total | mg/l | GMZ | 164.7897 | 7.6 | 11 | 16 | 27 | 16 | 27 | 35 | | | | | | | | |
| Upper | Downgradient | G33S | Sodium, total | mg/l | GMZ | 164.7897 | 5.8 | 5.2 | 7.5 | 8.2 | 7.4 | 8 | 7.6 | 7.9 | 10 | | 12 | 13 | 11 | 12 | 11 |
| Upper | Downgradient | G34S | Sodium, total | mg/l | GMZ | 164.7897 | 18 | 19 | 17 | 15 | 14 | 15 | 16 | 14 | 16 | 13 | 12 | 15 | 17 | 11 | 11 |
| Upper | Downgradient | G35S | Sodium, total | mg/l | GMZ | 164.7897 | 14 | 15 | 12 | 9.3 | 10 | 17 | 14 | 12 | 11 | 11 | 11 | 14 | 10 | 10 | 11 |
| Upper | Downgradient | G37S | Sodium, total | mg/l | GMZ | 164.7897 | 16 | 20 | 20 | 18 | | 23 | 19 | 19 | 18 | 15 | 14 | 13 | | | |
| Upper | Downgradient | G40S | Sodium, total | mg/l | GMZ | 164.7897 | 97 | 110 | 100 | 100 | 130 | 95 | 90 | 92 | | | | | | | |
| Upper | Downgradient | G41S | Sodium, total | mg/l | GMZ | 164.7897 | 20 | 32 | 27 | 27 | 30 | 18 | 16 | 18 | 12 | 13 | 23 | 15 | 15 | 13 | 18 |
| Upper | Downgradient | G50S | Sodium, total | mg/l | GMZ | 164.7897 | | | 50 | 10 | 10 | 11 | 16 | | | | | | | | |
| Upper | Downgradient | G51S | Sodium, total | mg/l | GMZ | 164.7897 | | | 55 | 48 | 42 | 60 | 72 | 120 | 220 | 230 | 240 | 270 | 360 | | |
| Upper | Compliance | G52S | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | 31 | 24 | 18 | 21 | 24 | 23 | 20 | 16 | 17 | 16 |
| Upper | Compliance | G54S | Sodium, total | mg/L | GMZ | 164.7897 | | | | | | | | | | | | | | | 7.2 |
| Upper | Downgradient | R03S | Sodium, total | mg/l | GMZ | 164.7897 | 17 | 18 | 19 | 17 | 18 | 19 | 17 | 17 | 19 | 17 | 17 | 16 | 17 | 17 | 18 |
| Upper | Downgradient | R42S | Sodium, total | mg/l | GMZ | 164.7897 | 54 | 54 | 52 | 49 | 52 | 52 | 43 | 39 | 42 | 43 | 46 | 44 | 44 | 47 | 32 |
| Upper | Downgradient | G119 | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G130 | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Upper | Downgradient | G15S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | | | | | | | | | | | | |
| Upper | Downgradient | G17S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | | | | | | | | |
| Upper | Downgradient | G18S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | | | | | | | | |
| Upper | Downgradient | G33S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | | | < 2 | | < 2 | |
| Upper | Downgradient | G34S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Upper | Downgradient | G35S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | 2.6 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Upper | Downgradient | G37S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | | |
| Upper | Downgradient | G40S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | | | | | | |
| Upper | Downgradient | G41S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | 36 | | 3.2 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Upper | Downgradient | G50S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | < 2.5 | | < 2.5 | | | | | | | | | |
| Upper | Downgradient | G51S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | | | 4.3 | | 18 | | 44 | | 61 | | 94 | | | |
| Upper | Compliance | G52S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Upper | Compliance | G54S | Tetrahydrofuran | ug/L | G2, GMZ | 42 | | | | | | | | | | | | | | | |
| Upper | Downgradient | R03S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |
| Upper | Downgradient | R42S | Tetrahydrofuran | ug/l | G2, GMZ | 42 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2.5 | | < 2 | | < 2 | |

Note: A highlighted cell indicates an exceedence of the AGQS value.


FIGURES

File: J:\1990\90-114 (Winnebago)\DWG\XSEC IMAGE revised.dwg Tab: C-C' (11x17) User: wulewicz Plotted: Apr 10, 2012 - 2:26 PM




NOTE:

1. GROUNDWATER ELEVATIONS ARE BASED ON WATER LEVEL DATA COLLECTED ON 02/17/95.
2. THE DISTANCED BETWEEN BORING LOCATIONS WERE ESTIMATED BASED ON STRAIGHT-LINE TRANSECTS.



SCALE: IN FEET

GRAPHIC SCALE
10X VERTICAL EXAGGERATION




EAST-WEST PROFILE C-C'

PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

DATE:
APRIL 2007
PROJECT ID:
90-114
SHEET NUMBER:


FIG. 2

ANDREWS
ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7235
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO



APPROVED BY: SRH DESIGNED BY: SRH DRAWN BY: MPN

File: J:\1990\90-114 (Winnebago)\DWG\K1\1995 GMZ EXTENT.dwg Tab: UPPER ZONE (11X17) FIG 4 User: wulewicz Plotted: Apr 20, 2012 - 2:12 PM



ANDREWS
ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

APPROVED BY: SRH DESIGNED BY: SRH DRAWN BY: MPN

1995 UPPER ZONE GMZ EXTENT

PLANS PREPARED FOR
WINNEBAGO RECLAMATION SERVICE, INC.
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS


DATE:
APRIL 2007


PROJECT ID:
90-114

SHEET NUMBER:
FIG. 3


© 2007 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\DWG\K1\1995 GMZ EXTENT.dwg Tab: LOWER ZONE (11X17) FIG 5 User: wulewicz Plotted: Apr 20, 2012 - 2:12 PM



| | | |
|---|--|------------------|
|  | ANDREWS ENGINEERING, INC. 3300 Ginger Creek Drive, Springfield, IL 62711-7233 Tel (217) 787-2334 Fax (217) 787-9495 Poniac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO | |
| | APPROVED BY: SRH | DESIGNED BY: SRH |
| 1995 LOWER ZONE GMZ EXTENT PLANS PREPARED FOR WINNEBAGO RECLAMATION SERVICE, INC. ROCKFORD, WINNEBAGO COUNTY, ILLINOIS | | |
| DATE: APRIL 2007 | | |
| PROJECT ID: 90-114 | | |
| SHEET NUMBER: | | |
| FIG. 4 | | |
| © 2007 Andrews Engineering, Inc. | | |

File: J:\1990\90-114 (Winnebago)\DWG\K1\GMZ_OUTLINES 2004 REV 0708-05.dwg Tab: UPPER ZONE (11X17) User: wulewicz Plotted: Apr 20, 2012 - 2:13 PM



NOTE:
FACILITY STRUCTURES SHOWN REPRESENT CONDITIONS IN 2004.



ANDREWS
ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

APPROVED BY: SRH DESIGNED BY: SRH DRAWN BY: MPN

2004 UPPER ZONE GMZ EXTENT

PLANS PREPARED FOR
WINNEBAGO RECLAMATION SERVICE, INC.
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS


DATE:
APRIL 2007

PROJECT ID:
90-114

SHEET NUMBER:


FIG. 5

File: J:\1990\90-114 (Winnebago)\DWG\K1\GMZ_OUTLINES 2004 REV 0708-05.dwg Tab: LOWER ZONE (11X17) User: wulewicz Plotted: Apr 20, 2012 - 2:13 PM




| EXPLANATION | |
|-------------|----------------------------|
| | SOUTH UNIT MONITORING WELL |
| | NON-PERMITTED PIEZOMETER |
| | GMZ MONITORING WELL |
| | GAS PROBE |

NOTE:
FACILITY STRUCTURES SHOWN REPRESENT CONDITIONS IN 2004.


| | | | |
|---|---|--------------------|---------------|
|  | ANDREWS ENGINEERING, INC. 3300 Ginger Creek Drive, Springfield, IL 62711-7233 Tel (217) 787-2334 Fax (217) 787-9495 Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO | | |
| | APPROVED BY: SRH | DESIGNED BY: SRH | DRAWN BY: MPN |
| | 2004 LOWER ZONE GMZ EXTENT | | |
| | PLANS PREPARED FOR WINNEBAGO RECLAMATION SERVICE, INC. ROCKFORD, WINNEBAGO COUNTY, ILLINOIS | | |
| DATE: APRIL 2007 | | PROJECT ID: 90-114 | FIG. 6 |
| SHEET NUMBER: | | | |

File: J:\1990\90-114 (Winnebago)\DWG\gmz-bedrock zone xsec.dwg Tab: C-C' (11x17) User: wulewicz Plotted: Apr 10, 2012 - 2:35 PM




NOTE:

1. GROUNDWATER ELEVATIONS ARE BASED ON WATER LEVEL DATA COLLECTED SECOND QUARTER 2005.
2. THE DISTANCED BETWEEN BORING LOCATIONS WERE ESTIMATED BASED ON STRAIGHT-LINE TRANSECTS.




SCALE: IN FEET

GRAPHIC SCALE
10X VERTICAL EXAGGERATION



2004 GMZ VERTICAL BOUNDARY MAP

PLANS PREPARED FOR
WINNEBAGO RECLAMATION SERVICE, INC.
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS



**ANDREWS
ENGINEERING, INC.**

3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

APPROVED BY: SRH DESIGNED BY: SRH DRAWN BY: MPN

DATE:

APRIL 2007


PROJECT ID:

90-114

SHEET NUMBER:

FIG. 7

File: J:\1990\90-114 (Winnebago)\DWG\K1\2008 GMZ INV\GMZ INVESTIGATION.dwg Tab: GMZ EXTENT REV User: wulewicz Plotted: Apr 20, 2012 - 2:14 PM



EXPLANATION

- BEDROCK MONITORING WELL
- UPPER GMZ MONITORING WELL
- LOWER GMZ MONITORING WELL
- UPPER GMZ EXTENT LIMIT
- LOWER GMZ EXTENT LIMIT

- NOTES:
- SGX = SURFACE WATER COLLECTION POINT
 - COMPREHENSIVE MAP FOR THE OUTLINE OF GMZ BASED ON THE INDIVIDUAL PARAMETER MAPS (FURTHEST EXTENT)
 - HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
 - GMZ EXTENT LINES REPRESENT THE APPROXIMATE FURTHEST EXTENT OF GMZ PARAMETERS DETECTED ABOVE THE PERMITTED BACKGROUND VALUES/STANDARDS. CLEAN AREAS/WELLS MAY EXIST INSIDE THE GMZ BOUNDARIES. THE REVISED GMZ BOUNDARIES DO NOT CONSTITUTE AN INCREASE IN THE SIZE OF THE GMZ BUT NOW INCLUDE ALL AFFECTED AREAS.
 - FACILITY STRUCTURES SHOWN REPRESENT CONDITIONS IN 2007.

ANDREWS
ENGINEERING, INC.

3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO




2007 GMZ EXTENT MAP - REVISED
PLANS PREPARED FOR
WINNEBAGO RECLAMATION SERVICE, INC.
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS


DATE:
APRIL 2008
PROJECT ID:
90-114
SHEET NUMBER:

FIG. 8

File: J:\1990\90-114 (Winnebago)\DWG\gmz-bedrock zone xsec.dwg Tab: fig-9 User: wulewicz Plotted: Apr 11, 2012 - 8:57 AM




- NOTE:**
1. GROUNDWATER ELEVATIONS ARE BASED ON WATER LEVEL DATA COLLECTED SECOND QUARTER 2005.
 2. THE DISTANCED BETWEEN BORING LOCATIONS WERE ESTIMATED BASED ON STRAIGHT-LINE TRANSECTS.



SCALE: IN FEET

GRAPHIC SCALE

10X VERTICAL EXAGGERATION



ANDREWS
ENGINEERING, INC.



3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

MPN

SRH

DESIGNED BY:

SRH

APPROVED BY:

SRH

2007 GMZ VERTICAL BOUNDARY MAP

PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

DATE:

APRIL 2007


PROJECT ID:

90-114

SHEET NUMBER:

FIG. 9

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\UPPER ZONE GMZ EXTENT.dwg Tab: MAX EXTENT User: wulewicz Plotted: Apr 20, 2012 - 2:15 PM



EXPLANATION

- SOUTHERN UNIT MONITORING WELL
- NORTHERN UNIT GMZ MONITORING WELL
- NORTH EXPANSION UNIT MONITORING WELL

MAXIMUM GMZ EXTENT LIMIT

NOTES:

- SGX = SURFACE WATER COLLECTION POINT
- COMPREHENSIVE MAP FOR THE OUTLINE OF GMZ BASED ON THE INDIVIDUAL PARAMETER MAPS (FURTHEST EXTENT)
- HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
- FACILITY FEATURES SHOWN REPRESENT CONDITIONS IN 2012.

ANDREWS
ENGINEERING, INC.

3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO




2012 UPPER ZONE GMZ BOUNDARY MAP

PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

DATE: APRIL 2012
PROJECT ID: 90-114
SHEET NUMBER:

FIG. 10

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\GMZ_LOWER_ZONE.dwg Tab: Max. Extent User: wulewicz Plotted: Apr 20, 2012 - 2:17 PM



2012 LOWER ZONE GMZ BOUNDARY MAP
PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

DATE:
APRIL 2012
PROJECT ID:
90-114
SHEET NUMBER:

FIG. 11


ANDREWS
ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO




© 2012 Andrews Engineering, Inc.

APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: WCU


File: J:\1990\90-114 (Winnebago)\DWG\gmz-bedrock zone xsec.dwg Tab: fig-12 User: wulewicz Plotted: Apr 11, 2012 - 9:55 AM



NOTE:
1. THE DISTANCED BETWEEN BORING LOCATIONS WERE
ESTIMATED BASED ON STRAIGHT-LINE TRANSECTS.



SCALE: IN FEET
GRAPHIC SCALE
10X VERTICAL EXAGGERATION



2012 GMZ VERTICAL BOUNDARY MAP

PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

DATE:
APRIL 2012
PROJECT ID:
90-114
SHEET NUMBER:

FIG. 12

ANDREWS
ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO



APPENDIX A

Application Forms



Illinois
Environmental
Protection Agency

Bureau of Land
1021 North Grand Avenue East
Box 19276
Springfield, IL 62794-9276

Certification of Authenticity of Official Forms

This form must accompany any application submitted to the Illinois EPA Bureau of Land, Division of Land Pollution Control, Permit Section on forms other than the official copy printed and provided by the Illinois EPA. The only allowed changes to the form are in spacing, fonts, and the addition of the information provided. Any additions must be underlined. The forms would not be considered identical if there is any change to, addition or deletion of words on the form or to the language of the form.

The same individuals that sign the application form it accompanies must sign the following certification.

I hereby certify under penalty of law that I have personally examined, and am familiar with the application form or forms and all included supplemental information submitted to the Illinois EPA herewith, and that the official Illinois Environmental Protection Agency application form or forms used herein is or are identical in all respects to the official form or forms provided by the Illinois EPA Bureau of Land Permit Section, and has not or have not been altered, amended, or otherwise modified in any way. I further certify under penalty of law that any attached or included electronic data version of the application form or forms complies with the official Illinois EPA's Electronic version thereof, and is or are identical in all respects to the official electronically downloadable form or forms provided by the Illinois EPA Bureau of Land Permit Section, and has not or have not been altered, amended or otherwise modified in any way.

By: [Signature]
Owner Signature

4-12-2012
(date)

Engineering Mgr
Title

By: [Signature]
Operator Signature

4-12-2012
(date)


Engineering Mgr
Title

[Signature]
Engineer Signature
(if necessary)

5/1/12
(date)

Subscribed and Sworn to Before Me,
a Notary Public in and for the
above-mentioned County and State.

[Signature]
Notary Public



My Commission Expires: 8-12-12

[Notary Seal]



Bureau of Land • 1021 N. Grand Avenue E. • Box 19276 • Springfield • Illinois • 62794-9276

General Application for Permit (LPC - PA1)

This form must be used for any application for permit, except for landscape waste composting or hazardous waste management facilities regulated in accordance with RCRA, Subtitle C from the Bureau of Land. One original, and two copies, or three if applicable, of all permit application forms must be submitted. Attach the original and appropriate number of copies of any necessary plans, specifications, reports, etc. to fully support and describe the activities and modifications being proposed. Attach sufficient information to demonstrate the compliance with all regulatory requirements. Incomplete applications will be rejected.

Note: Permit applications which are hand-delivered to the Bureau of Land, Permit Section must be delivered to the above address between 8:30 am and 5:00 pm, Monday through Friday (excluding State holidays).

NOTE: Please complete this form online, save a copy locally, print and submit it to the Permit Section #33, at the above address.

I. Site Identification:

Site Name: Winnebago Landfill IEPA ID Number: 2018080001
Street Address: 8403 Lindenwood Road P.O. Box: _____
City: Rockford State: IL Zip Code: 61109 County: Winnebago
Existing DE/OP Permit Numbers (if applicable): 1991-138-LF

2. Owner/Operator Identification:

Owner

Name: Winnebago Landfill Company, LLC
Street Address: 5450 Wansford Way, Suite 201B
PO Box: _____
City: Rockford State: IL
Zip Code: 61109 Phone: _____
Contact: Tom Hilbert
Email Address: thilbert@rresvcs.com

Operator

Name: Winnebago Reclamation Service, Inc.
Street Address: 5450 Wansford Way, Suite 201B
PO Box: _____
City: Rockford State: IL
Zip Code: 61109 Phone: _____
Contact: Tom Hilbert
Email Address: thilbert@rresvcs.com

TYPE OF SUBMISSION/REVIEW PERIOD:

New Landfill/180 days (35 IAC Part 813)
Landfill Expansion/180 days (35 IAC Part 813)
Sig. Mod. to Operate/90 days (35 IAC Part 813)
Other Sig. Mod./90 days (35 IAC Part 813)
Renewal of Landfill/90 days (35 IAC Part 813)
Developmental/90 days (35 IAC Part 807)
Operating/45 days (35 IAC Part 807)
Supplemental/90 days (35 IAC Part 807)
Permit Transfer/90 days (35 IAC Part 807)
Renewal of Experimental Permit (35 IAC Part 807)

TYPE OF FACILITY:

☐ Landfill
☐ Land Treatment
☐ Transfer Station
☒ Treatment Facility
☐ Storage
☐ Incinerator
☐ Composting
☐ Recycling/Reclamation
☐ Other (Specify) _____

TYPE OF WASTE:

☒ General Municipal Refuse
☐ Hazardous
☒ Special (Non-Hazardous)
☐ Chemical Only (exec. putrescible)
☐ Inert Only (exec. chem. & putrescible)
☐ Used Oil
☐ Potentially Infectious Medical Waste
☐ Landscape/Yard Waste
☐ Other (Specify) _____

3. Description of this Permit Request:

Five year evaluation of the Groundwater Management Zone in accordance with Permit Condition VIII.23 (Mod.53).

4. Completeness Requirements

The following items must be checked Yes, No or N/A. Each item will be reviewed for completeness by the log clerk. Blank items will result in rejection of the application. Please refer to the instructions for further guidance.

1. Have all required public notice letters been mailed in accordance with the LPC-PA16 instructions? ☒ Yes ☐ No ☐ N/A

(If so, provide a list of those recipients of the required public notice letters for Illinois EPA retention. Such retention shall not imply any Illinois EPA review and/or confirmation of the list.)

Public Notice Recipients

| | |
|---|-------------------------------------|
| Name: <u>Dave Syverson</u> | Title: <u>Senator - District 34</u> |
| Street Address: <u>200 South Wyman Street, Suite 302</u> | P.O. Box: _____ |
| City: <u>Rockford</u> State: <u>IL</u> Zip Code: <u>61101</u> | Phone: _____ |

| | |
|---|--|
| Name: <u>Charles Jefferson</u> | Title: <u>Representative - District 67</u> |
| Street Address: <u>200 South Wyman Street, Suite 304</u> | P.O. Box: _____ |
| City: <u>Rockford</u> State: <u>IL</u> Zip Code: <u>61101</u> | Phone: _____ |

| | |
|---|--------------------------------|
| Name: <u>Joseph Bruscato</u> | Title: <u>State's Attorney</u> |
| Street Address: <u>400 West State Street</u> | P.O. Box: _____ |
| City: <u>Rockford</u> State: <u>IL</u> Zip Code: <u>61101</u> | Phone: _____ |

| | |
|---|-------------------------------|
| Name: <u>Scott Christiansen</u> | Title: <u>County Chairman</u> |
| Street Address: <u>404 Elm Street, Room 504</u> | P.O. Box: _____ |
| City: <u>Rockford</u> State: <u>IL</u> Zip Code: <u>61101</u> | Phone: _____ |

| | |
|---|-----------------------------|
| Name: <u>Village of New Milford</u> | Title: <u>Village Clerk</u> |
| Street Address: <u>6771 11th Street</u> | P.O. Box: _____ |
| City: <u>Rockford</u> State: <u>IL</u> Zip Code: <u>61109</u> | Phone: _____ |

| | |
|---|-----------------------------|
| Name: <u>Village of Davis Junction</u> | Title: <u>Village Clerk</u> |
| Street Address: <u>106 North Elm Street</u> | P.O. Box: <u>207</u> |
| City: <u>Davis Junction</u> State: <u>IL</u> Zip Code: <u>61020</u> | Phone: _____ |

| | |
|---|-----------------|
| Name: <u>Cherry Valley Township</u> | Title: _____ |
| Street Address: <u>4875 Blackhawk Road</u> | P.O. Box: _____ |
| City: <u>Rockford</u> State: <u>IL</u> Zip Code: <u>61109</u> | Phone: _____ |

2. a. Is the Siting Certification Form (LPC-PA8) completed and enclosed?

☐ Yes ☒ No ☐ N/A

- b. Is siting approval currently under litigation?

☐ Yes ☒ No ☐ N/A

3. a. Is a closure, and if necessary a post-closure plan covering these activities being submitted, or ☐ Yes ☒ No ☐ N/A
b. has one already been approved? If yes, provide the permit number: 1991-138
4. a. For waste disposal sites, only: Has any employee, owner, operator, officer or director of the owner or operator had a prior conduct certification denied, canceled or revoked? ☐ Yes ☒ No ☐ N/A
b. Have you included a demonstration of how you comply or intend to comply with 35 Ill. Adm. Code 745? ☐ Yes ☐ No ☒ N/A
5. a. Is land ownership held in beneficial trust? ☐ Yes ☒ No ☐ N/A
b. If yes, is a beneficial trust certification form (LPC-PA9) completed and enclosed? ☐ Yes ☐ No ☒ N/A
6. a. Does the application contain information or proposals regarding the hydrogeology; groundwater monitoring, modeling or classification; a groundwater impact assessment; or vadose zone monitoring for which you are requesting approval? ☒ Yes ☐ No ☐ N/A
b. If yes, have you submitted a third copy of the application (4 total) and supporting documents? ☒ Yes ☐ No ☐ N/A

5. Signatures:

Original signatures are required. Signature stamps or applications transmitted electronically or by FAX are not acceptable.

All applications shall be signed by the person designated below as a duly authorized representative of the owner an/or operator.

Corporation - By a principal executive officer of the level of vice-president or above.

Partnership or Sole Proprietorship - By a general partner or the proprietor, respectively.

Government - By either a principal executive officer or a ranking elected official.

A person is a duly authorized representative of the owner and operator only if:

1. They meet the criteria above or the authorization has been granted in writing by a person described above; and
2. Is submitted with this application (a copy of a previously submitted authorization can be used).

I hereby affirm that all information contained in this application is true and accurate to the best of my knowledge and belief. I do herein swear that I am a duly authorized representative of the owner/operator and I am authorized to sign this permit application form.

Any person who knowingly makes a false, fictitious, or fraudulent material statement, orally or in writing, to the Illinois EPA commits a Class 4 felony. A second or subsequent offense after conviction is a Class 3 felony. (415 ILCS 5/44(h))

[Signature]
Owner Signature:
Thomas Hilbert
Printed Name:

4-12-2012

Date:

Engineer Msr

Title:

Notary: Subscribed and Sworn before me this 12th day of April 2012

My commission expires on: 8-12-12

[Signature]
Signature & Stamp/Seal of Notary Public

OFFICIAL SEAL
NICOLE M ROTE
NOTARY PUBLIC, STATE OF ILLINOIS
MY COMMISSION EXPIRES 08/12/12

[Signature]
Operator Signature:
Thomas Hilbert
Printed Name:

4-12-2012

Date:

Engineer Msr

Title:

Notary: Subscribed and Sworn before me this 12th day of April 2012

My commission expires on: 8-12-12

[Signature]
Signature & Stamp/Seal of Notary Public

OFFICIAL SEAL
NICOLE M ROTE
NOTARY PUBLIC, STATE OF ILLINOIS
MY COMMISSION EXPIRES 08/12/12

Engineer's Name: Douglas W. Mantel
Company: Andrews Engineering, Inc.
Street Address: 3300 Ginger Creek Drive
City: Springfield State: IL
Email Address: dwmantel@andrews-eng.com

Engineer's Title: Project Engineering
Registration Number: 062-054530
PO Box: _____
Zip Code: 62711
License Expiration Date: 5/1/12

Phone: 217-782-2334
OFFICIAL SEAL
DOUGLAS W. MANTEL
REGISTERED
PROFESSIONAL
ENGINEER
OF
ILLINOIS

Signature: [Signature]

Date: 5/1/12


Professional Engineer's Seal:

APPENDIX B

Quarterly Potentiometric Surface Maps

File: J:\1990\90-114 (Winnebago)\GWS\Annual GW Flow maps\2007\maps\1007.dwg User: wlewiecz Plotted: Apr 20, 2012 - 2:19 PM


PROPERTY EXTENDS TO BAXTER ROAD



| SOUTH UNIT WELLS | | | | NORTH UNIT WELLS | | | | GMZ WELLS | | | |
|------------------|------|-------|------|------------------|------|------|------|-----------|------|--|--|
| R05S | R24D | R03S | G33D | R03S | G33D | R03S | G16M | G34S | G40S | | |
| R11S* | R25D | G03M | G34D | G03M | G34D | G03M | G16D | G34D | G41S | | |
| G11D* | G26S | G09M* | G35D | G09M | G35D | G09M | G17S | G35S | G41M | | |
| G13S* | G26D | G09D* | G36S | G09D | G36S | G09D | G18S | G35D | G41D | | |
| G13D* | R27D | G13S* | G37S | G13S | G37S | G13S | G18D | G36S | R42S | | |
| R22S* | R28D | G13D* | G38S | G13D | G38S | G13D | G119 | G37S | G130 | | |
| G22D* | G29S | G15S | G39S | G14D | G20D | G14D | G20D | G37D | SG1 | | |
| G23D | G29D | G16M | G40S | G15S | G33S | G15S | G33S | G38S | SG3 | | |
| | G49D | G17S | G41S | | G33D | | G33D | G39S | SG4 | | |
| | | G18S | G41M | | | | | | | | |
| | | G18D | G41D | | | | | | | | |
| | | G20D* | R42S | | | | | | | | |

* REPRESENTS UPGRADIENT OR BACKGROUND WELL


| LEGEND | |
|--------|--|
| ◆ | SGX STREAM GAUGE LOCATION |
| ■ | GP-XX GAS MONITORING PROBE |
| ⊞ | NORTH UNIT GROUND WATER MONITOR WELL OR GMZ WELL |
| ⊙ | SOUTH UNIT GROUND WATER MONITOR WELL |
| --- | CURRENTLY PERMITTED FILL BOUNDARY |
| ⊗ | BENCHMARK |



- NOTES:
- FACILITY STRUCTURES SHOWN REPRESENT CONDITIONS IN 2007.

| REVISIONS | | BY |
|-----------|------|-------------|
| NO. | DATE | DESCRIPTION |
| | | |
| | | |
| | | |

ANDREWS ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL - Naperville, IL - Warrenville, MO

APPROVED BY: 


DESIGNED BY: SRH
DRAWN BY: LJE

| | |
|---|-----------------------|
| POTENTIOMETRIC SURFACE MAP - 1ST QUARTER 2007 | |
| PLANS PREPARED FOR WINNEBAGO RECLAMATION SERVICE, INC. ROCKFORD, WINNEBAGO COUNTY, ILLINOIS | |
| DATE: MARCH 2007 | PROJECT ID: 90-114 |
| SHEET NUMBER: B-1 | |

© 2007 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\GWS\Annual GW Flow maps\2007\maps\2007.dwg User: wlewicz Plotted: Apr 20, 2012 - 2:20 PM


PROPERTY EXTENDS TO BAXTER ROAD



| SOUTH UNIT WELLS | | NORTH UNIT WELLS | | GMZ WELLS | | | |
|------------------|------|------------------|------|-----------|------|------|------|
| R05S | R24D | R03S | G33D | R03S | G16M | G34S | G40S |
| R11S* | R25D | G03M | G34D | G03M | G16D | G34D | G41S |
| G11D* | G26S | G09M* | G35D | G09M | G17S | G35S | G41M |
| G13S* | G26D | G09D* | G36S | G09D | G18S | G35D | G41D |
| G13D* | R27D | G13S* | G37S | G13S | G18D | G36S | R42S |
| R22S* | R28D | G13D* | G38S | G13D | G119 | G37S | G130 |
| G22D* | G29S | G15S | G39S | G14D | G20D | G37D | SG1 |
| G23D | G29D | G16M | G40S | G15S | G33S | G38S | SG3 |
| | G49D | G17S | G41S | | G33D | G39S | SG4 |
| | | G18S | G41M | | | | |
| | | G18D | G41D | | | | |
| | | G20D* | R42S | | | | |

* REPRESENTS UPGRADIENT OR BACKGROUND WELL

| LEGEND | |
|--------|--|
| ◆ | SGX STREAM GAUGE LOCATION |
| ■ | GP-XX GAS MONITORING PROBE |
| ⊞ | NORTH UNIT GROUND WATER MONITOR WELL OR GMZ WELL |
| ● | SOUTH UNIT GROUND WATER MONITOR WELL |
| --- | CURRENTLY PERMITTED FILL BOUNDARY |
| ⊗ | BENCHMARK |



| | | | |
|-----------|------|-------------|--|
| REVISIONS | | BY | |
| NO. | DATE | DESCRIPTION | |
| | | | |
| | | | |
| | | | |
| | | | |

ANDREWS ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334
Portland, IL - Naperville, IL - Indianapolis, IN - Warrenton, MO

APPROVED BY: SRH
DESIGNED BY: SRH
DRAWN BY: LJE

POTENTIOMETRIC SURFACE MAP - 2ND QUARTER 2007

PLANS PREPARED FOR
WINNEBAGO RECLAMATION SERVICE, INC.
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS


DATE:
JULY 2007

PROJECT ID:
90-114

SHEET NUMBER:
B-2

© 2007 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\DWC\Annual GW Flow maps\2010-038 RESPONSE REV PMAPS\2007.dwg Layout: 3007 User: wulwicz Plotted: Apr 20, 2012 - 2:21 PM



| REVIEWS | | DESCRIPTION | |
|---------|------|-------------|--|
| NO. | DATE | BY | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

ANDREWS ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

POTENTIOMETRIC SURFACE MAP
3RD QUARTER 2007


PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

| | |
|---------------|----------------|
| DATE: | SEPTEMBER 2010 |
| PROJECT ID: | 90-114 |
| SHEET NUMBER: | B-3 |

APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: MPN

© 2007 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\GWS\Annual GW Flow maps\2010-038 RESPONSE\REV PMAPS\4007.dwg Layout: 4007 User: wulawitz Plotted: Apr 20, 2012 - 2:22 PM



| REVISIONS | | BY |
|-----------|------|-------------|
| NO. | DATE | DESCRIPTION |
| | | |
| | | |
| | | |
| | | |
| | | |

| |
|--|
| |
| |
| |
| |
| |
| |


**ANDREWS**
ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: MPN

| | |
|--|--|
| POTENTIOMETRIC SURFACE MAP 4TH QUARTER 2007 | PLANS PREPARED FOR WINNEBAGO LANDFILL ROCKFORD, WINNEBAGO COUNTY, ILLINOIS |
|--|--|

| |
|----------------------|
| DATE: SEPTEMBER 2010 |
| PROJECT ID: 90-114 |
| SHEET NUMBER: |

File: J:\1990\90-114 (Winnebago)\GWS\Annual GW Flow maps\2010-038 RESPONSE\REV PMAPS\008.dwg Layout: Layout1 User: wulawicz Plotted: Apr 20, 2012 - 2:23 PM



| REVISIONS | | DATE | |
|-----------|-------------|------|------|
| NO. | DESCRIPTION | NO. | DATE |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

ANDREWS ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO


| APPROVED BY: | DESIGNED BY: | DRAWN BY: | MPN |
|--------------|--------------|-----------|-----|
| JLR | JLR | JLR | MPN |

POTENTIOMETRIC SURFACE MAP
1ST QUARTER 2008


PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

| |
|-----------------------------|
| DATE: SEPTEMBER 2010 |
| PROJECT ID: 90-114 |
| SHEET NUMBER: B-5 |

© 2010 Andrews Engineering, Inc.

© 2010 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\UWS\Annual GW Flow maps\2010-038 RESPONSE\REV PMAPS\3008_REV.dwg Layout: Layout1 User: wulawicz Plotted: Apr 20, 2012 - 2:24 PM




| REVISIONS | |
|-----------|------|
| NO. | DATE |
| | |
| | |
| | |
| | |
| | |

| POTENTIOMETRIC SURFACE MAP 3RD QUARTER 2008 | |
|--|--|
| PLANS PREPARED FOR WINNEBAGO LANDFILL ROCKFORD, WINNEBAGO COUNTY, ILLINOIS | |


| DATE: SEPTEMBER 2010 | |
|----------------------|--|
| PROJECT ID: 90-114 | |
| SHEET NUMBER: | |
| B-7 | |

ANDREWS ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: MPN

© 2010 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\UWS Annual GW Flow maps\2010-038 RESPONSE\REV PWAPS\009_REV.dwg Layout: Layout1 User: wulawicz Plotted: Apr 20, 2012 - 2:28 PM



| REVISIONS | |
|-----------|------|
| NO. | DATE |
| | |
| | |
| | |
| | |
| | |

POTENTIOMETRIC SURFACE MAP
1ST QUARTER 2009

PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

DATE: SEPTEMBER 2010


PROJECT ID: 90-114


SHEET NUMBER:


B-9

ANDREWS ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO


APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: MPN

© 2010 Andrews Engineering, Inc.

© 2010 Andrews Engineering, Inc.

© 2010 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\UWS\Annual GW Flow maps\2010\PMAPS\REV PMAPS\1010 pmop_REV.dwg Layout: Layout1 User: wulewicz Plotted: Apr 20, 2012 - 2:33 PM



| REVISIONS | | BY | |
|-----------|------|-------------|--|
| NO. | DATE | DESCRIPTION | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

ANDREWS ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO


| APPROVED BY: | DESIGNED BY: | DRAWN BY: | MPN |
|--------------|--------------|-----------|-----|
| JLR | JLR | JLR | MPN |

POTENTIOMETRIC SURFACE MAP
1ST QUARTER 2010

PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

| DATE: | PROJECT ID: | SHEET NUMBER: |
|-----------|-------------|---------------|
| JUNE 2010 | 90-114 | B-13 |

File: J:\1990\90-114 (Winnebago)\UWS\Annual GW Flow maps\2010\PMAPS\REV PMAPS\2010 pmap_REV.dwg Layout: Layout1 User: wulawicz Plotted: Apr 20, 2012 - 2:33 PM



- NOTES:
1. CONTOUR INTERVAL = 5 FEET
 2. SAMPLE DATE = 4/14/2010-4/19/2010.
 3. (*) NOT USED IN THE COMPILATION OF THE POTENTIOMETRIC SURFACE.
 4. GROUNDWATER ELEVATIONS FOR B-10, B-10A, AND G-108 ARE AVERAGE GROUNDWATER ELEVATIONS FROM FIRST QUARTER 2008 TO THIRD QUARTER 2010.
 5. FACILITY STRUCTURES SHOWN REPRESENT CONDITIONS IN 2010.

| REVISIONS | | BY | |
|-----------|------|-------------|--|
| NO. | DATE | DESCRIPTION | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

ANDREWS
ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334
Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: MPN


POTENTIOMETRIC SURFACE MAP
2ND QUARTER 2010

PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

DATE: JUNE 2010
PROJECT ID: 90-114
SHEET NUMBER:

B-14

File: J:\1990\90-114 (Winnebago)\GWS\Annual GW Flow maps\2010\PMAPS\REV\PMAPS\3010 pmap_REV.dwg Layout: Layout1 User: wulawicz Plotted: Apr 20, 2012 - 2:34 PM



| REVISIONS | | BY | |
|-----------|------|-------------|--|
| NO. | DATE | DESCRIPTION | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |


ANDREWS
ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: MPN

| | |
|--|--|
| POTENTIOMETRIC SURFACE MAP 3RD QUARTER 2010 | PLANS PREPARED FOR WINNEBAGO LANDFILL ROCKFORD, WINNEBAGO COUNTY, ILLINOIS |
| DATE: SEPTEMBER 2010 | |
| PROJECT ID: 90-114 | |
| SHEET NUMBER: | |
| B-15 | |

© 2010 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\GWS\Annual GW Flow maps\2010\PMAPS\REV PMAPS\4010 pmmap_REV.dwg Layout: Layout1 User: wulawicz Plotted: Apr 20, 2012 - 2:34 PM



- NOTES:
1. CONTOUR INTERVAL = 5 FEET
 2. SAMPLE DATE = 10/8/2010.
 3. (*) NOT USED IN THE COMPILATION OF THE POTENTIOMETRIC SURFACE.
 4. THE NORTHERN AND SOUTHERN UNITS OF WINNEBAGO LANDFILL ARE OPERATED AND MONITORED IN ACCORDANCE WITH ILLINOIS EPA PERMIT NO. 1991-138-LF. THE NORTH EXPANSION UNIT OF WINNEBAGO LANDFILL IS OPERATED AND MONITORED IN ACCORDANCE WITH ILLINOIS EPA PERMIT NO. 2006-221-LF. THE DEPOSITS MONITORED BY ALL THREE WASTE UNITS ARE HYDRAULICALLY CONNECTED; THEREFORE, A SINGLE MAP DEPICTING THE GROUNDWATER FLOW REGIME HAS BEEN COMPILED.
 5. IN THE CASE OF NESTED WELLS THE GROUNDWATER ELEVATIONS FROM SHALLOW WELLS WERE USED IN THE COMPILATION OF POTENTIOMETRIC CONTOURS.
 6. POTENTIOMETRIC CONTOURS AS SHOWN ASSUME CONTINUOUS GEOLOGICAL CONDITIONS AND DO NOT ACCOUNT FOR LINER AND SIDEWALLS EMPLACED FOR DEVELOPMENT OF THE NORTH EXPANSION UNIT.
 7. FACILITY STRUCTURES SHOWN REPRESENT CONDITIONS IN 2010.

| REVISIONS | | BY | |
|-----------|------|-------------|--|
| NO. | DATE | DESCRIPTION | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

ANDREWS
ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

APPROVED BY: JLR

DESIGNED BY: JLR

DRAWN BY: MPN

POTENTIOMETRIC SURFACE MAP
4TH QUARTER 2010


PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

| | |
|---------------|---------------|
| DATE: | DECEMBER 2010 |
| PROJECT ID: | 90-114 |
| SHEET NUMBER: | |


B-16

© 2010 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\GWS\Annual GW Flow maps\2011 PMAPS\REV PMAPS\q11.dwg Layout: Layout1 User: wulawicz Plotted: Apr 20, 2012 - 2:37 PM




File: J:\1990\90-114 (Winnebago)\UGS\Annual GW Flow maps\2011 PMAPS\2a11.dwg Layout: Layout1 User: wilewicz Plotted: Apr 20, 2012 - 2:37 PM




| LEGEND | |
|--------|---|
| | STREAM GAUGE LOCATION |
| | NORTHERN UNIT GROUNDWATER MONITORING WELL OR GMZ WELL |
| | SOUTHERN UNIT GROUNDWATER MONITORING WELL |
| | PROPERTY BOUNDARY |
| | CURRENTLY PERMITTED FILL BOUNDARY |
| | GRADIENT LINE |
| | PIEZOMETER |
| | NORTH EXPANSION UNIT MONITORING WELL |
| | TEMPORARY GMZ ASSESSMENT WELL |
| | WESTERN EXPANSION UNIT MONITORING WELL |

- NOTES:
1. CONTOUR INTERVAL = 5 FEET
 2. SAMPLE DATES = 4/6/2011 - 4/8/2011.
 3. (*) NOT USED IN THE COMPILATION OF THE POTENTIOMETRIC SURFACE.
 4. THE NORTHERN AND SOUTHERN UNITS OF WINNEBAGO LANDFILL ARE OPERATED AND MONITORED IN ACCORDANCE WITH ILLINOIS EPA PERMIT NO. 1991-138-LF. THE NORTH EXPANSION UNIT OF WINNEBAGO LANDFILL IS OPERATED AND MONITORED IN ACCORDANCE WITH ILLINOIS EPA PERMIT NO. 2006-221-LF. THE DEPOSITS MONITORED BY ALL THREE WASTE UNITS ARE HYDRAULICALLY CONNECTED; THEREFORE, A SINGLE MAP DEPICTING THE GROUNDWATER FLOW REGIME HAS BEEN COMPILED.
 5. IN THE CASE OF NESTED WELLS THE GROUNDWATER ELEVATIONS FROM SHALLOW WELLS WERE USED IN THE COMPILATION OF POTENTIOMETRIC CONTOURS.
 6. POTENTIOMETRIC CONTOURS AS SHOWN ASSUME CONTINUOUS GEOLOGICAL CONDITIONS AND DO NOT ACCOUNT FOR LINER AND SIDEWALLS EMPLACED FOR DEVELOPMENT OF THE NORTH EXPANSION UNIT.
 7. FACILITY STRUCTURES SHOWN REPRESENT CONDITIONS IN 2011.



| REVISIONS | | | | |
|-----------|------|-------------|----|--|
| NO. | DATE | DESCRIPTION | BY | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |




ANDREWS
ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: MPN


POTENTIOMETRIC SURFACE MAP
2ND QUARTER 2011

PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

DATE: JULY 2011
PROJECT ID: 90-114
SHEET NUMBER:
B-18



J:\1990\90-114 (Winnebago)\DWG\Annual GW Flow maps\2011 FMAPS\4011.dwg Tab: Layout1 Last Saved: April 20, 2012, by William Ulewicz Plotted: Friday, April 20, 2012 2:39:12 PM



APPENDIX C

Acme Solvent Site Potentiometric Surface Maps

Figure 1: Acme Solvents Site Water Table Maps










Figure 1: Acme Solvents Site Water Table Maps (cont.)






APPENDIX D

Upper Zone Trend Graphs


Winnebago Landfill
Upper Zone

Total Sulfate




Winnebago Landfill
Upper Zone

Dissolved Sulfate




Winnebago Landfill
Upper Zone

Specific Conductance




Winnebago Landfill
Upper Zone

Total Selenium




Winnebago Landfill
Upper Zone

Polychlorinated Biphenyls




Winnebago Landfill
Upper Zone

pH




Winnebago Landfill
Upper Zone

Dissolved Manganese




Winnebago Landfill
Upper Zone

Total Magnesium




Winnebago Landfill
Upper Zone

Dissolved Magnesium




Winnebago Landfill
Upper Zone

Dissolved Lead




Winnebago Landfill
Upper Zone

Dissolved Iron




Winnebago Landfill
Upper Zone

Total Cobalt




Winnebago Landfill
Upper Zone

Chemical Oxygen Demand




Winnebago Landfill
Upper Zone

Carbon Disulfide




Winnebago Landfill
Upper Zone

Biochemical Oxygen Demand



Winnebago Landfill
Upper Zone


Total Alkalinity



Winnebago Landfill

Upper Zone

Acrylonitrile



Winnebago Landfill


Upper Zone

Acetone



Winnebago Landfill
Upper Zone


Tetrahydrofuran



Winnebago Landfill


Upper Zone

Total Sodium




Winnebago Landfill
Upper Zone

Total Potassium




Total Nitrate




Upper Zone

Total Fluoride



The graph displays the concentration of 18 pesticides (G119, G130, G15S, G17S, G18S, G33S, G34S, G35S, G37S, G40S, G41S, G50S, G51S, G52S, G54S, R03S, R42S, and AGQS) in mg/L over time from 1997 to 2011. The y-axis ranges from 0 to 300 mg/L. The x-axis shows sampling events: 1stQtr97, 3rdQtr97, 1stQtr98, 3rdQtr98, 1stQtr99, 3rdQtr99, 1stQtr00, 3rdQtr00, 1stQtr01, 3rdQtr01, 1stQtr02, 3rdQtr02, 1stQtr03, 2ndQtr03, 4thQtr03, 2ndQtr04, 3rdQtr04, 4thQtr04, 2ndQtr05, 4thQtr05, 2ndQtr06, 4thQtr06, 2ndQtr07, 4thQtr07, 2ndQtr08, 4thQtr08, 2ndQtr09, 4thQtr09, 2ndQtr10, 4thQtr10, 2ndQtr11, 4thQtr11. A thick black line at approximately 275 mg/L represents the AGQS limit. Most pesticides remain near 0 mg/L, with a small peak for G52S in 3rdQtr00.


Ethylbenzene



Winnebago Landfill

Upper Zone


Total Chloride



Winnebago Landfill


Upper Zone

Total Boron




Winnebago Landfill
Upper Zone

Dissolved Boron




Total Barium




Upper Zone

Total Barium




Winnebago Landfill
Upper Zone

Total Arsenic




Total Arsenic




Winnebago Landfill
Upper Zone

Dissolved Arsenic




Total Ammonia




Winnebago Landfill
Upper Zone

Dissolved Ammonia




Winnebago Landfill
Upper Zone

1,2,4-Trichlorobenzene



Winnebago Landfill
Upper Zone

1,2,3-Trichlorobenzene




APPENDIX E

Lower Zone Trend Graphs

Lower Zone


Tetrahydrofuran



Winnebago Landfill


Lower Zone

Total Sodium




Winnebago Landfill
Lower Zone

Total Potassium




Winnebago Landfill
Lower Zone

Total Nitrate




Winnebago Landfill
Lower Zone

Dissolved Nitrate



Total Fluoride




Lower Zone

[illegible]


Winnebago Landfill

Lower Zone


Ethylbenzene




Total Chloride




Dissolved Chloride



Total Boron




Dissolved Boron




Winnebago Landfill
Lower Zone

Total Barium




Winnebago Landfill
Lower Zone

Total Arsenic




Winnebago Landfill
Lower Zone

Dissolved Arsenic




Total Ammonia




Winnebago Landfill
Lower Zone

Dissolved Ammonia




Winnebago Landfill
Lower Zone

Dissolved Ammonia




Winnebago Landfill
Lower Zone

1,2,4-Trichlorobenzene



Winnebago Landfill
Lower Zone

1,2,3-Trichlorobenzene




APPENDIX F

Bedrock Zone Trend Graphs


Winnebago Landfill
Bedrock Zone

Tetrahydrofuran




Winnebago Landfill
Bedrock Zone

Total Sodium




Total Potassium




Winnebago Landfill
Bedrock Zone

Total Potassium




Winnebago Landfill
Bedrock Zone

Total Nitrate




Winnebago Landfill
Bedrock Zone

Dissolved Nitrate




Winnebago Landfill
Bedrock Zone

Total Fluoride




Winnebago Landfill
Bedrock Zone

Ethylbenzene




Winnebago Landfill
Bedrock Zone

Total Chloride




Winnebago Landfill
Bedrock Zone

Dissolved Chloride




Winnebago Landfill
Bedrock Zone

Total Boron




Winnebago Landfill
Bedrock Zone


Total Boron



Dissolved Boron




Dissolved Boron




Winnebago Landfill
Bedrock Zone


Total Barium



Total Barium




Total Arsenic




Winnebago Landfill
Bedrock Zone

Dissolved Arsenic




Winnebago Landfill
Bedrock Zone

Total Ammonia




Winnebago Landfill
Bedrock Zone

Dissolved Ammonia




Winnebago Landfill
Bedrock Zone

1,4-Dichlorobenzene



Winnebago Landfill
Bedrock Zone


1,2,3-Trichlorobenzene



APPENDIX G

Upper Zone Concentration Exceedence Maps

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\UPPER ZONE GMZ EXTENT.dwg Tab: FIG 1 User: wulewicz Plotted: Apr 11, 2012 - 10:23 AM



ANDREWS
ENGINEERING, INC.




3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

1ST QUARTER 2012
AMMONIA EXCEEDENCES – UPPER ZONE
PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

DATE:
APRIL 2012
PROJECT ID:
90-114
SHEET NUMBER:


G-1



1. NE = NO EXCEEDENCE
2. SGX = SURFACE WATER COLLECTION POINT
4. HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
5. G37S INACCESSIBLE AT TIME OF SAMPLING FIRST QUARTER 2012.
6. ESTIMATED EXTENT OF EXCEEDENCE IS DASHED WHERE INFERRED DUE TO DRY CONDITIONS AT TIME OF SAMPLING.
7. AGQS FOR DISSOLVED/TOTAL ARSENIC = $2/10 \mu\text{g/L}$.

© 2012 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\UPPER ZONE GMZ EXTENT.dwg Tab: FIG 3 User: wulewicz Plotted: Apr 11, 2012 - 10:24 AM



| EXPLANATION | |
|-------------------------------------|---|
| 2012 CONCENTRATIONS OF BORON (µg/L) | |
| 10/20 | 2012 CONCENTRATION DISSOLVED/TOTAL |
| 10/20 | 2007 CONCENTRATION DISSOLVED/TOTAL |
| 15/16 | 2004 CONCENTRATION DISSOLVED/TOTAL |
| ◆ | NORTH EXPANSION UNIT MONITORING WELL |
| ● | SOUTHERN UNIT MONITORING WELL |
| ⊞ | NORTHERN UNIT GMZ MONITORING WELL |
| — | 2012 ESTIMATED EXTENT OF BORON EXCEEDENCE |
| — | 2007 ESTIMATED EXTENT OF BORON EXCEEDENCE |
| — | 2004 ESTIMATED EXTENT OF BORON EXCEEDENCE |

- NOTES:
- NE = NO EXCEEDENCE
 - SGX = SURFACE WATER COLLECTION POINT
 -
 - HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
 - G37S INACCESSIBLE AT TIME OF SAMPLING FIRST QUARTER 2012.
 - ESTIMATED EXTENT OF EXCEEDENCE IS DASHED WHERE INFERRED DUE TO DRY CONDITIONS AT TIME OF SAMPLING.
 - AGQS FOR DISSOLVED/TOTAL BORON = 98/200 µg/L.

ANDREWS
ENGINEERING, INC.

3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO



1ST QUARTER 2012
BORON EXCEEDENCES – UPPER ZONE
PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS


DATE:
APRIL 2012

PROJECT ID:
90-114

SHEET NUMBER:

G-3

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWCS\UPPER ZONE GMZ EXTENT.dwg Tab: FIG 4 User: wulewicz Plotted: Apr 11, 2012 - 10:24 AM




| EXPLANATION | |
|--|--|
| 2012 CONCENTRATIONS OF CHLORIDE (mg/L) | |
| 10/20 | 2012 CONCENTRATION DISSOLVED/TOTAL |
| 10/20 | 2007 CONCENTRATION DISSOLVED/TOTAL |
| 15/16 | 2004 CONCENTRATION DISSOLVED/TOTAL |
| ◆ | NORTH EXPANSION UNIT MONITORING WELL |
| ● | SOUTHERN UNIT MONITORING WELL |
| ⊞ | NORTHERN UNIT GMZ MONITORING WELL |
| — | 2012 ESTIMATED EXTENT OF CHLORIDE EXCEEDENCE |
| — | 2007 ESTIMATED EXTENT OF CHLORIDE EXCEEDENCE |
| — | 2004 ESTIMATED EXTENT OF CHLORIDE EXCEEDENCE |

- NOTES:
- NE = NO EXCEEDENCE
 - SGX = SURFACE WATER COLLECTION POINT
 -
 - HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
 - G37S INACCESSIBLE AT TIME OF SAMPLING FIRST QUARTER 2012.
 - ESTIMATED EXTENT OF EXCEEDENCE IS DASHED WHERE INFERRED DUE TO DRY CONDITIONS AT TIME OF SAMPLING.
 - AGQS FOR DISSOLVED/TOTAL CHLORIDE = 87.51/87.51 mg/L.

| | |
|---|--------------------------------------|
| ANDREWS ENGINEERING, INC. 3300 Ginger Creek Drive, Springfield, IL 62711-7233 Tel (217) 787-2334 Fax (217) 787-9495 Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO | |
| | |
| 1ST QUARTER 2007 CHLORIDE EXCEEDENCES – UPPER ZONE PLANS PREPARED FOR WINNEBAGO LANDFILL | ROCKFORD, WINNEBAGO COUNTY, ILLINOIS |
| DATE: APRIL 2012 | |
| PROJECT ID: 90-114 | |
| SHEET NUMBER: | |
| G-4 | |
| APPROVED BY: JLR | DESIGNED BY: JLR |
| | DRAWN BY: WCU |

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWCS\UPPER ZONE GMZ EXTENT.dwg Tab: FIG 5 User: wulewicz Plotted: Apr 11, 2012 - 10:25 AM



| EXPLANATION | |
|---|---|
| 2012 CONCENTRATIONS OF POTASSIUM (mg/L) | |
| NE | 2012 CONCENTRATION TOTAL |
| 30 | 2007 CONCENTRATION TOTAL |
| 83 | 2004 CONCENTRATION TOTAL |
| ◆ | NORTH EXPANSION UNIT MONITORING WELL |
| ● | SOUTHERN UNIT MONITORING WELL |
| ⊞ | NORTHERN UNIT GMZ MONITORING WELL |
| — | 2012 ESTIMATED EXTENT OF POTASSIUM EXCEEDENCE |
| — | 2007 ESTIMATED EXTENT OF POTASSIUM EXCEEDENCE |
| — | 2004 ESTIMATED EXTENT OF POTASSIUM EXCEEDENCE |

- NOTES:
- NE = NO EXCEEDENCE
 - SGX = SURFACE WATER COLLECTION POINT
 -
 - HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
 - G37S INACCESSIBLE AT TIME OF SAMPLING FIRST QUARTER 2012.
 - ESTIMATED EXTENT OF EXCEEDENCE IS DASHED WHERE INFERRED DUE TO DRY CONDITIONS AT TIME OF SAMPLING.
 - AGQS FOR DISSOLVED/TOTAL POTASSIUM = 29.01 mg/L.

ANDREWS ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

1ST QUARTER 2012 TOTAL
POTASSIUM EXCEEDENCES – UPPER ZONE
PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS

DATE:
APRIL 2012


PROJECT ID:
90-114

SHEET NUMBER:
G-5

APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: WCU

© 2012 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\UPPER ZONE GMZ EXTENT.dwg Tab: FIG 6 User: wulewicz Plotted: Apr 11, 2012 - 10:25 AM



| EXPLANATION | |
|--------------------------------------|--|
| 2012 CONCENTRATIONS OF SODIUM (mg/L) | |
| NE | 2012 CONCENTRATION TOTAL |
| 30 | 2007 CONCENTRATION TOTAL |
| 83 | 2004 CONCENTRATION TOTAL |
| | NORTH EXPANSION UNIT MONITORING WELL |
| | SOUTHERN UNIT MONITORING WELL |
| | NORTHERN UNIT GMZ MONITORING WELL |
| | 2012 ESTIMATED EXTENT OF SODIUM EXCEEDENCE |
| | 2007 ESTIMATED EXTENT OF SODIUM EXCEEDENCE |
| | 2004 ESTIMATED EXTENT OF SODIUM EXCEEDENCE |

- NOTES:
- NE = NO EXCEEDENCE
 - SGX = SURFACE WATER COLLECTION POINT
 -
 - HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
 - G37S INACCESSIBLE AT TIME OF SAMPLING FIRST QUARTER 2012.
 - ESTIMATED EXTENT OF EXCEEDENCE IS DASHED WHERE INFERRED DUE TO DRY CONDITIONS AT TIME OF SAMPLING.
 - AGQS FOR DISSOLVED/TOTAL SODIUM = 164.79 mg/L.

ANDREWS
ENGINEERING, INC.

3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO



1ST QUARTER 2012 TOTAL
SODIUM EXCEEDENCES - UPPER ZONE
PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS


DATE:
APRIL 2012

PROJECT ID:
90-114

SHEET NUMBER:

G-6

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\UPPER ZONE GMZ EXTENT.dwg Tab: FIG 7 User: mnnguyen Plotted: May 01, 2012 - 9:59 AM




| EXPLANATION | |
|---|---|
| 2012 CONCENTRATIONS OF 1,4-DICHLOROBENZENE (µg/L) | |
| NE | 2012 CONCENTRATION |
| 30 | 2007 CONCENTRATION |
| 83 | 2004 CONCENTRATION |
| | NORTH EXPANSION UNIT MONITORING WELL |
| | SOUTHERN UNIT MONITORING WELL |
| | NORTHERN UNIT GMZ MONITORING WELL |
| | 2012 ESTIMATED EXTENT OF 1,4-DICHLOROBENZENE EXCEEDENCE |
| | 2007 ESTIMATED EXTENT OF 1,4-DICHLOROBENZENE EXCEEDENCE |

- NOTES:
- NE = NO EXCEEDENCE
 - SGX = SURFACE WATER COLLECTION POINT
 -
 - HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
 - G37S INACCESSIBLE AT TIME OF SAMPLING FIRST QUARTER 2012.
 - ESTIMATED EXTENT OF EXCEEDENCE IS DASHED WHERE INFERRED DUE TO DRY CONDITIONS AT TIME OF SAMPLING.
 - AGQS FOR 1,4-DICHLOROBENZENE = 5 µg/L.

| | | | | |
|---|--|---|------------------|---------------|
| ANDREWS ENGINEERING, INC. 3300 Ginger Creek Drive, Springfield, IL 62711-7233 Tel (217) 787-2334 Fax (217) 787-9495 Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO | | APPROVED BY: JLR | DESIGNED BY: JLR | DRAWN BY: WCU |
| | | 1ST QUARTER 2012 1,4-DICHLOROBENZENE UPPER ZONE PLANS PREPARED FOR WINNEBAGO LANDFILL ROCKFORD, WINNEBAGO COUNTY, ILLINOIS | | |
| DATE: APRIL 2012 | | PROJECT ID: 90-114 | | |
| SHEET NUMBER: | | G-7 | | |

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\UPPER ZONE GMZ EXTENT.dwg Tab: FIG 8 User: mnguyen Plotted: May 01, 2012 - 10:02 AM



| EXPLANATION | |
|-------------|---|
| | SOUTHERN UNIT MONITORING WELL |
| | NORTHERN UNIT GMZ MONITORING WELL |
| | NORTH EXPANSION UNIT MONITORING WELL |
| | 2012 ESTIMATED EXTENT OF AMMONIA EXCEEDENCE |
| | 2012 ESTIMATED EXTENT OF ARSENIC EXCEEDENCE |
| | 2012 ESTIMATED EXTENT OF BORON EXCEEDENCE |
| | 2012 ESTIMATED EXTENT OF CHLORIDE EXCEEDENCE |
| | 2012 ESTIMATED EXTENT OF POTASSIUM EXCEEDENCE |
| | 2012 ESTIMATED EXTENT OF SODIUM EXCEEDENCE |
| | 2012 ESTIMATED EXTENT OF 1,4-DICHLOROBENZENE EXCEEDENCE |
| N/A | NOT APPLICABLE* |

- NOTES:
1. SGX = SURFACE WATER COLLECTION POINT
 2. * CONCENTRATIONS OF NITRATE WERE DETECTED IN G130 BUT DO NOT APPEAR TO BE ASSOCIATED WITH THE LANDFILL FACILITY AS DEMONSTRATED BY THE LACK OF NITRATE DETECTIONS IN WELLS PROXIMAL TO THE LANDFILL. CONCENTRATIONS IN G130 MAY BE THE RESULT OF AGRICULTURAL LAND-USE TO THE WEST OF THE FACILITY.
 3. HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.


| | | | | |
|--|--|--|------------------|---------------|
| ANDREWS ENGINEERING, INC. 3300 Ginger Creek Drive, Springfield, IL 62711-7233 Tel (217) 787-2334 Fax (217) 787-9495 Pontiac, IL • Indianapolis, IN • Warrenton, MO | | APPROVED BY: JLR | DESIGNED BY: JLR | DRAWN BY: WCU |
| 2012 COMPOSITE EXCEEDENCES – UPPER ZONE | | PLANS PREPARED FOR WINNEBAGO LANDFILL ROCKFORD, WINNEBAGO COUNTY, ILLINOIS | | |
| DATE: APRIL 2012 | | PROJECT ID: 90-114 | | |
| SHEET NUMBER: | | G-8 | | |

© 2012 Andrews Engineering, Inc.

APPENDIX H


Lower Zone Concentration Exceedence Maps

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\GMZ_LOWER_ZONE.dwg Tab: FIG 1 User: wulewicz Plotted: Apr 11, 2012 - 10:27 AM



| | | | | |
|---|--|--|------------------|---------------|
| ANDREWS ENGINEERING, INC. 3300 Ginger Creek Drive, Springfield, IL 62711-7233 Tel (217) 787-2334 Fax (217) 787-9495 Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO | APPROVED BY: JLR | | DESIGNED BY: JLR | DRAWN BY: WCU |
| | 1ST QUARTER 2012 AMMONIA EXCEEDENCES - LOWER ZONE PLANS PREPARED FOR WINNEBAGO LANDFILL ROCKFORD, WINNEBAGO COUNTY, ILLINOIS | | | |
| | DATE: APRIL 2012 PROJECT ID: 90-114 SHEET NUMBER: H-1 | | | |

© 2012 Andrews Engineering, Inc.




NOTES:

1. NE = NO EXCEEDENCE
2. SGX = SURFACE WATER COLLECTION POINT
4. HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
5. G37D INACCESSIBLE AT TIME OF SAMPLING FIRST QUARTER 2012.
6. AGQS FOR DISSOLVED/TOTAL ARSENIC = $2/10 \mu\text{g/L}$.

NOTES:

1. NE = NO EXCEEDENCE
2. SGX = SURFACE WATER COLLECTION POINT
4. HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
5. G37D INACCESSIBLE AT TIME OF SAMPLING FIRST QUARTER 2012.
6. AGQS FOR DISSOLVED/TOTAL ARSENIC = 2/10 $\mu\text{g/L}$.



1ST QUARTER 2012
ARSENIC EXCEEDENCES – LOWER ZONE

PLANS PREPARED FOR WINNEBAGO LANDFILL

DATE:

APRIL 2011

PROJEC

90-114

SHEET NUMBER.

H-2

© 2012 Andrews Engineering, Inc.


APPROVED BY:

DESIGNED BY:

DRAWN BY:

WCU

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\GMZ_LOWER_ZONE.dwg Tab: FIG 3 User: wulewicz Plotted: Apr 11, 2012 - 10:28 AM



| EXPLANATION | |
|-------------------------------------|---|
| 2012 CONCENTRATIONS OF BORON (µg/L) | |
| 10/20 | 2012 CONCENTRATION DISSOLVED/TOTAL |
| 3.5/5.7 | 2007 CONCENTRATION DISSOLVED/TOTAL |
| 4.5/6.7 | 2004 CONCENTRATION DISSOLVED/TOTAL |
| ◆ | NORTH EXPANSION UNIT MONITORING WELL |
| ● | SOUTHERN UNIT MONITORING WELL |
| ⊞ | NORTHERN UNIT GMZ MONITORING WELL |
| — | 2012 ESTIMATED EXTENT OF BORON EXCEEDENCE |
| — | 2007 ESTIMATED EXTENT OF BORON EXCEEDENCE |
| — | 2004 ESTIMATED EXTENT OF BORON EXCEEDENCE |

- NOTES:
- NE = NO EXCEEDENCE
 - SGX = SURFACE WATER COLLECTION POINT
 -
 - HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
 - G37D INACCESSIBLE AT TIME OF SAMPLING FIRST QUARTER 2012.
 - AGQS FOR DISSOLVED/TOTAL BORON = 98/200 µg/L.

ANDREWS ENGINEERING, INC.
3300 Ginger Creek Drive, Springfield, IL 62711-7233
Tel (217) 787-2334 Fax (217) 787-9495
Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO

APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: WCU

1ST QUARTER 2012
BORON EXCEEDENCES – LOWER ZONE
PLANS PREPARED FOR
WINNEBAGO LANDFILL
ROCKFORD, WINNEBAGO COUNTY, ILLINOIS


DATE:
APRIL 2012

PROJECT ID:
90-114

SHEET NUMBER:


H-3

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\GMZ_LOWER_ZONE.dwg Tab: FIG 4 User: wulewicz Plotted: Apr 11, 2012 - 10:28 AM



| | | |
|---|---|---|
| ANDREWS ENGINEERING, INC. 3300 Ginger Creek Drive, Springfield, IL 62711-7233 Tel (217) 787-2334 Fax (217) 787-9495 Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO | 1ST QUARTER 2012 CHLORIDE EXCEEDENCES – LOWER ZONE PLANS PREPARED FOR WINNEBAGO LANDFILL ROCKFORD, WINNEBAGO COUNTY, ILLINOIS | |
| | DATE: APRIL 2012 | PROJECT ID: 90-114 |
| | SHEET NUMBER: H-4 | APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: WCU |

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\GMZ_LOWER_ZONE.dwg Tab: FIG 5 User: wulewicz Plotted: Apr 11, 2012 - 10:29 AM




| EXPLANATION | |
|---------------------------------------|---|
| 2012 CONCENTRATIONS OF NITRATE (mg/L) | |
| 10/20 | 2012 CONCENTRATION DISSOLVED/TOTAL |
| 3.5/5.7 | 2007 CONCENTRATION DISSOLVED/TOTAL |
| 4.5/6.7 | 2004 CONCENTRATION DISSOLVED/TOTAL |
| | NORTH EXPANSION UNIT MONITORING WELL |
| | SOUTHERN UNIT MONITORING WELL |
| | NORTHERN UNIT GMZ MONITORING WELL |
| | 2012 ESTIMATED EXTENT OF NITRATE EXCEEDENCE |
| | 2007 ESTIMATED EXTENT OF NITRATE EXCEEDENCE |
| | 2004 ESTIMATED EXTENT OF NITRATE EXCEEDENCE |

- NOTES:
- NE = NO EXCEEDENCE
 - NS = NOT SAMPLED
 - SGX = SURFACE WATER COLLECTION POINT
 - HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
 - G37D INACCESSIBLE AT TIME OF SAMPLING FIRST QUARTER 2012.
 - AGQS FOR DISSOLVED/TOTAL NITRATE = 11.74/11.74 mg/L.

| | |
|--|---|
| ANDREWS ENGINEERING, INC. 3300 Ginger Creek Drive, Springfield, IL 62711-7233 Tel (217) 787-2334 Fax (217) 787-9495 Pontiac, IL • Indianapolis, IN • Warrenton, MO | |
| | APPROVED BY: JLR DESIGNED BY: JLR DRAWN BY: WCU |
| 1ST QUARTER 2012 NITRATE EXCEEDENCES – LOWER ZONE PLANS PREPARED FOR WINNEBAGO LANDFILL ROCKFORD, WINNEBAGO COUNTY, ILLINOIS | |
| DATE: APRIL 2012 | PROJECT ID: 90-114 |
| SHEET NUMBER: H-5 | |

© 2012 Andrews Engineering, Inc.

File: J:\1990\90-114 (Winnebago)\DWG\K1\2012 GMZ EVAL DWGS\GMZ_LOWER_ZONE.dwg Tab: FIG 6 User: wulewicz Plotted: Apr 11, 2012 - 10:29 AM



| EXPLANATION | |
|-------------|--|
| | SOUTHERN UNIT MONITORING WELL |
| | NORTHERN UNIT GMZ MONITORING WELL |
| | NORTH EXPANSION UNIT MONITORING WELL |
| | 2012 ESTIMATED EXTENT OF AMMONIA EXCEEDENCE |
| | 2012 ESTIMATED EXTENT OF ARSENIC EXCEEDENCE |
| | 2012 ESTIMATED EXTENT OF BORON EXCEEDENCE |
| | 2012 ESTIMATED EXTENT OF CHLORIDE EXCEEDENCE |
| | 2012 ESTIMATED EXTENT OF NITRATE EXCEEDENCE |

- NOTES:
1. DRAWING ONLY DEPICTS CONCENTRATIONS THAT EXCEED THE AGQS.
 2. NE = NO EXCEEDENCE
 3. SGX = SURFACE WATER COLLECTION POINT
 4. HORIZONTAL DATUM BASED ON ILLINOIS STATE PLANE COORDINATE SYSTEM, WEST ZONE, NORTH AMERICAN DATUM, 1927.
 5. ESTIMATED EXTENT OF EXCEEDENCE IS DASHED WHERE INFERRED DUE TO DRY CONDITIONS AT TIME OF SAMPLING.

| | | | | |
|---|--|---|------------------|---------------|
| ANDREWS ENGINEERING, INC. 3300 Ginger Creek Drive, Springfield, IL 62711-7233 Tel (217) 787-2334 Fax (217) 787-9495 Pontiac, IL • Naperville, IL • Indianapolis, IN • Warrenton, MO | | APPROVED BY: JLR | DESIGNED BY: JLR | DRAWN BY: WCU |
| | | 2012 COMPOSITE EXCEEDENCES - LOWER ZONE | | |
| PLANS PREPARED FOR WINNEBAGO LANDFILL | | DATE: APRIL 2012 | | |
| ROCKFORD, WINNEBAGO COUNTY, ILLINOIS | | PROJECT ID: 90-114 | | |
| | | SHEET NUMBER: H-6 | | |

© 2012 Andrews Engineering, Inc.